Key Notes

1. PROVIDE 4' F04 FIXTURE RECESSED VERTICALLY IN WALL WITH TOP OF FIXTURE AT THE CEILING. PROVIDE 2' F04 FIXTURE RECESSED IN CEILING WITH END OF FIXTURE AT WALL IN LINE WITH VERTICALLY MOUNTED FIXTURE.

2. GRAFIK EYE LIGHTING CONTROL PANEL (QS3000).

   PROVIDE 3 ADDITIONAL TYPE F27 FIXTURES WALL MOUNTED IN ELEVATOR HOISTWAY. FIXTURES TO BE SERVED FROM CIRCUIT LSGHA–7 AND SWITCHED IN MACHINE ROOM.

1 Lighting - Ground Floor Plan
SCALE: 1/8"=1'-0"

PLAN NORTH

KEY PLAN

FOR CONSTRUCTION
FULLY SPRINKLERED

Revisions:	Date
5 VAMC Partition Changes	04-15-13
4 Lighting Fixture Modifications	08-30-12
3 Bulkhead Deletion	08-06-12
2 Site and Entrance Area Modifications	03-09-12
1 Amendment #8	11-18-10

CONSULTANTS:

HDR Architecture, Inc.
1101 King Street | Suite 400 | Alexandria, Virginia 22314-2944 | 703.518.8500

ARCHITECT/ENGINEERS:

ARCHITECTURE ENGINEERING INTERIOR DESIGN DESIGN/BUILD ASTORINO
227 Fort Pitt Boulevard Pittsburgh Pennsylvania 15222
TEL 412 765 1700 FAX 412 765 1711 www.astorino.com

Drawing Title: **Lighting Ground Floor Plan**
Approved: Project Director

Project Title: **VA CARES CONSOLIDATION VAMC, PITTSBURGH, PA RESEARCH OFFICE BLDG.**
Location: **VAPHS UNIVERSITY DRIVE**
Date: **08-18-10** Checked: **TMR** Drawn: **DRS**

Project Number: **646CA2500R**
Building Number: **30**
Drawing Number: **REVISED EL1-111**
Dwg: ** of **

Office of Facilities Management
Department of Veterans Affairs

VA FORM 08–6231, OCT 1978

P:\Project\20002227.00\040\Electrical\E211.dwg RDUFFY 04/03/01 - 13:50:14
three inches = one foot | one and one half inches = one foot | one inch = one foot | three quarters inch = one foot | one half inch = one foot | three eighths inch = one foot | one quarter inch = one foot | one eighth inch = one foot