June 4, 2014

## AMENDMENT NO. 4

VA Health Care System Expand Imaging and Lab Fargo, ND Image 1013.14 / VAMC 437-CSI-105

- A. Refer to the SPECIFICATIONS of the above project and make the following additions, corrections, deletions, corrections and/or interpretations.
  - 1. Refer to Specification Section 12 52 00 MODULAR FURNISHINGS: REPLACE section in its entirety with the attached revised Section 12 52 00.
- B. Refer to the DRAWINGS of the above project and make the following additions, corrections, deletions, corrections and/or interpretations.
  - 1. <u>Refer to Drawing Sheet A3, A4 and A5</u>: REVISE Equipment Notes as follows:
    - a. Note 17: 39" High, Powered, Tackable Acoustical-Barrier Panel (CC) Omit under Alternate Bid No. 1.
    - b. Note 18: 62" High, Non-Powered, Tackable Acoustical-Barrier Panel (CC) Omit under Alternate Bid No. 1.
- C. Response to Contractor questions:
  - Question regarding the Modular Component System under 2.1 of the Specification and Plan Equipment Notes Legend Symbols Legend numbers 9 and 10; do these units have shelves on the support frames above the work surface and if so how many shelves? Shelves are not required.
  - 2. Is it possible to get more detail and information on how each single and double-sided casework bench is serviced. Specification Section 123450 calls for plumbing, electrical and data but the drawings do not indicate what services go to each bench. There is also to be ceiling service panels supplying the services to these bench's but no indication what the services are to be. Refer to Reflected Ceiling Plan Sheet A-12, Hex Note No. 9 and 10 for electrical and mechanical service panels. Refer to Sheet P5 for plumbing services; and Sheet E6 for electrical services. Refer to Detail 6/E18 and 7/E18 for required electrical services at ceiling panels located at double sided and single sided workstation support frames.
- D. Attachments:
  - 1. Specification Section 12 64 00 MODULAR FURNISHINGS

END OF AMENDMENT NO. 4