

SECTION 12 64 00
MODULAR FURNISHINGS (DEDUCT ALTERNATE)

PART 1 - GENERAL

1.1 DESCRIPTION

A. This section specifies modular furnishings.

1.2 SUBMITTALS

- A. Material list of all items proposed to be furnished under this section.
- B. Manufacturers catalog cuts and specification data sheets as required to demonstrate conformance with the specification requirements. Where contents of submitted literature from manufacturers includes data not pertinent to the submittal, clearly show which portions of the contents is being submitted for review; including product number, intended options, finishes and fabrics.
- C. Copy of dealers order acknowledgment as required to demonstrate compliance with the specifications.

PART 2 - PRODUCTS

2.1 MODULAR WORKSTATIONS

- A. Manufacturer: Equal to Herman Miller
- B. Product: Action Office System
- C. Size: See plan for size and configuration of panels and/or wall track.
- D. Panels:
 - 1. Types: Series 2
 - a. Tackable Acoustical-Barrier Panel, 39" high, powered.
 - b. Tackable Acoustical-Barrier Panel, 62" high, non-powered.
 - 2. Trim Finish:
 - a. Typical: Soft White, No. LU.
 - b. Director's Suite: Warm Grey Neutral, No. WN.
 - 3. Base Finish: Medium Tone MT.
 - 4. Connector Finish:
 - a. Typical: Soft White, No. LU.
 - b. Director's Suite: Warm Grey Neutral, No. WN.
 - 5. Fabric:
 - a. Typical: Aggregate, Color: Parchment, No. 5E06.
 - b. Director's Suite: Strands, Color: Rye, No. 8W06.
 - 6. Power: 4-circuit power with two (2) duplex receptacles and one (1) data port per side. Power to include normal and emergency power.
 - 7. Refer to Electrical Drawings for locations of data outlets by Electrical Contractor.
- E. Worksurface:
 - 1. Edge Style: Square edge.
 - 2. Laminate:

- a. Typical: Soft White, No. LU.
- b. Director's Suite:
 - 1) Typical: Warm Grey Neutral, No. WN.
 - 2) Transaction: Medium Tone Frosted, No. J7.
- 3. Supports/Wall Track Finish:
 - a. Typical: Soft White, No. LU.
 - b. Director's Suite: Warm Grey Neutral, No. WN.
- 4. Provide c-leg at end worksurfaces.
- 5. Provide wall track at wall-mounted worksurfaces and storage.
- 6. Provide universal post legs and surface ganging brackets at worksurfaces shown not attached to panels or wall strips.
- F. Flipper Door Unit:
 - 1. Style: B style, 16" deep, locking.
 - 2. Finish:
 - a. Typical: Soft White, No. LU.
 - b. Director's Suite: Warm Grey Neutral, No. WN.
 - 3. Tackboard: B style, 16" high, fabric:
 - a. Typical: Aggregate, Color: Parchment, No. 5E06.
 - b. Director's Suite: Strands, Color: Rye, No. 8W06.
 - 4. Task Light: G6150 Standard, Color:
 - a. Typical: Soft White, No. LU.
 - b. Director's Suite: Warm Grey Neutral, No. WN.
 - 5. Lock: Chrome, keyed alike by room or workstation. Provide two (2) keys per lock.
- G. Pencil Drawer:
 - 1. Style: A-Style.
 - 2. Finish: Medium Tone MT.
- H. Keyboard Tray:
 - 1. Style: Thrive Portfolio, Comfort Surface Tray with mouse tray, No. Y7727.2H.
- J. Quantity: See plan.

2.2 FILE STORAGE

- A. Manufacturer: Equal to Herman Miller
- B. Product:
 - 1. Meridian, Bevel-Pull Freestanding Pedestal, File/File, No. F14-1522-FFSST1KAB4NOC.
 - 2. Meridian, Bevel-Pull Freestanding Pedestal, Box/Box/File, No. F14-1522-BBFSST1KAB4NOC, and No. F14-1528-BBFSST1KAB4NOC.
 - 3. Meridian, Bevel-Pull Freestanding Lateral File, 42" wide, 20" deep, 2-drawer, front-to-back filing, NO. 24-4220-2NSST1KAB4CB9P.
 - 4. Meridian, Bevel-Pull Freestanding Lateral File, 42" wide, 20" deep. 4-drawer, front-to-back filing, No. 24-4220-4NSST1KAB4CB9P.

5. Finish:
 - a. Typical: Soft White, No. LU.
 - b. Director's Suite: Warm Grey Neutral, No. WN.
6. Lock: Chrome, keyed alike by room or workstation. Provide two (2) keys per lock.
7. Quantity: See plan.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Deliver furniture to job in manufacturer's original containers with brand name marked thereon.
- B. Unpack and place in scheduled location. Protect products against damage during field handling and installation. Protect adjacent existing and newly placed construction and finishes during installation.
- C. Contractor shall be responsible for any damaged product or adjacent construction.

- - - E N D - - -