

- A. TOP OF SLAB / MAIN FLOOR LEVEL IS ELEVATION 0'-0".
- B. FINISH GRADE SHOWN ON THESE DRAWINGS IS APPROXIMATE. REFER TO CIVIL ENGINEERING AND LANDSCAPE DRAWINGS FOR GRADING, WALKS, DRIVES AND RETAINING WALLS.
- C. REFER TO WINDOW AND DOOR SCHEDULES (DRAWING AE-500S) FOR TYPES AND SIZES.
- D. REFER TO SPECIFICATIONS SECTION 09 06 00 SCHEDULE FOR FINISHES FOR COLOR SELECTIONS.
- E. HORIZONTAL LINES IN EIFS TO BE 1" REPEL SAVED 16" o.c. VERTICALLY. REFER TO ELEVATIONS FOR ALIGNMENT WITH WINDOWS AND WATERTABLE.

**CMU - 1**  
GROUND FACE BLOCK BASE

**MST - 1**  
MANUFACTURED STONE MASONRY VENEER

**CST - 1**  
CAST STONE SILL / WATERTABLE

**MST - 1**  
MANUFACTURED STONE MASONRY VENEER

**CST - 1**  
CAST STONE SILL / WATERTABLE

**EIFS - 1**  
DRAINABLE EIFS

## EIFS - 2

### DRAINABLE EIFS

**CMP - 1**  
COMPOSITE METAL PANELS

**CMP - 2**  
COMPOSITE METAL PANELS  
ON 2" EXTRUDED POLYSTYRENE INSULATION  
REFER TO DETAIL 2/AE-602

**SSM - 1**  
ALUMINUM PRE-FINISHED STANDING SEAM METAL ROOF  
AND METAL FASCIA

**ALUM - 1**  
ALUMINUM BREAK METAL WINDOW TRIM

**ALUM - 2**  
ALUMINUM PRE-FINISHED METAL COPING

**ALUM - 3**  
METAL CONDUCTOR HEADS, SCUPPERS & DOWNSPOUTS

**LVR - 1**  
MECHANICAL LOUVER WITH SCREEN

**PT - 1**  
EXTERIOR PAINT

**PT - 2**  
EXTERIOR PAINT

**EJ - 1**  
EIFS EXPANSION JOINT - 1/2"

**EJ - 2**  
BUILDING EXPANSION JOINT - 1"

**LT - 1**  
LAMBS TONGUE

01/17/2014  
 BID DOCUMENTS  
 FULLY SPRINKLERED

# BID DOCUMENTS FULLY SPRINKLERED

VA FORM 08-6231