

Clarification - Interpretation

Project Name: Phase 1B – SPS / Phase 2A – Warehouse

C-I Number:

Project Number:

To Contractor/CM:

Date of Issuance: 6/13/2014

Regarding: REVISION 1

The Work shall be carried out in accordance with the following, which is consistent with the intent of and reasonably inferable from the Contract Documents, or order minor changes in the Work without change in Contract Sum or Contract Time:

Description:

Phase 1B – SPS

REVISION 1 includes the following changes:

1. The wall along the opposite side of the corridor along "Prep-Pack, Sterile Storage and Staff Admin" has been relocated from 5'-6" to 6'-0" in order to align to the future scope of work for the last remaining project on the ground floor.
2. The temporary construction entry point along that same corridor was relocated to avoid the existing electrical closet.
3. Modifications were made to the proposed Steam and Chilled Water lines to accommodate the change in heating system for Phase 2A. Please see below.

Drawing List:

General:

GI001 COVER SHEET
GI004 PARTIAL GROUND FLOOR INFECTION CONTROL PLAN
GI005 ENLARGED GROUND FLOOR INFECTION CONTROL PARTIAL PLANS

Architecture:

AE112 GROUND FLOOR PARTIAL PLAN PART 02
AE113 GROUND FLOOR PARTIAL PLAN PART 03
AE114 GROUND FLOOR PARTIAL PLAN PART 04
AE192 GROUND FLOOR PARTIAL REFLECTED CEILING PLAN PART 02
AE193 GROUND FLOOR PARTIAL REFLECTED CEILING PLAN PART 03
AE194 GROUND FLOOR PARTIAL REFLECTED CEILING PLAN PART 04
AE912 GROUND FLOOR PARTIAL DEVICE PLAN PART 02

Mechanical:

MH100 MECHANICAL REFERENCE PLAN*
MH110 MECHANICAL GROUND FLOOR PLAN – OVERALL AND PIPING
MH500 MECHANICAL DETAILS
MP501 MECHANICAL DETAILS

*New drawings.

Phase 2A – Warehouse

REVISION 1 includes the following changes:

1. The heating system throughout the Warehouse project was changed from an electric to a steam-to-hot water system. A reverse return piping system was designed for the heating water loop. Steam was provided via Phase 1B. A heat exchanger, pump, and other components were added as well. All previously-scheduled electric heating was converted to heating water with 35% propylene glycol. Controls and Electrical have also been updated accordingly to accommodate this change in system.

2. Two (2) new IT rooms were added with dedicated fan coil units. Both are on emergency power and are tied into a constant source of chilled water via Phase 1B.

Drawing List:

General:

GI0001	COVER SHEET
GI2001	PHASING DIAGRAM

Architecture:

AD1000	PARTIAL GROUND FLOOR DEMOLITION REFERENCE PLAN
AD1001	PARTIAL GROUND FLOOR DEMOLITION PLAN – PART A
AD1002	PARTIAL GROUND FLOOR DEMOLITION PLAN – PART B
AE1000	PARTIAL GROUND FLOOR REFERENCE PLAN
AE1001	PARTIAL GROUND FLOOR PLAN – PART A
AE1002	PARTIAL GROUND FLOOR PLAN – PART B
AE2001	ENLARGED PLANS
AE6001	DOOR SCHEDULE & DETAILS
AE9001	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN – PART A
AE9002	PARTIAL GROUND FLOOR REFLECTED CEILING PLAN – PART B
AG1001	PARTIAL GROUND FLOOR SIGNAGE LOCATION PLAN – PART A
AG1002	PARTIAL GROUND FLOOR SIGNAGE LOCATION PLAN – PART B
AG6001	SIGNAGE MESSAGE SCHEDULE
AG6002	SIGNAGE MESSAGE SCHEDULE (CONTINUED)
AF6001	FINISH SCHEDULE AND FINISH KEY

Mechanical:

MH1001	PARTIAL GROUND FLOOR PLAN - PART A - MECHANICAL
MH1002	PARTIAL GROUND FLOOR PLAN - PART B - MECHANICAL
MH1003	PARTIAL GROUND FLOOR PLAN - PART C – MECHANICAL
MP1001U	PARTIAL GROUND UNDERFLOOR PLAN - PART A – MECHANICAL PIPING*
MP1001	PARTIAL GROUND FLOOR PLAN - PART A – MECHANICAL PIPING*
MP1002	PARTIAL GROUND FLOOR PLAN - PART B – MECHANICAL PIPING*
MP1003	PARTIAL GROUND FLOOR PLAN - PART C – MECHANICAL PIPING*
M5001	MECHANICAL DETAILS
M7001	MECHANICAL SCHEDULES
MI110	MECHANICAL CONTROLS DETAILS
MI111	MECHANICAL CONTROLS DETAILS

Electrical:

E0001	ELECTRICAL SYMBOLS, ABBREVIATIONS
EG5001	ELECTRICAL DETAILS
EY001	SYMBOLS, ABBREVIATIONS, GENERAL NOTES AND DETAILS - SYSTEMS
EY1002	PARTIAL GROUND FLOOR PLAN – PART B - SECURITY
EY1003	PARTIAL GROUND FLOOR PLAN – PART C – SECURITY
ET1001	PARTIAL GROUND FLOOR PLAN - PART A - TELECOMM SYSTEM
ET1002	PARTIAL GROUND FLOOR PLAN - PART B - TELECOMM SYSTEM

Plumbing:

PP1001	GROUND FLOOR PLUMBING PLAN PART A
--------	-----------------------------------

Fire Protection:

FD1001	GROUND FLOOR FIRE PROTECTION DEMOLITION PLAN PART A
FA1002	PARTIAL GROUND FLOOR PLAN -PART B - FIRE DET. & ALARM SYSTEM
FA1003	PARTIAL GROUND FLOOR PLAN -PART C - FIRE DET. & ALARM SYSTEM
FX1001	GROUND FLOOR FIRE PROTECTION PLAN PART A

*New drawings.

CS-10-10-D1 020910

If you believe that a change in Contract Sum or Contract Time is involved, submit written notice within twenty-one (21) days substantiating claim to the Architect. The claim must be made in accordance with the provisions of the Contract Documents. The Owner's authorization is required prior to proceeding to execute any work which will incur additional cost or time.

From Architect/Engineer: HDR Architecture, Inc.

By: _____

DISTRIBUTION: ☐ OWNER ☐ C.M./Contractor ☐ FILE