

STATEMENT OF WORK (SOW)
as of 6/18/2014

1. Contracting Officer's Representative (COR). TBD

2. Contract Title. CLC Phases I & II Televisions

3. Background. Patient Room Televisions and Common Area/Administrative televisions for Phases I & II of new CLC.

4. Scope. Installation of (32) 32" hospital grade televisions with internal DVD Module and remotes for patient rooms and (6) 55" commercial grade televisions with remotes for common and administrative areas of Phases I & II of new CLC in Cincinnati.

5. Specific Tasks. Contractor shall supply specified electronic equipment detailed in below table. All televisions will be installed on tilt-wall mounts by contractor. (32) Patient Room televisions shall have an internal DVD Module and integrate with Dukane ProCare 6000 Nurse Call system so that television can be controlled by residents utilizing their pillow speaker. (6) Common/Administrative Area televisions will be installed by vendor on tilt mount.

1	PDI- P3LCDE- NKP (32) of item 32" HDTV with Remote
2	55LN549E (6) of item 55 HDTV with Remote
3	PD251-002,(32) of item Internal Mounted DVD Module
4	PD 168-003, (32) of item Tilt Wall Mount
5	HCMT-RF,(38) of item RF Jumper , 3'
6	PDI- Jump, (32) of item Pillow Jumper Cable, 1/4"
7	PT660, (6) of item Tilt Wall Mount

5.1 Task 1 – Installation of Televisions

5.1.1 Subtask 1 – Installation Plan and Timeline Contractor shall provide a timeline of project completion from award date, with following milestones: a). delivery, b). installation of (32) patient room televisions, c). installation and programming of (32) patient room television internal DVD modules, d). integration of (32) patient room televisions with nurse call system, e).installation of (6) Common/Administrative Area televisions, f). project completion.

5.1.2 Subtask 2 - Installation Install requested electronic equipment as specified in paragraph 5.

Deliverables: **Installation Plan and Timeline**
 Installation

6. Performance Monitoring Performance will be monitored against provided installation timeline provided in Task 5.1.1. Successful completion of project will be evidenced by successful operation of televisions, internal DVD Modules, and their integration with nurse call system.

7. Security Requirements Not Applicable

8. Government-Furnished Equipment (GFE)/Government-Furnished Information (GFI).

Government will furnish information related to the location of the equipment. Power and nurse call system will be already installed.

9. Other Pertinent Information or Special Considerations. Contractor will need knowledge of integrating televisions into nurse call system.

a. Packaging, Packing and Shipping Instructions. If required, delivery of equipment will be coordinated through Cincinnati VA Receiving Warehouse.

b. Inspection and Acceptance Criteria. Furnished Equipment will be inspected as acceptable by Engineering Department prior to installation.

10. Risk Control Not Applicable

11. Place of Performance. Phase I & II of new CLC currently under construction at the Main Campus of the Cincinnati VAMC.

12. Period of Performance. Performance will start upon award of contract. Installation start expected within 21 days ARO and completion 45 days ARO.