

Date of Addendum: June 20th, 2014
Original Date of Contract Documents: May 21st, 2014
Cannon Project No. 003630.13

Owner

Department of Veteran Affairs
VA NY Harbor Healthcare System
423 East 23rd Street
New York, New York 10010

Architects and Engineers

Cannon Design
2170 Whitehaven Road
Grand Island, New York 14072

This addendum amends Drawings and/or Specifications dated May 21st, 2013 for the above titled project, as indicated below, and is hereby incorporated into the Contract Documents as part thereof.

Attachments:

Specifications: 010000, 028211.01, 028211.02, 089000, 092900

Drawings: 1-1AE117N, 1-1AF001, 1-1AF117N, 1-1AI414, 1-1AI504, 1-1AI520, 1-1AI522, 1-1AE601, 1-1QH117N, 1-1EL108N, 1-1EL601, 1-1EP108N, 1-1TM108N, 1-1TM501 1-PL116N, 1-PL117N, 1-PL604, 1-1PP117N, 1-PP603

Miscellaneous: Medical Equipment Activation List, Patient Lift Cut Sheet

SPECIFICATIONS

The following specifications have been revised and issued as an attachment to this addendum.

1. **010000 General Conditions** – Updated Phasing Description (1.5.H) in response to Bid RFI's.
2. **028211.01 Asbestos Abatement** – Reference to all work being performed during regular business hours was updated as to not contradict with the General Conditions specification.
3. **028211.02 Asbestos Abatement** – Reference to all work being performed during regular business hours was updated as to not contradict with General Condition specification.
4. **089000 Louvers and Vents** – Brick Vents added to specification section.
5. **092900 Gypsum Board** – Scope of work related to bullet resistive fiberglass sheet has been added.

DRAWINGS

ARCHITECTURAL DRAWINGS

1. **1-1AE117N ARCHITECTURAL PLAN 17TH FLOOR – NORTH**
 - A. Wall-mounted sink, recessed paper towel dispenser, and soap dispenser added to the west wall in 17083C.

- B. The stud size of the east wall in 17086C will be changed from 4 7/8" to 8 1/4" to be able to contain plumbing risers.
 - C. The column enclosure in 17094N will be enlarged to fit (2) 4" plumbing risers.
 - D. The column enclosure in 17113N will be enlarged to fit (2) 4" plumbing risers.
 - E. Revise Specific Construction Note 19 for partition assembly at medication room
 - F. Adjust partition thickness at medication room accommodating 1/2" thick bullet proof fiberglass. Adjust related dimensions.
- 2. **1-1AF001 FINISH LEGEND 8TH FLOOR – NORTH, 17TH FLOOR – NORTH AND WEST**
 - A. Revised product number of RB-3. Revised finish W-5 and W-6.
 - 3. **1-1AF117N FINISH PLAN 17TH FLOOR - NORTH**
 - A. Floor finishes are being adjusted next to new partition.
 - 4. **1-1AI414 ENLARGED PLANS & INTERIOR ELEVATIONS 17TH FLOOR – NORTH**
 - A. Wall-mounted sink, recessed paper towel dispenser, and soap dispenser added to the west wall in the Dining Room 17083C.
 - 5. **1-1AI504 INTERIOR DETAILS 17TH – NORTH**
 - A. Added a bullet resistant partition and notes to detail sheet (details B3, B5, B8 and D7)
 - 6. **1-1AI520 MILLWORK DETAILS 8TH FLOOR – NORTH AND 17TH FLOOR – WEST**
 - A. Millwork edges revised from PVC or aluminum edges to plastic laminate edges.
 - 7. **1-1AI522 MILLWORK DETAILS 8TH FLOOR – NORTH**
 - A. Millwork edges revised from PVC or aluminum edges to plastic laminate edges.
 - 8. **1-1AE601 PARTITION SCHEDULE AND DETAILS**
 - A. Revised note included in detail E2 related to partitions at the 17th floor medication room
 - 9. **1-1QH117N ENLARGED EQUIPMENT PLAN – 17TH FLOOR NORTH**
 - A. Coffee Maker K1550.1 and Refrigerator R7250.1 location adjusted to match casework change
 - B. Rm. 17120N: A4015.1 clock has been added.
 - C. Interview 17094N: clock A4015.1 relocated

ELECTRICAL DRAWINGS

- 10. **1-1EL108N ELECTRICAL LIGHTING PLAN – 8TH FLOOR – NORTH**
 - A. Change (5) exit signs from recessed fixture type 'XA1' to surface mounted type 'XA3'.
- 11. **1-1EL601 LUMINAIRE SCHEDULE AND DETAILS**
 - A. Add surface wall mounted exit sign fixture type 'XA3'.
- 12. **1-1EP108N ELECTRICAL POWER PLAN – 8TH FLOOR - NORTH**
 - A. Relocate receptacles for nurse call UPS.

TELECOMMUNICATION DRAWINGS

- 13. **1-1TM108N NURSE CALL PLAN – 8TH FLOOR - NORTH**
 - A. Relocate Nurse Call equipment.

14. 1-1TM501 NURSE CALL DETAILS

- A. Change Nurse Call equipment mounting to single wall mounted rack.
- B. Revise Nurse Call UPS to include 30 min. back-up battery.

PLUMBING DRAWINGS

15. 1-1PL116N PLUMBING SANITARY PLAN – 16TH FLOOR – NORTH

- A. Remove sanitary piping up to the sink in 17th floor South scope.
- B. Add sanitary piping for the temporary sink for 17th floor dining room

16. 1-1PL117N PLUMBING SANITARY PLAN – 17TH FLOOR – NORTH

- A. Remove vent piping to the sink in 17th floor South scope.
- B. Add rough-in to temporary sink for 17th floor dining room

17. 1-1PL604 SANITARY RISER DIAGRAMS – 17TH FLOOR

- A. Revise Stack 54 to comply 16th and 17th floor changes.

18. 1-1PP117N PLUMBING SUPPLY PLAN – 17TH FLOOR - NORTH

- A. Remove water rough-in to the sink in 17th floor South scope.
- B. Add water rough-in to the temporary sink for 17th floor dining room
- C. Add keyed note 12. Capped CW, HW & HWR for future work in 17th floor south.

19. 1-1PP603 WATER RISER DIAGRAMS – 17TH FLOOR

- A. Revise detail E6 to comply 17th floor changes. Added scope of work in the Dining area.

MISCELLANEOUS

The following have been revised and issued as an attachment to this addendum.

1. Activation List

- a. The cut sheet for U0008 Patient Lift has been updated to the Maxi Sky 2 – 600lb. lift
- b. The responsibility code for U0008 has been changed to VC – VA purchased/Contractor installed
- c. The soap dispenser A5075 has been changed to a tamper proof soap dispenser A5075.1 for 17N Room 17083C - Dining

2. Medical Equipment Cut Sheet.

- a. The cut sheet for U0008 Patient Lift is provided

END OF ADDENDUM NO. 1