



4 — 5 — REMOVE THROUGHOUT WORK AREA

**ASBESTOS ABATEMENT KEY:**

1 —	Remove 12"x12" Floor Tile & Mastic	4 —	Remove Radiator Heat Shields (Assumed ACM)
2 —	Remove Piping Insulation	5 —	Remove Fire Door Core (Assumed ACM)
3 —	Remove Sink with Coating		

**PROJECT NOTES**

- 1) Drawing does not show location of all asbestos containing materials (ACM).
- 2) Reference attached asbestos survey report excerpts for additional information on ACM locations. Survey report also contains locations containing non-acm black flooring mastic.
- 3) Contractors bid shall include the removal of all designated ACM located throughout the Work areas.
- 4) Specification quantities include an estimate of thermal system insulation (TSI) expected to be found inside wall/ceiling cavities that requires removal. Contractor shall be responsible for exploratory demolition required to access these areas.
- 5) Materials assumed to contain asbestos will be verified by VPIH / CIH prior to abatement work.

**CONSTRUCTION BID DOCUMENTS  
FULLY SPRINKLERED**

<b>CONSULTANTS:</b>		<b>ARCHITECTS/ENGINEERS:</b>		<b>ARCHITECTURAL PROJECT # 18500</b>		<b>Drawing Title</b>		<b>Project Title</b>		<b>Project Number</b>		<b>Office of Construction and Facilities Management</b>			
						PARTIAL SECOND FLOOR ASBESTOS ABATEMENT PLAN		VA Pittsburgh Healthcare System UD, EXPAND MEDICAL AND SURGICAL CLINICS		646-372					
						Approved: Project Director		Location UNIVERSITY DRIVE DIVISION		Building Number					
ADDENDUM NO. 1 CONSTRUCTION BID DOCUMENTS Revisions		05/30/2014 Date		7850 Freeway Circle 440.243.2000 t		Cleveland, OH 44130 440.243.3305 f		Date 05/06/2014		Checked JJV		Drawn BTH		Drawing Number <b>1-X5</b> Dwg. 5 of 133	