

U.S. DEPARTMENT OF VETERANS AFFAIRS

REQUEST FOR INFORMATION

SOLICITATION NO. VA245-14-B-0083

MANAGED CARE/EMERGENCY DEPT/ENROLLMENT CENTER

PROJECT NO. 512-511

Date Submitted: 6/20/14 RFI # 72

Reference/Subject: PH Exhaust Fans Install

Sec. Section No. / Title _____

Page / Art. / Para. _____

Drawing No.: MH-III

Plan/Detail/Schedule: _____

Request (Explain your request in detail here): Exhaust Fans EF-2, EF-3 & EF-4 are new installations. Can we receive the electric information need for the installation? (Panel board, conduit type in the Penthouse, etc.)

Submitted by (Company Name): TUCKMAN-BARBEE CONSTRUCTION CO., INC. (Person Name): Michelle Clements

VAMHCS Response: _____

Date Received by VAMHCS: _____

Response by: _____

Attachments: _____

A/E Firm Response: _____

A/E Firm Response Date: _____

The wire size for each of the fans is 3#12 + 1#12G in 3/4" conduit. The conduit will be galvanized rigid steel if run exposed. If the conduit is concealed in wall or ceiling space, it shall be EMT. The fans should be connected to available circuits in 480/277V, 3-PHASE Panel in the penthouse.

The electrical data for each new fan is as follows:

EF-2: 0.5Hp/460V/3ph
EF-3: 0.5Hp/460V/3ph
EF-4: 0.5Hp/460V/3ph

This response is based on the drawings dated August 17, 2012 and specifications dated April 27, 2012.

- cVa 7-2-2014

SUBMIT ALL QUESTIONS TO THE CONTRACTING OFFICER BY E-MAIL, NOCHELLE.ELLIOTT@VA.GOV OR BY FAX TO 410-642-1102
PLEASE NOTE DEADLINE FOR RECEIPT OF ALL QUESTIONS IS JUNE 6, 2013 BY 12:00 NOON EST.