

CHF,ACQ & MAT MGT B40017
V.A. Medical Center
REC. WHSE. BLDG 500
1201 BROAD ROCK BLVD.
RICHMOND, VA 23249
PO#: 652-B40017

| Line # | Description | Qty |
|--------|-------------|-----|
|--------|-------------|-----|

| | | |
|---|---------------------------|---|
| 1 | 30Fr/sec Extension | 1 |
|---|---------------------------|---|

Frame Rate Extension increases the system acquisition speed for cardiac applications that require high speed imaging. The frame rate extension increases the acquisition speed to 15fps and 30fps with a 1024x1024 matrix.

| | | |
|---|----------------------------|---|
| 2 | AlluraClarity FD20C | 1 |
|---|----------------------------|---|

The AlluraClarity FD20 (Ceiling) single-plane cardiovascular system comprises a ceiling mounted C-arm stand and digital imaging X-ray system for cardiovascular diagnostic and interventional procedures.

ClarityIQ technology is the foundation of AlluraClarity systems touching every part of the imaging system.

ClarityIQ incorporates powerful state-of-the-art image processing technology, developed by Philips research, all working in real-time enabled by the latest computing technology:-

- Noise and artifact reduction, also on moving structures and objects
- Image enhancement and edge sharpening;
 - Automatic real-time patient and accidental table motion correction on live images.
- Flexible digital imaging pipeline
- ClarityIQ systems have a flexible digital imaging pipeline from tube to display that is tailored for each and every application area such as Cardio or Neuro. This gives the flexibility to select virtually unlimited application-specific configurations.
- With ClarityIQ over 500 system parameters are fine-tuned for each application area; the result of years of Philips clinical leadership. It is now possible to filter out more X-ray radiation, use smaller focal spot sizes, shorter pulses, thereby fully utilizing the unique capabilities of the Philips MRC X-ray tube.

The AlluraClarity FD20 system uses an integrated single-host concept. The system is comprised of five functional building blocks: Geometry, X-ray Generation, Image Detection, Viewing, and User Interface. Each functional building block is explained in further detail including accessories.

GEOMETRY

The AlluraClarity FD20 Stand

The Allura stand consists of a ceiling-mounted C-arm. The stand has the following capability:

- The L-arm can be rotated and can be moved in longitudinal direction allowing a three-sided patient approach and total body coverage.
 - L-arm rotation around the patient table: +90, 0, -90 degrees.
 - L-arm longitudinal movement: 300 cm
 - This movement features auto-stops at the parking position, cardio/neuro position and lower peripheral position.

The Allura stand allows a very wide range of projections, including PA and AP imaging.

- In the head position (0 degrees position, L-arm parallel to patient table):
 - C-arm rotation range (degrees): 120 LAO to 185 RAO
 - C-arm angulation range (degrees): 90 CA to 90 CR
 - (Full angulation capability determined by patient position)
- In the side position (+90 / -90 degrees position, L-arm perpendicular to patient table):
 - C-arm rotation range (degrees): 90 LAO to 90 RAO
 - C-arm angulation range (degrees): 185 CA to 120 CR or 120 CA to 185 CR
 - (Full angulation capability determined by patient position)
- The stand provides fully motorized fast movements with variable and configurable maximum speed.
 - Variable C-arm rotation speed, up to 25 degrees per second
 - Variable C-arm angulation speed, up to 18 degrees per second
- L-arm rotation and longitudinal movement: motorized and manual
- C-arm depth is 90 cm
- The FD20 Dynamic Flat Detector features Xper Access which allows the flat detector to be positioned in either portrait or landscape imaging modes in 3 seconds.
- The variable source image distance between focus and Dynamic Flat Detector input screen is motorized from 86.5 to 123 cm.
- The stand features BodyGuard a capacitive sensing collision avoidance system for patient protection.

Patient support

The Xper Table

Patient support with flat carbon fiber tabletop

- Table top length of 319 cm, width 50 cm
- Metal-free overhang 125 cm
- Floating table-top movement of 120 cm longitudinal and 35 cm transversal range.
- Motorized height adjustment from 74.5 to 102.5 cm
- Maximum cantilever of 223 cm , for full patient coverage
- Maximum patient weight 250 kg plus 500 N for CPR (or 225 kg plus 1000 N) in any longitudinal position of the table top
 - The operating modules can be attached to either side of the table.

Patient Support Accessories set

- One cerebral filter
 - Three rail accessory clamps
 - One IV stand
 - One slow recovery foam mattress
 - One Set of Arm Supports (FCV0248)
 - One Set of Patient Straps (FCV0250)
 - One Head Support (FCV0251)
 - One Arm Support (FCV0258)
 - One Table-mounted Radiation Shield
 - One anti-fatigue mat with Philips logo
-

X-ray Generation

The AlluraClarity FD20 comprises an integrated dedicated X-ray system, micro-processor controlled Velara CFD generator based on high frequency converter technique. The user interface control of this X-ray Generator is incorporated in the Xper module, Xper Desktop Viewing Console, and the Xper on-screen displays.

The Velara CFD generator comprises:

- X-ray generator 100 kW
- Voltage range is 40 - 125 kV
- Maximum current 1250 mA at 80 kV
- Program selection
 - Pulsed X-ray for pulsed fluoroscopy; 3.75, 7.5, 15 and 30 frames/s
 - Pulsed X-ray for (subtracted) acquisition up to 6 frames/s for vascular applications
 - Minimum exposure time of 1 ms
 - Automatic kV and mA control for optimal image quality prior to run to save dose
 - An X-ray depth collimator with two semi-transparent wedged filters with manual and automatic positioning
 - SpectraBeam filtering of low energy radiation to optimize image quality and dose efficiency with MRC-GS 0407 X-ray tube.
 - Grid switching at dynamic pulsed fluoroscopy
 - Xper Beam Shaping, positioning of both shutters and wedges on the Last image Hold without the need for X-ray radiation

Fluoroscopy

- Three programmable fluoroscopy modes
 - Each mode can be set to different composition of dose rate, pulse speed, filter setting, and image processing (noise reduction, adaptive contour enhancement, and adaptive harmonization).
- Roadmap Pro
 - Roadmap Pro can be selected from the Xper imaging module and/or Xper module.
 - A vessel map is created and superimposed with (un)subtracted live fluoroscopy. Acquisition runs can be done during Roadmap without losing the vessel map. Roadmap Pro features Smart Settings in special clinical modes that are optimized to visualize special materials such as coils and glue. Live processing of the vessel map, the device map and the landmark map can be done on the Xper Module. Xres for vascular procedures is standard part of Roadmap Pro.
 - **Disclaimer:** AMC only corrects movement artifacts in two dimensions. Three dimensional movements such as swallowing or rotation of the head cannot be corrected.
 - In Roadmap Pro R2 "Automatic Motion Compensation" (AMC) is added to the roadmap functionality. During roadmap, small movements of the patient can lead to subtraction artifacts. These artifacts might conceal important clinical information. "Automatic Motion Compensation" compensates for rigid, uniform (skeletal/table) translations and is therefore very effective in interventional (neurology) applications where subtraction imaging is applied.
 - **Disclaimer:** AMC only corrects movement artifacts in 2 dimensions. 3 dimensional movements like swallowing or rotation of the head cannot be corrected.

- Xper Fluoro Storage, a grab function allows storage and archiving of both a fluoro image and the last 20 seconds of Fluoroscopy, called Xper Fluoro Storage. These fluoro images or fluoro runs can be archived as a regular exposure run.

X-ray tube

The AlluraClarity FD20 has the Maximus ROTALIX Ceramic grid switch tube assembly MRC 200 GS 0407 integrated in the C-arc. This MRC tube has an anode heat storage capacity of 2.4 MHU and 0.4/0.7 mm. nominal focal spot values. The tube has a maximal loading of 30 and 67 kW. Dynamic pulsed fluoroscopy uses grid switching technology to eliminate soft radiation and improve image quality. SpectraBeam allows for filtration of the x-ray beam with (a combination of) 0.2, 0.5 or 1 mm CU-equivalent filters.

Tube housing ROT-GS 1004 is for oil-cooling and has a build-in thermal safety switch. A rotor control unit is build-in for continuous rotation of the anode disk. The heat exchanger CU 3101 is for direct and continuous forced cooling with oil.

IMAGE DETECTION

The AlluraClarity FD20 comprises the following image detection chain:

- A 30 cm by 40 cm FD20 Dynamic Flat Detector with eight imaging modes.
 - 30 x 38, 30 x 30, 26 x 26, 22 x 22, 19 x 19, 16 x 16, 13.5 x 13.5, and 11 x 11 cm
- The digital output of the FD20 flat detector is 2k*2.5k image matrix at 14 bits depth for the largest mode
- The flat detector subsystem features Xper Access, the detector can be rotated over 90 degrees, it moves from portrait to landscape back & forth
- DQE (Detective Quantum Efficiency) >73 %
- The pixel pitch: 154 x 154 microns

Viewing

AlluraClarity FD20 comprises the following components in order to display the clinical images in the control and examination room:

Displays

Examination Room

Two 18-inch monochrome LCD monitors designed for medical applications. The first display is used for viewing live images. The second display is the reference monitor.

- 18-inch monochrome TFT-LCD display with a 160 degree viewing angle.
- Native format 1280x1024 SXGA
- 10-bit gray-scale resolution with gray-scale correction

These monitors are not delivered when FlexVision XL, EP Cockpit or EP Cockpit XL is selected.

The monitor ceiling suspension in the exam room can be configured to accommodate 3, 4, 6 or 8 LCD monitors and includes motorized height adjustment. The height-adjust feature is dependent on the room ceiling height. When FlexVision XL, EP Cockpit or EP Cockpit XL is selected the monitor ceiling suspension is configured for one of those options.

- Of the two medical monochrome LCD monitors included in the MCS, one is used for viewing of live images and the other serves as the first reference display. Reference images or runs are controlled by infra-red remote-control Xper ViewPad.

- The On-Screen Display provides status information on stand rotation, angulation, display of system messages, X-ray tube load status, selected fluoroscopy mode, selected detector Field of View, and both the rate and accumulation of the dose area product and skin dose. For cardiac applications, the system also monitors and displays body zone specific Air Kerma data (10 zones).

Control Room

One 19-inch color LCD monitor used as a data monitor.

- 19-inch color TFT-LCD display
- Native format 1280x1024 SXGA

One 18-inch monochrome LCD monitor (Xper review monitor) designed for medical applications.

- 18-inch monochrome TFT-LCD display
- Native format 1280x1024 SXGA
- 10-bit gray-scale resolution with gray-scale correction

These control room monitors are not delivered when EP Cockpit or EP Cockpit XL is selected.

The Graphical User Interface on the monochrome monitor has the following features and functions:

- Step through file, run, or images
- File, and run overview
- Contrast, brightness, and edge enhancement settings
- Flagging of runs or images for transfer
- Applying text annotation in images
- Optional DICOM printing
- Executing Quantitative Analysis Packages if available
- Subtraction functionality
- Zoom/pan functionality
- Electronic shutters
- Video invert
- View trace, stacking of images
- Landmarking

Acquisition

The acquisition segment coordinates the parameters for automatic exposure control. The program is selected via the Xper module or Xper Desktop Console.

Exposure techniques:

- Serial imaging for DA and DSA with automatic exposure setting
- Single shot mode
- Acquisition frame rates: 0.5 to 6 images/s at 2048 x 2048, 12-bit matrix
- Frame Rate Extension for 15fps and 30fps with a 1024x1024 matrix.

The AlluraClarity FD20 offers a storage capacity of:

- 50,000 images at matrix size of 1024 x 1024
 - 12,500 images at matrix size of 2048 x 2048
-

- Maximum number of examinations is 999, with no limit to the maximum number of images per examination

USER INTERFACE

Xper is comprised of three elements: 1) Xper Settings, which customizes the system to each user preferred settings. 2) Xper User Interface 3) Xper Integration, which makes advanced integration functionality available such as DICOM Query / Retrieve, background archiving, and Xper Fluoro Storage.

The Xper User Interface uses User Interface modules in the Examination Room with On-Screen Display.

The On-Screen Display is positioned on the left side of the reference monitor. The following system information is displayed

- X-ray indicator and X-ray tube temperature condition
- Gantry position in rotation, angulation, and Source Image Distance
- Detector field size display
- General System messages
- Selected Frame speed
- Fluoroscopy mode
- Integrated fluoroscopy time
- Skin Dose and Dose Area Product
- Stopwatch

The Xper ViewPad contains the preprogrammed function settings. The system is provides with two Xper Viewpads. The following functions are provided:

- Run and image selection
- File and run cycle
- File overview
- Store to Reference image file
- Copy image to photo file
- Digital (fixed) zoom and panning
- Recall reference images
- Laser pointer, intended to point at regions of interest on the imaging monitors
 - LED indication of laser pointer on/off and battery low
- Subtraction on/off
- Remasking
- Landmarking

Remote Intercom

The separate intercom which is connected independently from the system that allows separate placement of the intercom at the preferred working position in the control room and examination room.

Table Side Modules

Two Xper Modules are provided for use. The first Xper Module is mounted tableside. The Second Xper Module (NCVA778) is located in the control room. These modules use a touch screen, which can be operated when draped with sterile covers. The Xper Module contains the following functionality:

- Acquisition settings
-

- Selection of Xper Setting allows the user to set frame rates and X-ray generation settings applicable for the type of the preferred intervention
- Image Processing

The Xper Geometry module can be positioned on all sides of the patient table, while keeping the button operation intuitive. The Xper Geometry module provides the following functionality :

- Tabletop float and table height position
- Source Image Distance selection
- Longitudinal movement of the Gantry along the ceiling
- Gantry rotation in an axis perpendicular to the ceiling
- Store and recall of two scratch gantry positions including SID
- Emergency stop button

The Xper Imaging module can also be positioned on three sides of the patient table, while keeping the button operation intuitive. The Xper Imaging module provides the following functionality:

- Fluoroscopy Flavor selection defined per Xper Setting
- Shutters and Wedge positioning
- Xper Fluoro Storage and Grab
- Selection of the Detector field size
- Shutter positioning
- Reset of the fluoroscopy buzzer

Pan Handle (NCVA081)

The Pan Handle is an extension of the control facility for floating movements of the tabletop.

Control Room

The control room comprises a Xper Review Module, Xper Desktop Module, a keyboard, and a mouse. The Xper Review Module offers the basic functions for review. The Xper Review Module contains the following functionality:

- Power on/off
- Tagarno wheel to control the review of a patient file
- File and run cycle
- Contrast, Brightness, and Edge enhancement settings
- File, Run, Image stepping and run and file overview
- Delete run
- Image invert and digital zoom
- Reset fluoroscopy timer and enable/disable X-ray

System information is displayed on the bottom of the data monitor:

- Stopwatch and Time
 - System guidance information
 - Dose Area Product (DAP) and Skin Dose, and accumulative dose
 - Frame speed settings, fluoroscopy mode, and accumulated fluoroscopy time
 - Exposure and fluoroscopy settings as Voltage (kV), Current (mA) and pulse time (ms)
-

- Geometry information as rotation, angulation, and SID

Scheduling

The patients can be listed and selected per date, physician, and intervention type. Previous DICOM patient studies can be uploaded with the DICOM Query Retrieve function in the Allura system.

Patient management protocols are flexible and allow for multiple studies to be selected under one patient identification number. This means that new studies can be appended to an earlier patient file. Furthermore, each study can contain multiple examinations to allow for split administrative purposes. Each examination contains multiple files, like acquisition file, reference file, and QA results file.

Preparation

The preparation page provides the information of the room and patient preparation of each individual physician. The preparation page is customizable per Xper Setting and allows each physician to provide his own room protocols. This preparation page makes hard copies of the protocol instructions redundant.

Acquisition

The acquisition page contains information on the current selected patient.

Review

The review page allows for reviewing of patients:

- Previous examination cases
- Review of other DICOM XA or DICOM SC studies

Radiation Dose Structured Report

Collection of dose relevant parameters and settings and export to a DICOM database (e.g. PACS, RIS), according IEC60601-2-43, 2nd Edition.

The reported data can be used for, for example:

- Quality improvement: evaluating trends in X-ray dose performance per facility, system and operator.
- RDSR enables analysis of average dose levels & variance for routinely performed exams and procedures.
- Typical system usage can be extracted from the data.

Archive

Continuous Autopush (NCVA090)

Continuous Autopush is an archive accelerator, which ensures that background archiving continues with minimal disruptions.

Clinical studies can be archived to a CD or a PACS. The archive process can be completely automated and customized with Xper Settings. Parameters like multiple destinations, archive formats can be selected to the individual needs and wishes for programming under the Xper Settings,

The Xper DICOM Image Interface enables the export of clinical images to PACS. The export formats are based on DICOM 3.0 protocols. The system exports clinical studies in Cardiac DICOM XA Multi-Frame or DICOM Secondary Capture formats.

- The export format is configurable in 512x512, 1024x1024 2048 x 2048 (unprocessed) matrix.
- The examination can be sent to multiple destinations for archiving and reviewing purposes.
- The Xper DICOM Image Interface provides DICOM Storage and DICOM Storage Commitment Services.
- The DICOM Query/Retrieve function allows older DICOM XA MF and DICOM SC studies to be uploaded in the system. Furthermore, additional information can be appended to a study, while keeping the patient identification the same.

Remote Service

Access to the system from a Remote location is possible via network or modem connection. Remote access to a system can shorten the time needed for e.g. changing system settings or problem diagnosis.

Clinical Education Program for the Allura Xper System

Essentials OffSite Education: Philips will provide up to two (2) Cardiovascular Technologists, Registered Technologists Registered Nurses, or other system operator as selected by customer, with in-depth didactic, tutorial, and hands-on training covering basic functionality and work-flow of the cardiovascular imaging system. In order to provide trainees with the ability to apply all fundamental functioning on their system, and to achieve maximum effectiveness, this class should be attended no earlier than two weeks prior to system installation.

In the event that an EP Navigator workstation has also been ordered, the offsite training course will be tailored to focus on the electrophysiology functionality of the FD system and the EPN workstation.

In the event that your main FD system will be dedicated to Cardiac applications your offsite training course will be tailored to focus on the Cardiac functionality.

This twenty-eight (28) hour class is located in Cleveland, Ohio, and is scheduled based on your equipment configuration and availability. Due to program updates, the number of class hours is subject to change without notice. Customer will be notified of current, total class hours at the time of registration. This class is a prerequisite to your equipment handover OnSite Education. CEU credits may be available for each participant that meets the guidelines provided by Philips. Please refer to guidelines for more information. **Travel and lodging are not included, but may be purchased through Philips. It is highly recommended that 989801292102 (CV Full Travel Pkg OffSite) is purchased with all OffSite courses.**

Handover OnSite Education: Philips Education Specialists will provide twenty-eight (28) hours of education for up to four (4) students, selected by customer, including technologists from night/weekend shifts if necessary. Students should attend all 28 hours, and must include the two OffSite education attendees. CEU credits may be available for each participant that meets the guidelines provided by Philips. Please refer to guidelines for more information. Note: Site must be patient-ready. Philips personnel are not responsible for actual patient contact or operation of equipment during education sessions except to demonstrate proper equipment operation. **It is highly recommended for systems that are fully loaded or for customers with a large number of staff members to also purchase 989801292099 (CV Add OnSite Clin Educ 24h).** Education expires one (1) year from equipment installation date (or purchase date if sold separately). Ref #106107-110915

FlexVision XL is an integrated viewing solution designed to give you full control over your viewing environment.

The FlexVision XL provides the ability to:

- Display 2 to 8 screens simultaneously from up to 16 sources (incl. third party systems) on the Philips 56-inch color LCD in the Exam Room.
- Resize and/or enlarge information at any stage during the case.
- Select and customize viewing lay-outs of the Philips 56-inch color LCD via the Xper table-side module

XperHD on FlexVision XL brings High Definition viewing for clinical images. Native resolution of FD20 can be displayed. Excellent sharp and crisp clinical images can be displayed at full size without digital zoom.

Xper HD brings:

- High Definition imaging
 - Sharp images at full size without zoom
- High Definition display at native resolution
 - Up to 2k*2k image display fully integrated
- High Definition for the ultimate detail
 - Enhanced small vessel visualization
- Overview connected equipment (incl. third party systems) from a single location.

The FlexVision XL consists of:

- OmniSwitch
 - OmniSwitch allows the user to direct and switch the video output of all connected medical equipment to specific sub windows of the Philips 56-inch color LCD in the Exam Room.
 - OmniSwitch is a 16 channel video-switch operated from the Xper tableside module. 16 channels are available for a mix of up to 7 internal and up to 9 external inputs.
 - OmniSwitch supports a wide variety of display formats (up to 1600x1200).
 - External inputs are connected to OmniSwitch via Wall Connection box(es).
- Medical grade, high resolution color LCD in the Exam Room
 - This display supports the image quality requirements for monochrome X-ray images as well as color images and replaces all displays normally delivered with an Allura Xper FD system for the Exam Room.
 - Main characteristics are:
 - 56 inch, 8 Megapixel color LCD
 - Native resolution: 3840x2160
 - Brightness: Max: 450 Cd/m2 (typical) stabilized: 350 Cd/m2
 - Contrast ratio: 1200:1 (typical)
 - Wide viewing angle (approx. 176 degrees)
 - Constant brightness stabilization control
 - Lookup tables for gray-scale, color and DICOM transfer function
 - Full protective screen
 - Ingress Protection: IP-21
- Large color LCD control (Xper Module)
 - Resize and/or enlarge information at any stage during the case via the Xper tableside module in the Exam or Control Room
 - Select viewing lay-outs via the Xper table-side module in the Exam Room

- Create new layouts by matching inputs to desired locations on preset templates. Monitor Ceiling Suspension
- Monitor ceiling suspension for use in the Exam Room carries the 56 inch color LCD, providing highly flexible viewing capabilities. The monitor ceiling suspension is height-adjustable and moveable along ceiling rails. It can be positioned on either side of the table.
- Isolated Wall Connection Boxes
 - Up to 8 Isolated Wall Connection Boxes can be connected to FlexVision XL.
 - Through Isolated Wall Connection Boxes, 3rd party equipment can be connected to the FlexVision Omniswitch.
- Snapshot
 - The snapshot function allows the user to store/save a screen-capture of any image on the 56" display as a DICOM Secondary Capture image to a connected PACS. The snapshot-all function allows the user to store/save a screen-capture for each displayed image in the Exam Room / Control Room as separate DICOM Secondary Capture images.

4

RIS / CIS DICOM interface

1

This package allows communication of the Allura Xper system with a local information system (CIS or RIS). The interface uses the DICOM Worklist Management (DICOM WLM) and Modality Performed Procedure Step (DICOM MPPS) standards.

If a hospital has an Allura Xper system and an information system it can receive patient and examination request information from the information system and report examination results in order to:

- Eliminate the need for retyping patient information on the Allura Xper
- Prevent errors in typing patient names and registration numbers (ensuring consistency with IS information to prevent problems in archive clusters or to search for a name in case of later retrieval)
- Inform the IS about the acquired images and radiation dose

Upon request from the Allura Xper system the complete worklist with all relevant patient and examination data is returned from the IS to the Allura Xper system. For each patient the following information will be shown on the Allura Xper after it has been retrieved from the IS:

Patient Identification:

- Patient name
- Patient ID
- Birth date
- Sex

Examination/Request Information:

- Accession number
- Scheduled procedure step start time
- Scheduled performing physician's name

It is possible at all times to enter patient demographics information manually within the Allura Xper system in case of an emergency or in case the local Information System connection is down.

On request of the clinical user the Allura Xper will report the following information about the

selected patient to the IS:

Patient Identification:

- Patient name
- Patient ID
- Birth date
- Sex

Examination/Request Information:

- Accession number
- Performed procedure step status start/end date and time
- Performing physician's name
- Referenced image sequence

Radiation dose:

- Total time of fluoroscopy
- Accumulated fluoroscopy dose
- Accumulated exposure dose
- Total dose
- Total number of exposures
- Total number of frames

Further detailed information can be found in the Allura Xper DICOM Conformance Statement.

The interface requires an EasyLink (hardware and software) if the IS is not compliant with DICOM Work List Management and Modality Performed Procedure Step.

| | | | |
|---|---|---|--|
| 5 | Standard Line Rate Video Output | 1 | This interface provides image output to standard line rate video peripherals, such as VCRs or paper printers. This option also comprises automatic start and stop of a VCR, synchronous to the generation of X-ray (fluoroscopy and exposures). |
| 6 | Lab Reporting | 1 | Lab Reporting allows the user to generate and print simple reports in modality stand-alone situations. The user is able to incorporate free text and clinical images. The reporting functionality is suited for local printing and email. Part of the report is generated automatically from administrative data (e.g. patient/exam data hospital name) and required data (e.g. run-log dose information and event-log). |
| 7 | Dicom Print compose | 1 | Dicom Print provides the possibility to interface to any DICOM Printer. This is an automated printing protocol. The option provides Print Manual Overrides, Print Job submission, and Print Job management. |
| 8 | Automatic Position Control (APC) | 1 | |

The Automatic Position Controller (APC) for Integris Allura Flat Detector systems provides two modes of operation:

- Preset Position Sequence; the sequence of projections is determined per Xper Settings. Each set contains a maximum of 10 positions. Positions can be recalled in sequence or directly. The projection sequence comprises rotation, angulation, and SID settings, related to the selected reference image.
- Reference driven positioning. The projections on the reference monitors can be recalled with the push of a button. The reference driven positioning recollects the rotation, angulation, and SID.

9

Table APC

1

The Automatic Position Controller (APC) for the table provides two modes of operation:

- Auto positioning. The tabletop position and table height will be adjusted automatically to the pre-defined default point of interest. This to save time and x-ray dose at the start of an exam or for setting up the system for rotation scans.
- Store/recall of a position of the table top. This includes the height-, longitudinal- and lateral position of the table top.

10

FD Rotational Angio

1

Rotational angiography provides real-time 3D impressions of complex vasculature and coronary artery tree. It acquires multiple projections with just one contrast injection via a fast rotational scan of the region of interest.

Rotational Angiography can be used during screening procedures to quickly determine the optimal projection for the study as the angle (rotation/angulation) of the projection is indicated on each image.

Compared with traditional angiography, Rotational Angiography can save considerable time, dose and contrast, while providing image detail required for diagnostic and therapeutic decisions.

A rotational scan is possible both with the Allura Xper systems in the side position (ceiling mounted systems) and in the head position, providing the flexibility to perform procedures virtually from head to toe.

C-arm in side position:

- Max. rotation Speed: 30 degrees/s
- Max. rotation Angle: 180 degrees

C-arm in head position:

- Max. rotation Speed: 55 degrees/s
- Max. rotation Angle: 305 degrees

Max. Frame speeds are given by the framespeed specifications of the system configuration.

The speed and range of rotation are the highest available (see table). The very high speed allows using less contrast, whereas the very wide rotation range provides a complete evaluation of the anatomy.

A contrast run can be followed up with a mask run, to allow image/run subtraction.

The stand is designed for a very high mechanical stability. It offers precise positioning and high reproducibility, assuring you of high quality images and excellent subtraction studies.

Operation of Rotational Angiography is extremely easy. The procedure is selected, set up and executed virtually in a matter of seconds, supporting the highest patient throughput.

A set of dedicated acquisition programs is available on the Xper Module and can be selected at the touch of a button. The rotation end- and start-positions are easily selected. The procedure is controlled from the exposure hand- or footswitch.

| | | |
|-----------|-------------------|----------|
| 11 | Xper Swing | 1 |
|-----------|-------------------|----------|

XperSwing allows dual-axis rotational coronary angiography to gather more information in less time and with less X-ray and contrast dose. XperSwing acquires simultaneous RAO/LAO cranial-caudal views in just one acquisition run by moving the C-arm in a curved trajectory instead of multiple acquisitions. XperSwing can be used during screening procedures to quickly determine the optimal projection for the study as the angle (rotation/angulation) of the projection is indicated on each image, providing image detail required for diagnostic and therapeutic decisions and to obtain a real-time 3D impression of the coronary artery tree.

In total seven pre-programmed trajectories are available:

- Three for Left coronary imaging
- Two for Right Coronary imaging,
- Two generic trajectories.

The choice depends on size and weight of the patient. These trajectories are designed to fully cover all conventional projections for a diagnostic coronary angiography. Rotation and angulation movements are combined in one complete scan trajectory, using the maximum rotation and angulation speed of the Allura Xper system. (55 resp 30 degr/sec). XperSwing is possible in the side position (ceiling mounted systems) and in the head position

XperSwing functionality includes, but is not limited to

- 15 frames per seconds acquisition to allows using of less contrast.
- Wide rotation range provides a complete evaluation of the anatomy.
- Precise positioning and high reproducibility, assuring you of high quality images and excellent subtraction studies.
- Set up and executed in a matter of seconds.
- Set of dedicated acquisition programs with the trajectories available on the Xper Module
- The rotation end- and start-positions can be selected.
- Acquisition procedure is controlled from the exposure hand or footswitch.

| | | |
|-----------|-------------------------------|----------|
| 12 | Subtracted Bolus Chase | 1 |
|-----------|-------------------------------|----------|

For visualization of vessel structures when the blood flow is difficult to estimate, in particular in the lower peripherals.

Bolus Chase solves the problem of cumbersome step movements, the mismatch between blood flow and selected program, and lack of real-time image information.

During digital acquisition in non-subtracted mode with uninterrupted real-time image display, the contrast bolus is followed (chased) interactively by a motorized table scan movement using a hand-hold speedcontroller to adapt the speed of the table scan to the contrast flow. The framespeed can be adapted as well.

The bolus run is followed with a mask run while using the same speedcurve and framespeed as generated during the bolus run. Viewing is possible in the subtracted and non-subtracted mode. If subtracted viewing is not required, the mask run can be skipped.

Subtracted Bolus Chase gives fast, accurate results for increased patient throughput and improved patient management. Automated exposure control and precise speed control assure a high quality images and excellent subtraction studies.

Comprising:

- automatic exposure control
- tabletop motordrive and hand-held speed controller (tableside)
- technique selection using Xper module, available both tableside and in control room (Xper FD20, FD20/10)

| | | |
|-----------|--------------------------|----------|
| 13 | Storage extension | 1 |
| | Storage extension | |

Storage extension provides an increased storage capacity for

Allura Xper FD20 systems the storage is increased from:

- 50.000 to 100.000 images at 1024x1024 matrix
- 12.500 to 25.000 images at 2048x2048 matrix

Allura Centron system the storage is increased from:

- 50.000 to 100.000 images at 1024x1024 matrix

Power requirements:
refer to system configuration

| | | |
|-----------|---|----------|
| 14 | Ventricular Quant.Sw pkg(Xper) | 1 |
|-----------|---|----------|

Left Ventricular Quantification Software Package. Software package for the analysis of single plane Left ventricular angiograms. Calculates the Ejection fraction and local wall motion parameters in different formats.

Functions:

- Various LV-volumes
- Ejection Fraction
- Cardiac Output
- Centerline Wall Motion
- Slager Wall Motion
- Regional Wall Motion
- Calibration routines

In addition the package allows manual measurements of line lengths (absolute and ratio's) and angulations. Multiple measurements in one image are possible.

Comprising:

- software license

Compatible with:

- . Allura Xper FD 10 Rel 3 and FD10/10 Rel 2 onwards
- . Allura Xper FD20 Rel 2, FD20/10 Rel 2 onwards

15 **Coronary Quant.Sw pkg(Xper)** 1

Functions:

- diameter measurement along the selected segment
- cross sectional area
- %-stenosis
- pressure gradient values
- stenotic flow reserve
- calibration routines

In addition the package allows manual measurements of line lengths (absolute and ratio's) and angulations. Multiple measurements in one image are possible.

Comprising:

- software license

Compatible with:

- . Allura Xper FD 10 Rel 3 and FD10/10 Rel 2 onwards
- . Allura Xper FD20 Rel 2, FD20/10 Rel 2 onwards

16 **Vascular Quant.Sw pkg(Xper)** 1

Functions:

- vessel diameter / stenotic index
- automated vessel analysis
- calibration routines

In addition the package allows manual measurements of line lengths (absolute and ratio's) and angulations. Multiple measurements in one image are possible.

Compatible with:

- Allura Xper FD10 Rel 3 and FD10/10 Rel 2 onwards
- Allura Xper FD20 Rel 2 and FD20/10 Rel 2 onwards
- Allura CV20 R1 onwards

17 **Wireless footswitch: mono-plane version** 1

The wireless footswitch is an option for our Allura systems. It provides the possibility to have one wireless footswitch in the exam room.

A wireless footswitch provides workflow optimization, flexibility at table-side, removes cable clutter on the floor and provides easier cleaning of the footswitch.

The mono-plane wireless footswitch is a 3 pedal version; one pedal for fluoroscopy, one for exposure and one to control the roomlight/single shot. The pedals can be configured according customers preferred lay-out.

The wireless footswitch is working via RF technology and is fully tested and released for medical use. It has an active range up to 10 meters, depending on structures within this range.

The wireless footswitch has a lithium battery which only needs to be recharged once per week. During recharging the footswitch still can be used and is fully functional. In parallel, a wired footswitch can also be used.

The status of the battery is indicated by an LED-indication on the footswitch itself, so that the user can decide when the footswitch needs to be recharged.

The wireless footswitch can easily be cleaned in water. It has the highest water ingress protection standard (IPX8).

The wireless footswitch has an on/off switch. It can be switched off when not in use. When the footswitch is active, but not in use, it will go into a sleep-mode. It will be re-activated when touched or when one of the pedals is pressed.

- | | | |
|-----------|--|----------|
| 18 | Peripheral X-ray Filter | 1 |
| | Set of flexible x-ray filters to provide an uniform density in angiographic examinations of the lower peripheral area. | |
| | Comprising: | |
| | <ul style="list-style-type: none">· one central filter, at the top edge provided with sizing markers at every 5 cm, length : 1 m· two side filters, length: 1 m | |

- | | | |
|-----------|--|----------|
| 19 | Pivot for table base. | 1 |
| | For angiographic- and interventional procedures of the upper peripherals. | |
| | Provides improved table access for patient transfer. | |
| | Allows pivoting of the table base around its vertical axes. | |
| | Pivot range from -90 degrees to + 180 degrees (or -180 to +90 degrees) with locked positions on 0, -13/+13 (facilitating arm-angiography) and -90/+90 and 180 degrees. | |
| | Comprising: | |
| | <ul style="list-style-type: none">• pivot device with graduated scale to be mounted on the universal floor plate of the table. | |

Compatible with Xper Table

- | | | |
|-----------|--|----------|
| 20 | Xper Table Tilt | 1 |
| | This innovating SyncraTilt enhances the accuracy and efficiency of gravity-oriented procedures. It is available as an option for the Xper table in Allura Xper series systems. | |

SyncraTilt is ideal for interventional, myelography, phlebography and head down procedures because it provides more precise imaging of contrast medium, blood, or objects in the body.

With SyncraTilt, the isocentre is automatically located at the isocentre of rotation and angulation of the stand. If the longitudinal position of the stand changes, the tilt isocentre is changed to match with the new stand position. As a result, the region of interest is always centred

As the table tilts, the X-ray beam automatically coordinates to the movement.

The table floats even when tilted, and the region of interest can be followed by panning the tabletop.

When combined with the Bolus Chase option, SyncraTilt enables phlebography to be performed with a head-up tilted patient.

The option provides:

- maximum tilt range:
- 17 degrees (head down) to +17 degrees (head up).
- tilt speed: 2 degrees/sec
- automatic safeguarding system with manual override
- panning range in tilted plane: equal to the standard
- tabletop specifications (longitudinal 120cm, lateral 35cm)
- easy to use controls
Comprising:
 - Tilt drive with user controls

Compatible with:

- . Xper table in Allura Xper FD series Rel 3 onwards (monoplane versions) and Rel 2 onwards (biplane versions)
- . Bolus Chase
- . Pivot for table base
- . swivel for table base

| | | | |
|----|---|----|---|
| 21 | Airfare to Cleveland for Biomed Training | 1 | Includes one (1) participant's airfare from North American customer location to the Cleveland Training Center (CTC) in Cleveland, Ohio. All other expenses will be the responsibility of the attendee. Details are provided during the scheduling process. Note: Cancellation/rescheduling policy strictly enforced. Expires one (1) year from the earlier of equipment delivery date or purchase date. |
| 22 | Food Transpt Lodging for Cleveland Biomed Training | 14 | Includes one (1) day of modest lodging, ground transportation, and meal expenses in Cleveland, Ohio for one (1) attendee. All other expenses will be the responsibility of the attendee. Details are provided during the scheduling process. Note: Cancellation/rescheduling policy strictly enforced. Although this part is only for one day, it is sold in multiple quantities to account for entire length of course. Expires one (1) year from the earlier of equipment delivery date or purchase date. |
| 23 | XD3970ALLURAFD7.6PART1C TC9 | 1 | Course Number: XD3970 System Codes: 722010, 722011, 722012, 722013 Course Title: Allura Xper Rel 7.6 Part 1 Course Length: 9 days (exclude Saturday, Sunday, and Philips holiday) Delivery Method(s): Instructor-Led Modality: iXR Location: PHC, SLC, CTC Target Audience: Service Engineers. DESCRIPTION: Part 1 trains the Customer Support engineer to a technical level which will enable him/her to |

perform Planned Maintenance (PM) and basic Corrective Maintenance (CM) on Allura Xper systems, according to the Customer Support philosophy. He / She will also be able to assist during a system installation.

Part 1 can be followed up by part 2, intended for dedicated Cardio Vascular modality Engineers. Part 2 focuses on setting to work (configuration) and extended Corrective Maintenance.

The following Allura Xper systems are covered:

FD10 release 7.6

FD10/10 release 7.6

FD20 release 7.6

FD20/10 release 7.6

FD20/20 release 7.6

PREREQUISITES:

CS9020 BASIC NETWORKING

XC3002 X-RAY SYSTEMS BASIC PART 2

COURSE OBJECTIVES:

The engineer will learn how to:

- Operate the system, as far as required to perform service tasks.
- Make use of the service documentation.
- Make use of basic functionality of the service tools.
- Perform Planned Maintenance:
 - Safety checks
 - Performance checks
 - Adjustments(Not included: Mechanical checks)
- Create a backup of the system.
- Perform a restore of the system.
- Perform basic CM with help of the service documentation and service tools.
 - Faultfinding using the System Manual Corrective Maintenance.
 - Focus on replacement of parts with a high exchange rate.
 - Retrieve the log file from the system to escalate a problem.
- Customize positions for Automatic Position Control in the EPX-database.

MAJOR TOPICS:

Introduction Allura Xper systems

Operating

Service documentation

Service tools

Planned Maintenance

Corrective Maintenance

System Architecture

X-ray generation

Geometry

Operator controls

Power supply

Imaging

System control

Radiation safety

Image quality

Customization

Software

* PHILIPS PROPRIETARY MATERIALS SUCH AS DIAGNOSTIC SOFTWARE AND SERVICE DOCUMENTATION ARE NOT INCLUDED IN THE TRAINING AND WILL NOT BE AVAILABLE FOR USE OUTSIDE OF THE TRAINING ENVIRONMENT. THE TRAINEE MUST RETURN ALL PROPRIETARY MATERIALS RECEIVED DURING THE TRAINING AT THE END OF THE TRAINING. CUSTOMER ACKNOWLEDGES AND AGREES THAT NEITHER CUSTOMER NOR

TRAINEE WILL RECEIVE A LICENSE TO SUCH PROPRIETARY MATERIALS AND THAT THE TRAINEE MAY NOT BE ABLE TO FULLY UTILIZE THE TRAINING WITHOUT THE USE OF SUCH PROPRIETARY MATERIALS. (CERTAIN LICENSES MAY BE OBTAINED THROUGH PURCHASE OF AN ALLIANCE CO; OP AGREEMENT.) Course dates and location to be finalized by Philips. Philips shall attempt to accommodate Customer requested dates and training location. The price quoted includes course tuition. Travel and living expenses are not included, but may be purchased separately through Philips.

IMPORTANT Notes Regarding Admission to Philips Customer Engineer Training Courses:

1. Trainee must meet all prerequisites
2. Course expires one (1) year from equipment installation date (or purchase date if sold separately)
3. Customer must sign Philips Nondisclosure statement
4. Trainee must sign Philips Nondisclosure statement
5. Customer must sign Philips terms and conditions of training

24

**XD3974ALLURAXPERREL7.6P
ART2CTC9**

1

Course Number: XD3974
System Codes: 722010, 722011, 722012, 722013
Course Title: Allura Xper Rel 7.6 Part 2
Course Length: 9 days
Delivery Method(s): Instructor-Led
Modality: iXR
Location: PHC, SLC
Target Audience: Service Engineers.

DESCRIPTION:

This course is a follow up on the Allura Xper Part 1 course and is intended for modality Engineers that specialize in Cardio Vascular.

3 months Field experience on Allura Xper systems is strongly recommended before attending this part 2 course, this means the engineer has done some installation, pm- and cm visits.

In part 2 the customer support engineer is trained to a technical level which will enable him/her to perform setting to work and extended corrective maintenance on Allura Xper systems, according the customer support philosophy.

Not covered are the Mechanical Installation and Cabling of the Allura Xper System.
These topics are covered in the e-learning: Allura Xper Mechanical Installation.

The following Allura Xper systems are covered:

FD10 release 7.6
FD10/10 release 7.6
FD20 release 7.6
FD20/10 release 7.6
FD20/20 release 7.6

PREREQUISITES:

- XD3866 or XD3966 or XD3970

COURSE OBJECTIVES:

For Allura Xper systems, the engineer will learn how to:

Perform the setting to work, including:

Setting to work of Dicom Store and Storage Commit from Allura towards an Xcelera PACS as well as Setting To Work of the CWIS option towards an Xcelera and/or Hemodynamic system Xper Flex Cardio.

Customizing of common parameters of the Xper database.

Distinguish technical problems from incorrect operating.

Perform extended corrective maintenance; with help of analytical trouble shooting, service documentation and service tools.

Perform a Dicom traffic capture file, with help of the DVTK program (Dicom Network Analyzer), as part of the connectivity Fault Isolation Procedure for analyzing and if needed sending to helpdesk Image quality faultfinding using lower level IQ measurements.

25 Rad Shield w/ Arm (Contoured) 1
61X76

Contoured Rad Shield with Arm rest. 61X76

26 Exam Lamp 220v 1

Spring arm mounted examination light for cardiovascular applications

27 Portegra 2 360 Ceiling Column 1

Portegra 2 360 Column w/ trolley and ceiling track

28 Mark 7 Arterion, Table Mount 1

The Mark 7 Arterion Injection System is the latest in MEDRAD's "Mark" series of angiographic injectors. Compared to earlier systems, the Mark 7 Arterion injector head is lighter and easier to use so you can focus more on the patient.

The clear and intuitive user interface guides you through proper set-up, and highlights the information you need to perform safe procedures.

Unique to the market, the front load system simplifies set-up and makes for a cleaner tear down.

The clear syringe provides a higher level of confidence that you are ready to inject.

Made from a clear material, the Mark 7 Arterion syringe (Catalog ART 700 SYR) allows you to easily view the inside of the syringe for smoother purging of air. And MEDRAD's famous fluid dots are still there to help-round for fluid, oval for air.

The table mount injector solution ensures the contrast injector is conveniently placed and always available when it is needed. It provides a clean workspace without occupying valuable floor space.

System includes:

- Table Mount
- display control panel
- 6 ft. coiled hand switch
- operation manual (CD)
- 10 ft. head cable
- syringe heat maintainer
- imaging system interface cable for the Allura / Allura Xper
- consumables starters kit

For the MEDRAD Mark7 Injector system Philips is only the distributor. MEDRAD provides the service as well as the application support of both versions unless stated differently in the Philips Service Agreement

System Specifications:

- Flow Rate 0.1-45.0 ml/s in 0.1 ml increments
- 0.1-59.9 ml/m in 0.1 ml increments
- Volume 1-150 ml in 1 ml increments
- Pressure Limit 100-1200 psi in 1 psi increments
- (150ml syringe) 689-8273 kPa in 1 kPa increments
- Rise Time 0.0-9.9 seconds in 0.1 increments
- Delay Time 0.0-99.9 seconds in 0.1 increments
- Fill Speed 1-20 ml/s
- Fill Volume 1-150 ml
- Syringe Size 150 ml
- Syringe Heat Maintainer 35 °C (95 °F) ± 5 °C (9 °F)
- Protocol Memory 40 Protocols
- Injection Memory History

29

FlexVision XL 8 Input Package

1

The FlexVision XL8 input package provides eight isolated wall connection boxes and eight legacy converters.

Isolated Wall Connection Box

This Isolated Wall connection Box facilitates connection of the video source via standard DVI cable/connector and lossless transfer of the video signal over the approximate 30 m cable distance. It can be mounted in the exam room or in the control room, depending on the location of the video source.

The quantity of the VWCB's has to be calculated as follows:

For each video signal to FlexVision XL on Vascular System: 8 VWCB

Note:

No VWCB is required in case a video signal is connected directly to a dedicated LCD from the following sources:

- 1) Xper Live/ref Slaving
- 2) Interventional HW (XtraVision), ViewForum, Xcelera (only if workstations are powered by Allura Xper)
- 3) Xper IM

Legacy Video Convertor

The Legacy Video Convertor enables conversion from VGA towards DVI for supported input resolutions as listed in the table below.

| Signal type | Native resolution | Image Aspect Ratio |
|-------------|-------------------|--------------------|
|-------------|-------------------|--------------------|

| | | |
|-----|---------|-----|
| VGA | 640x480 | 4:3 |
|-----|---------|-----|

| | | |
|------|---------|-----|
| SVGA | 800x600 | 4:3 |
|------|---------|-----|

| | | |
|-----|----------|-----|
| XGA | 1024x768 | 4:3 |
|-----|----------|-----|

| | | |
|------|-----------|-----|
| SXGA | 1280x1024 | 5:4 |
|------|-----------|-----|

| | | |
|-------|-----------|-----|
| SXGA+ | 1400x1050 | 4:3 |
|-------|-----------|-----|

| | | |
|------|-----------|-----|
| UXGA | 1600x1200 | 4:3 |
|------|-----------|-----|

| | | |
|------|----------|-------------|
| WXGA | 1280x800 | 16:10 (8:5) |
|------|----------|-------------|

| | | |
|-------|----------|-------------|
| WSXGA | 1440x900 | 16:10 (8:5) |
|-------|----------|-------------|

WSXGA+ 1680x1050 16:10 (8:5)
WUXGA 1920x1200 16:10 (8:5)
2K 2048x1080 19:10
TV1080I/P 1920x1080 16:9
TV 480I 720x480 4:3
TV 480P 704x480 4:3

| | | |
|-----------|-------------------------------|----------|
| 30 | Universal Power Supply | 1 |
| | UNIVERSAL POWER SUPPLY | |