

Bldg	Location	No. of Doors	Push Bars or Device Needed	Door Hardware	Key	Notes	Door Hardware Required
2	Credit Union and Side Door	1	1	1 Set	New 7 Pin	For single aluminum door, remove existing hardware and install new exit devices and door hardware	(1) Corbin-Russwin Exit Device ED4200-03 W039 M52 x P1057-03 US32D; (1) Rim Cylinder 3030-058 x 422F88 US32D
Corr	Corr. From Bldg 2 to Bldg 3	1	1	1 Set	New 7 Pin	For single aluminum door, remove existing hardware and install new exit devices and door hardware	(1) Corbin-Russwin Exit Device ED4200-03 W042 M52 x P1057-03 US10B; (1) Rim Cylinder 3030-058 x 422F88 US10B
38	Patio Exit and connecting corridor from Bldg 135	1	1	1 Set	New 7 Pin	Replace aluminum door, hardware, and frame; patch and repair adjoining interior wall surface - minimum paint repair; remove and dispose existing transom unit	(1) Corbin-Russwin ED5470-08 M52 x L955 US32D RHR; (1) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (1) Rim Cylinder 3030-058 x 422DF88 US32D; (1) 3'0" x 7'0" Wide Stile Door with 8" midrail glass to be 1/4" tempered; Continuous hinges - Clear Aluminum
39	Loading Dock Areas and Main Entrance	3	3	3 Sets	New 7 Pin	adjust and repair door hardware on 3 Aluminum doors,	(1) Sargent Cylinder Dogging Kit 816 F 32D; (2) Corbin-Russwin Cylinder Dogging Kit 653F12 US32D; (3) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (1) 644 Rim Exit Strike
39	Connecting Corr to Bldg 46	1	1	1 Set	New 7 Pin	Existing metal door; replace door hardware; remove existing mortise lock - repair and fill door as required; install new exit device	(1) Corbin-Russwin Exit Device ED5200SA-08 x L955 US10; (1) Rim Cylinder 3030-058 x 422DF88 US32D;
46	Main connecting corridor doors to chapel from tunnel from Bldg 1	4	4	2 Sets	New 7 Pin	(Two sets of doors are operated by push plate); Remove existing deadlock and flush bolts	(2) Corbin-Russwin ED5470-08 M52 x L955 US10B RHR; (2) Corbin-Russwin ED5470-02 M52 x L950 US10B LHR; (4) Mortise Cylinder 1037-114-A02 x 270F15 US10B; (2) Rim Cylinder 3030-058 x 422DF88 US10B
46	Chapel connecting corridor	2	2	2 Sets	New 7 Pin	Two aluminum side exit doors; Replace existing hardware	(2) Corbin-Russwin ED4200-03 W044 M52 x P1057-03 US32D; (2) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (2) Rim Cylinder 3030-058 x 422DF88 US32D

46	Chapel interior exit door, after sliding doors	1		1 Set	New 7 Pin	44" Wood Door; Remove dead lock and push pull hardware	(1) Corbin-Russwin ED5200S-08 W044 M52 x L955 US10; (1) Mortise Cylinder 1037-114-A02 x 270F15 US10; (1) Rim Cylinder 3030-058 x 422DF88 US10; (1) Closer DC6210 M54 691 (mounted for 180 degree operation)
46	Main Entrance, Chapel Doors	2		1 Set	New 7 Pin	chapel main entrance; remove doors and replace with VA-provided door and sidelights. Install framing around door.	VA-provided door hardware. To be installed by contractor along with door, sidelights, and framing.
46	Side exits in chapel	2	2	2 Sets	New 7 Pin	Two aluminum doors; remove existing hardware and replace with new	(2) Corbin-Russwin ED4200-03 W044 M52 x P1057-03 US32D; (2) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (2) Rim Cylinder 3030-058 x 422DF88 US32D
61	Loading Dock Areas and Connecting Corr to Bldg 4/HBPC	4	4	4 Sets	New 7 Pin	Remove existing hardware and install new exit devices and door hardware	(4) Corbin-Russwin Exit Device ED4200-03 W048 M52 x P1057-03 US32D; (4) Rim Cylinder 3030-058 x 422F88 US32D
61	East Side (Main Courtyard)	4		4 Sets	New 7 Pin	Two pairs of metal doors plus door hardware; Patch and repair existing metal doors; remove dead locks and flush bolts;	(2) Corbin-Russwin ED5470-08 M52 x L955 US32D RHR; (2) Corbin-Russwin ED5470-02 M52 x L950 US32D LHR; (4) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (2) Rim Cylinder 3030-058 x 422DF88 US32D
61	West Side - Center Corr.	2		2 Sets	New 7 Pin	Remove existing door hardware and install new door hardware for existing doors	(1) Corbin-Russwin ED5470-08 M52 x L955 US32D RHR; (1) Corbin-Russwin ED5470-02 M52 x L950 US32D LHR; (2) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (1) Rim Cylinder 3030-058 x 422DF88 US32D
135	Connecting Corr. From Bldg 38	1	1	1 Set	New 7 Pin	Includes patch and repair existing door	(1) Corbin-Russwin ED5470-08 W042 H096 M52 x L955 US32D RHR; (1) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (1) Rim Cylinder 3030-058 x 422DF88 US32D
137	Loading Dock Area	1 Double Door	2	2 Sets	New 7 Pin	Patch and repair existing metal metal doors	(1) Corbin-Russwin ED5470-08 W048 H090 M52 x L955 US32D RHR; (1) Corbin-Russwin ED5470-02 W048 H090 M52 x L950 US32D LHR; (2) Mortise Cylinder 1037-114-A02 x 270F15 US32D; (1) Rim Cylinder 3030-058 x 422DF88 US32D

137	Northeast Stairwell Exit	1	1	1 Set	New 7 Pin	Remove and replace existing door hardware	(1) Corbin-Russwin ED4200-03 M52 x P1057-03 US10; (1) Mortise Cylinder 1037-114-A02 x 270F15 US10; (1) Rim Cylinder 3030-058 x 422DF88 US10
-----	--------------------------	---	---	-------	--------------	--	---

NOTES: 1. Contractor shall verify material quantities before ordering/procuring any materials.  
2. Field verify all existing doors and locations in above schedule.  
3. Unless otherwise noted, all doors on schedule are to have hardware replaced on them  
with specified door hardware.