ROOM FINISH SCHEDULE - PAGE 2 OF 3

ROOM NO	ROOM NAME	FINISH FLOOR	FINISH BASE	FINISH WALL	FINISH CEILING	NOTES
Level 2						
2E09	STAIR 2	RF	RB	GWB	GWB	
2E10	GROUP	CPT	RB	GWB / FWP	AT-1	
2E11	MECH SHAFT	-	-	EXP	-	
2E12	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
2E18	RECP	CPT	RB	GWB / FWP	AT-5	
2E19	OFF	CPT	RB	GWB	AT-1	
2E20	OFF	CPT	RB	GWB	AT-1	
2E21	ELEC	EPY	RB	GWB	EXP	
2E22	OFF	CPT	RB	GWB	AT-1	
2E23	OFF	CPT	RB	GWB	AT-1	
2E24	WAIT	CPT	RB	GWB	AT-3	
2E25	OFF	CPT	RB	GWB	AT-1	
2E27	OFF	CPT	RB	GWB	AT-1	
2E28	OFF	CPT	RB	GWB	AT-1	
2E29	OFF	CPT	RB	GWB	AT-1	
2E30	GROUP	CPT	RB	GWB / FWP	AT-1	
2E30A	STOR	LN	RB	GWB	AT-1	
2E33	TLT	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
2E35	TLT	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
2E36	HAC	QT	QT	GWB(SC) / CT	GWB	4'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND EPOXY PAINT FINISH ABOVE, 5"x6" COVE BASE
2E37	OFF	CPT	RB	GWB	AT-1	
2E38	ELEC	EPY	RB	GWB	EXP	
2E39	OFF	CPT	RB	GWB	AT-1	
2E41	OFF	CPT	RB	GWB	AT-1	
2E43	OFF	CPT	RB	GWB	AT-1	
2E44	IDF	EPY	RB	GWB	EXP	
2E45	OFF	CPT	RB	GWB	AT-1	
2E46	SIGNAL	EPY	RB	GWB	EXP	
2E47	OFF	CPT	RB	GWB	AT-1	
2E48	OFF	CPT	RB	GWB	AT-1	
2E49	OFF	CPT	RB	GWB	AT-1	
2E50	OFF	CPT	RB	GWB	AT-1	
2E51	OFF	CPT	RB	GWB	AT-1	
2E52	OFF	CPT	RB	GWB	AT-1	
2E53	OFF	CPT	RB	GWB	AT-1	
2E54	OFF	CPT	RB	GWB	AT-1	
2E55	OFF	CPT	RB	GWB	AT-1	
2E56	OFF	CPT	RB	GWB	AT-1	
2E57	OFF	CPT	RB	GWB	AT-1	
2E58	OFF	CPT	RB	GWB	AT-1	
2E59	OFF	CPT	RB	GWB	AT-1	
2E60	ELEC	EPY	RB	GWB	EXP	
2E61	OFF	CPT	RB	GWB	AT-1	
2E63	CHIEF	CPT	RB	GWB	AT-1	
2E64	OFF	CPT	RB	GWB	AT-1	
2E65	OFF	CPT	RB	GWB	AT-1	
2E66	OFF	CPT	RB	GWB	AT-1	
2E67	OFF	CPT	RB	GWB	AT-1	
2E68	OFF	CPT	RB	GWB	AT-1	
2E69	OFF	CPT	RB	GWB (W) 1	AT-1	
2E70	OFF	CPT	RB	GWB	AT-1	
2E71	RN	LN	ICB	GWB	AT-1	SEMI GLOSS PAINT FINISH AT PLUMBING FIXTURE WALL ONLY
2E71A	WORKROOM	LN	ICB	GWB	AT-1	SEMI GLOSS PAINT FINISH AT PLUMBING FIXTURE WALL ONLY
2E72	COMM	LN	RB	GWB	AT-1	
2E73	ELEC	EPY	RB	GWB	EXP	
2E75	RN	LN	ICB	GWB	AT-1	SEMI GLOSS PAINT FINISH AT PLUMBING FIXTURE WALL ONLY
2E76	EDUCATION	CPT	RB	GWB / FWP	AT-1	
2E78	INTV	CPT	RB	GWB / FWP	AT-1	
2E79	STAIR 3	RF	RB	GWB	GWB	
2E80	DAY	CPT	RB	GWB / FWP	AT-1	
2E80A	QUIET	CPT	RB	GWB / FWP	AT-1	
2E80B	TRAINING KIT.	LN	RB	GWB	AT-1	SEMI GLOSS PAINT FINISH AT PLUMBING FIXTURE WALL ONLY
2E86	GROUP	CPT	RB	GWB / FWP	AT-1	
2E90	OT	LN	RB	GWB / FWP	AT-1	SEMI GLOSS PAINT FINISH AT PLUMBING FIXTURE WALL ONLY
2E92	TOILET	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
2E96	TOILET	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
2H10	HALLWAY	TER	TER	PWT / WDW	AT-2 / AT-6	
2H20	HALLWAY	LN	RB	GWB	AT-3	
2H30	HALLWAY	LN	RB	W / GWB (W) 1	AT-3	
2H40	HALLWAY	LN / CPT	RB	GWB / W (WDW) 1	AT-3	
2H60	HALLWAY	LN	RB	GWB	AT-3	
2H70	HALLWAY	LN	RB	W / GWB	AT-3	
2H80	HALLWAY	LN	RB	GWB	AT-3	
2H90	HALLWAY	TER	TER	WDW	AT-2	
2W04	ELEVATOR LOBBY	PT	PT	FWP / W	GWB / AT-5	
2W07	10 CUBICLES	CPT	RB	GWB (W) 1	AT-1	
2W07A	RECP	PT	PT	WDW	AT-8	
2W08	TOILET	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
2W09	WORK	LN	RB	GWB	AT-1	
2W09A	ELEC	EPY	RB	GWB	EXP	
2W10	GROUP	CPT	RB	GWB / FWP	AT-1	
2W14	PHAR OFF.	CPT	RB	GWB (W) 1	AT-1	
2W15	GROUP	CPT	RB	GWB / FWP	AT-1	
2W16	STOR	LN	RB	GWB	AT-1	
2W17	GROUP	CPT	RB	GWB / FWP	AT-1	
2W19	GROUP	CPT	RB	GWB / FWP	AT-1	
2W21	GROUP	CPT	RB	GWB / FWP	AT-1	
2W24	WAIT	TER	TER	PWT / WDW	AT-2 / AT-6	
2W25	GROUP	CPT	RB	W / FWP (GWB) 1	AT-1	
2W25A	STOR	LN	RB	GWB	AT-1	
2W27	STAIR 1	RF	RB	GWB	GWB	
2W28	MECH SHAFT	-	-	EXP	-	
2W29	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
2W30	OFF	CPT	RB	GWB	AT-1	
2W31	OFF	CPT	RB	GWB	AT-1	
2W32	OFF	CPT	RB	GWB	AT-1	
2W33	OFF	CPT	RB	GWB	AT-1	
2W34	OFF	CPT	RB	GWB	AT-1	
2W35	OFF	CPT	RB	GWB	AT-1	
2W36	ELEC	EPY	RB	GWB	EXP	
2W37	OFF	CPT	RB	GWB	AT-1	
2W38	OFF	CPT	RB	GWB	AT-1	
2W39	OFF	CPT	RB	GWB	AT-1	
2W40	OFF	CPT	RB	GWB	AT-1	
2W41	OFF	CPT	RB	GWB	AT-1	
2W42	OFF	CPT	RB	GWB	AT-1	
2W43	OFF	CPT	RB	GWB	AT-1	
2W44	OFF	CPT	RB	GWB	AT-1	
2W45	CHIEF	CPT	RB	GWB	AT-1	
2W46	ELEC	EPY	RB	GWB	EXP	
2W47	OFF	CPT	RB	GWB	AT-1	
2W49	OFF	CPT	RB	GWB	AT-1	
2W50	OFF	CPT	RB	GWB	AT-1	
2W51	OFF	CPT	RB	GWB	AT-1	
2W52	OFF	CPT	RB	GWB	AT-1	
2W53	OFF	CPT	RB	GWB	AT-1	
2W54	OFF	CPT	RB	GWB	AT-1	
2W55	OFF	CPT	RB	GWB	AT-1	
2W56	OFF	CPT	RB	GWB	AT-1	
2W57	OFF	CPT	RB	GWB	AT-1	

ROOM FINISH SCHEDULE - PAGE 2 OF 3

ROOM NO	ROOM NAME	FINISH FLOOR	FINISH BASE	FINISH WALL	FINISH CEILING	NOTES
2W58	OFF	CPT	RB	GWB	AT-1	
2W59	OFF	CPT	RB	GWB	AT-1	
2W60	ELEC	EPY	RB	GWB	EXP	
2W61	OFF	CPT	RB	GWB	AT-1	
2W63	OFF	CPT	RB	GWB	AT-1	
2W64	IDF	EPY	RB	GWB	EXP	
2W65	OFF	CPT	RB	GWB	AT-1	
2W66	SIGNAL	EPY	RB	GWB	EXP	
2W67	OFF	CPT	RB	GWB	AT-1	
2W69	CHIEF	CPT	RB	GWB	AT-1	
2W70	LOUNGE	PT	PT	GWB / FWP / CT	AT-3	
2W72	LOUNGE	PT	PT	GWB / FWP / CT	AT-3	
2W75	WORK	LN	RB	GWB	AT-1	
2W76	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
2W78	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
2W80	OFF	CPT	RB	GWB	AT-1	
2W82	OFF	CPT	RB	GWB	AT-1	
2W84	OFF	CPT	RB	GWB	AT-1	
2W85	CONF	CPT	RB	GWB / FWP	AT-1	
2W86	OFF	CPT	RB	GWB	AT-1	
2W87	GROUP	CPT	RB	GWB / FWP	AT-1	
2W88	ELEC	EPY	RB	GWB	EXP	
2W89	GROUP	CPT	RB	GWB / FWP	AT-1	
2W90	OFF	CPT	RB	GWB	AT-1	
2W91	WAIT	CPT	RB	W	AT-3	
2W92	OFF	CPT	RB	GWB	AT-1	
2W94	FAM. TLT.	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
2W95	HAC	QT	QT	GWB(SC) / CT	GWB	4'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND EPOXY PAINT FINISH ABOVE, 5"x6" COVE BASE
2W96	TOILET	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
2W97	MECH SHAFT	-	-	EXP	-	
Level 3						
3E08	RECP	CPT	RB	FWP	AT-5	
3E09	STAIR 2	RF	RB	GWB	GWB	
3E10	WAIT	CPT	RB	FWP / GWB	AT-5	
3E11	MECH SHAFT	-	-	EXP	-	
3E12	TEAM	CPT	RB	GWB / FWP	AT-1	
3E13	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
3E15	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
3E17	INT	CPT	RB	GWB / FWP	AT-1	
3E18	WORKROOM	LN	RB	GWB	AT-1	
3E19	INT	CPT	RB	GWB / FWP	AT-1	
3E20	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E21	OFF	CPT	RB	GWB	AT-1	
3E22	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E23	ELEC	EPY	RB	GWB	EXP	
3E24	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E25	OFF	CPT	RB	GWB	AT-1	
3E26	C UTIL	LN	ICB	GWB(SC)	GWB(SC)	EPOXY PAINT FINISH
3E27	OFF	CPT	RB	GWB	AT-1	
3E28	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E29	MICRO	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E30	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E32	EXAM	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E33	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
3E34	PHYSIO	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3E35	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
3E36	STOR	LN	RB	GWB	AT-1	
3E37	ADMIN	CPT	RB	GWB	AT-1	
3E38	ELEC	EPY	RB	GWB	EXP	
3E39	OFF	CPT	RB	GWB	AT-1	
3E41	OFF	CPT	RB	GWB	AT-1	
3E43	OFF	CPT	RB	GWB	AT-1	
3E44	IDF	EPY	RB	GWB	EXP	
3E45	OFF	CPT	RB	GWB	AT-1	
3E46	SIGNAL	EPY	RB	GWB	EXP	
3E47	OFF	CPT	RB	GWB	AT-1	
3E49	OFF	CPT	RB	GWB	AT-1	
3E50	STOR	LN	RB	GWB	AT-1	
3E51	OFF	CPT	RB	GWB	AT-1	
3E53	OFF	CPT	RB	GWB	AT-1	
3E54	WORK	LN	RB	GWB	AT-1	
3E55	OFF	CPT	RB	GWB	AT-1	
3E56	TEAMROOM (6)	CPT	RB	GWB (W) 1	AT-1	
3E57	OFF	CPT	RB	GWB	AT-1	
3E59	OFF	CPT	RB	GWB	AT-1	
3E60	ELEC	EPY	RB	GWB	EXP	
3E61	ADMIN	CPT	RB	GWB	AT-1	
3E62	OFF	CPT	RB	GWB	AT-1	
3E63	ADMIN	CPT	RB	GWB	AT-1	
3E64	TEAMROOM (6)	CPT	RB	GWB	AT-1	
3E65	OFF	CPT	RB	GWB	AT-1	
3E66	STOR	LN	RB	GWB	AT-1	
3E67	OFF	CPT	RB	GWB	AT-1	
3E68	HAC	QT	QT	GWB(SC) / CT	GWB	4'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND EPOXY PAINT FINISH ABOVE, 5"x6" COVE BASE
3E69	OFF	CPT	RB	GWB	AT-1	
3E71	OFF	CPT	RB	GWB	AT-1	
3E73	OFF	CPT	RB	GWB	AT-1	
3E74	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
3E75	OFF	CPT	RB	GWB	AT-1	
3E76	TLT	PT	CT	CT / GWB	GWB	5'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND SEMI GLOSS PAINT FINISH ABOVE, 3"x6" COVE BASE
3E78	ELEC	EPY	RB	GWB	EXP	
3E79	STAIR 3	RF	RB	GWB	GWB	
3E80	TEAMROOM (6)	CPT	RB	GWB (W) 1	AT-1	
3E80A	OFF	CPT	RB	GWB	AT-1	
3E80B	OFF	CPT	RB	GWB	AT-1	
3E80C	OFF	CPT	RB	GWB	AT-1	
3E90	TEAMROOM (6)	CPT	RB	GWB	AT-1	
3E90A	OFF	CPT	RB	GWB	AT-1	
3E90B	OFF	CPT	RB	GWB	AT-1	
3E90C	OFF	CPT	RB	GWB	AT-1	
3H10	HALLWAY	TER	TER	PWT / WDW	AT-2	
3H20	HALLWAY	LN	RB	GWB	AT-3	
3H30	HALLWAY	LN	RB	W / GWB	AT-3	
3H40	HALLWAY	TER	TER	GWB / PWT	GWB	
3H60	HALLWAY	LN	RB	GWB / W	AT-3	
3H65	HALLWAY	LN	RB	GWB	AT-3	
3H70	HALLWAY	LN	RB	W / GWB	AT-3	
3H80	HALLWAY	LN	RB	GWB	AT-3	
3H90	HALLWAY	TER	TER	WDW	AT-2	

ROOM FINISH SCHEDULE - PAGE 2 OF 3

ROOM NO	ROOM NAME	FINISH FLOOR	FINISH BASE	FINISH WALL	FINISH CEILING	NOTES
3W03	CONF	CPT	RB	GWB / FWP	AT-1	
3W04	ELEVATOR LOBBY	PT	PT	FWP / W	GWB / AT-5	
3W04A	AUTOCLAVE	LN	ICB	GWB(SC)	GWB(SC)	EPOXY PAINT FINISH
3W05	CONF	CPT	RB	GWB / FWP	AT-1	
3W06	ELEC	EPY	RB	GWB	EXP	
3W07	ELEC	EPY	RB	GWB	EXP	
3W07A	ELEC	EPY	RB	GWB	EXP	
3W07B	ELEC	EPY	RB	GWB	EXP	
3W08	CHEM	SEC	RB	GWB(SC)	EXP	EPOXY PAINT FINISH
3W09	LAB 5	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W09A	LAB 6	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W09B	EQUIP	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W10	DNA	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W11	TISSUE CULT	LN	ICB	GWB(SC)	AT-7	EPOXY PAINT FINISH
3W13	TISSUE CULT	LN	ICB	GWB(SC)	AT-7	EPOXY PAINT FINISH
3W15	LN2	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W17	MICRO	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W19	MICRO	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W20	EQUIP	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W21	LAB 3	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W21A	LAB 4	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W21B	EQUIP	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W22	DARK	LN	ICB	GWB / S	AT-1	VERTICAL SOLID SURFACE AND SEMI GLOSS PAINT FINISH ABOVE AT PLUMBING FIXTURE WALL
3W23	ELEC	EPY	RB	GWB	EXP	
3W23A	ELEC	EPY	RB	GWB	EXP	
3W24	LOUNGE	TER	TER	FWP / WDW / W 1	AT-2	
3W25	LAB 2	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W25A	LAB 1	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W25B	EQUIP	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W28	MECH SHAFT	-	-	EXP	-	
3W29	KIT	LN	RB	GWB	AT-1	SEMI GLOSS PAINT FINISH AT PLUMBING FIXTURE WALL ONLY
3W30	STOR	LN	RB	GWB	AT-1	
3W31	OFF	CPT	RB	GWB	AT-1	
3W32	ELEC	EPY	RB	GWB	EXP	
3W33	OFF	CPT	RB	GWB	AT-1	
3W35	OFF	CPT	RB	GWB	AT-1	
3W37	OFF	CPT	RB	GWB	AT-1	
3W39	OFF	CPT	RB	GWB	AT-1	
3W40	COPY	LN	RB	GWB / W	AT-1	
3W41	OFF	CPT	RB	GWB	AT-1	
3W42	OFF	CPT	RB	GWB	AT-1	
3W43	OFF	CPT	RB	GWB	AT-1	
3W45	OFF	CPT	RB	GWB	AT-1	
3W46	ELEC	EPY	RB	GWB	EXP	
3W47	OFF	CPT	RB	GWB	AT-1	
3W48	OFF	CPT	RB	GWB	AT-1	
3W49	OFF	CPT	RB	GWB	AT-1	
3W50	OFF	CPT	RB	GWB	AT-1	
3W51	OFF	CPT	RB	GWB	AT-1	
3W52	OFF	CPT	RB	GWB	AT-1	
3W53	OFF	CPT	RB	GWB	AT-1	
3W54	OFF	CPT	RB	GWB	AT-1	
3W55	OFF	CPT	RB	GWB	AT-1	
3W56	OFF	CPT	RB	GWB	AT-1	
3W57	OFF	CPT	RB	GWB	AT-1	
3W59	OFF	CPT	RB	GWB	AT-1	
3W60	DATA ANLYS	LN	RB	GWB	AT-1	
3W61	OFF	CPT	RB	GWB	AT-1	
3W62	ELEC	EPY	RB	GWB	EXP	
3W63	OFF	CPT	RB	GWB	AT-1	
3W64	IDF	EPY	RB	GWB	EXP	
3W65	OFF	CPT	RB	GWB	AT-1	
3W66	SIGNAL	EPY	RB	GWB	EXP	
3W67	OFF	CPT	RB	GWB	AT-1	
3W69	ADMIN	CPT	RB	GWB	AT-1	
3W70	CONF	CPT	RB	GWB / FWP	AT-3	
3W72	LOUNGE	PT	PT	GWB / FWP / CT	AT-3	
3W75	UNASSIGNED	LN	RB	GWB	AT-1	
3W84	GAS	SEC	RB	GWB(SC)	EXP	EPOXY PAINT FINISH
3W85	LAB 7	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W85A	LAB 8	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W85B	EQUIP	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W86	TISSUE CULT	LN	ICB	GWB(SC)	AT-1	EPOXY PAINT FINISH
3W87	ELEC	EPY	RB	GWB	EXP	
3W91	WASH	LN	ICB	GWB(SC)	AT-7 / GWB(SC)	EPOXY PAINT FINISH
3W92	TOILET	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
3W95	HAC	QT	QT	GWB(SC) / CT	GWB	4'-0" A.F.F. WAINSCOT CT AT ALL WALLS AND EPOXY PAINT FINISH ABOVE, 5"x6" COVE BASE
3W96	TOILET	PT	PT	PWT	GWB	FULL HEIGHT PT AT ALL WALLS, 2"x12" COVE BASE
3W97	MECH SHAFT	-	-	EXP	-	
5H95	STAIR 1	RF	RB	GWB	GWB	

NOTES

FINISH LEGEND

FLOORING

CPT	CARPET TILE
PT	PORCELAIN FLOORING TILE
LN	LINOLEUM
RF	RUBBER FLOORING
TER	TERRAZZO / POURED
EPY	EPOXY FLOORING
ICB	INTEGRAL COVE BASE
RB	RESILIENT BASE
WM	WALKOFF MAT
SEC	SEALED CONCRETE
SC	SPECIAL COATING, SEE SPEC SECTION 09 96 59.
QT	QUARRY TILE

WALL

CT	CERAMIC TILE
PWT	PORCELAIN WALL TILE
FWP	ACOUSTICAL FABRIC WALL PANEL
GWB	GYPSUM WALLBOARD PANEL / PAINTED
PP	PHENOLIC PANEL
WDW	WOOD WALL PANEL
W	WALL COVERING
SS	STAINLESS STEEL
EXP	EXPOSED
RSW	RIGID SHEET WAINSCOT

CEILING

AT-1	2X4 TEGULAR / MINERAL FIBER
AT-2	2X4 SQUARE TEGULAR / FIBER GLASS
AT-3	2X6 SQUARE TEGULAR / FIBER GLASS
AT-4	4X4 SQUARE TEGULAR / FIBER GLASS
AT-5	2X2 VECTOR / WOOD CHANNEL PERFORATIONS (W/ ACOUSTICAL BACKING)
AT-6	ACOUSTICAL SPECIAL CEILING
AT-7	2X4 CLEAN ROOM MINERAL / FIBER SQUARE LAY-IN
AT-8	WOOD PLANK CHANNEL (W/ ACOUSTICAL BACKING)
EXP	EXPOSED CEILING
GWB	GYPSUM CEILING / PAINTED

CONSTRUCTION DOCUMENT 2
FULLY SPRINKLERED

1 AMENDMENT A00004	07.14.2014
BID DOCUMENTS	05.30.2014
CONSTRUCTION DOCUMENT CD2	06.05.2013

CONSULTANTS:

6454 REGISTERED ARCHITECT STATE OF WASHINGTON

ARCHITECT

STANTEC | THE DESIGN PARTNERSHIP

Drawing Title: MH&R - ROOM FINISH SCHEDULE
Project Title: Building 101 Mental Health Services VAPSHCS Seattle Division - Phase 2 MENTAL HEALTH AND RESEARCH BUILDING
Drawing Scale: 1/4" = 1'-0"
Location: 1660 South Columbian Way, Seattle, WA 98105
Approved: Project Director
Date: JUNE 05, 2013
Checked: AL
Drawn: HH
Project Number: VA# 663-405B
Building Number: B101 Mental Health Services
Drawing Number: AF622
Volume 2a

Office of Construction and Facilities Management
Department of Veterans Affairs

7/14/2014 9:33:18 AM