



**INFECTION CONTROL RISK ASSESSMENT:**

**LOW/MEDIUM RISK (LEVEL II):**

NO WORK SHALL COMMENCE WITHOUT PRIOR SCHEDULING AND APPROVAL FROM COTR. PROVIDE ACTIVE MEANS TO PREVENT AIRBORNE DUST FROM DISPERSING INTO THE ATMOSPHERE. WATER MIST WORK SURFACES TO CONTROL DUST WHILE CUTTING. WIPE WORK SURFACE WITH DISINFECTANT. CONTAIN CONSTRUCTION WASTE BEFORE TRANSPORT IN TIGHTLY COVERED CONTAINERS. ALL CEILING TILES REMOVED FOR CONDUIT INSTALLATION SHALL BE REPLACED AT THE END OF EVERY WORK SHIFT IN ORDER TO MAINTAIN THE SMOKE BARRIER. USE A HEPA VACUUM ON EVERY TILE BEFORE REINSTALLATION. ONLY ONE CEILING TILE CAN BE REMOVED AT A TIME FOR CABLE/CONDUIT INSTALLATION. WET MOP AND/OR VACUUM WITH HEPA FILTERED VACUUM AT THE END OF EVERY WORK SHIFT.

**SHEET NOTES:**

**DETAIL 1:**

- EXISTING FAN COIL UNIT - NOT BEING USED
- EXISTING REPROCESSING UNITS TO BE REMOVED - SEE ATTACHMENT 1 ON SCHEDULE B.
- REMOVE DOOR AND CONSTRUCT WALL TO MATCH EXISTING.

1  
A-01  
NTS  
8TH FLOOR GI LAB



**NOTE 3**

**GENERAL NOTES:**

- SCALED DIMENSIONS & ARCHITECTURAL FEATURES MAY NOT BE CORRECT.
- CONTRACTORS & A/E's ARE RESPONSIBLE TO FIELD VERIFY ALL DIMENSIONS WITHIN THE PROJECT AREA.

**DEPARTMENT OF VETERANS AFFAIRS  
MEDICAL CENTER  
1055 Clermont Street  
Denver, Colorado, 80220**

Drawing Title <b>8TH FLOOR PLAN GI LAB</b>		Project Title <b>GI HVAC &amp; EQUIPMENT SITE PREP</b>		Date 05/15/2014
Approved: Service Chief	Drawn CMG	Building Number 1	Title Block By ska	Project No. 554-14-821
Approved: Section Chief	Checked	Wing C	DRAWING No. A-01	Dwg 2 Of 2

By	Revisions	Date