



Lighting Electrical Parts List Summary

ITEM	DWG SYMBOL	FIXTURE QUANTITY	MANUFACTURER	DESCRIPTION	REMARKS
1	C	16	H.E. Williams, Inc.*	Two lamp extruded, surface mounted wraparound fluorescent fixture. 120-277 volt; 50/60 Hz. Include lamps with fixture. Catalog Number - 37-4-232-A** Lamps - FO32/841/XPS/ECO (2 per fixture)	Surface Wraparound Fixture Quantity Shown = Actual +3 (spares)
2	D1	33	The Kirlin Company*	Recessed downlight. 120-277 multi-volt; 50/60 Hz. Include lamps with fixture. Catalog Number - FRR-07015** Lamps -CF42DT/E/IN/841/ECO (1 per fixture)	Recessed Downlight Fixture Quantity Shown = Actual +2 (spares)
3	D2	30	The Kirlin Company*	Recessed downlight. 120-277 multi-volt; 50/60 Hz. Include lamps with fixture. Catalog Number - FRR-07015** Lamps -CF26DT/E/IN/841/ECO (1 per fixture)	Recessed Downlight Fixture Quantity Shown = Actual +3 (spares)
4	E	12	Luminaire, Inc.*	Wall/ceiling mount fluorescent fixture. 120 volt. Include lamp with fixture. Catalog Number - LPL512-1PLC26** Lamps -CF26DT/E/IN/841/ECO (1 per fixture)	Wall Pack
5	F	2	Finelite, Inc.*	Linear suspended fluorescent fixture; Series 12P (perforated) 120 volt. Include lamps with fixture. Catalog Number - S12P-36-2T8-SC-91W-FA-CE** Lamps - FO32/841/XPS/ECO (18 per fixture)	Linear Suspended - with 4' fluorescent lamps
6	G	12	The Kirlin Company*	One lamp, recessed downlight. 120 volt; 50/60 Hz. Electronic dimming ballast. Include lamp with fixture. Catalog Number - FRR-07015-39** Lamps -CF42DT/E/IN/835/ECO (1 per fixture)	Recessed Downlight (Dimming) Fixture Quantity Shown = Actual +2 (spares)
7	H	20	Singapore Moderne*	Wall sconce - warm muted silver leaf finish. 120 volts. Include lamps with fixture. Catalog Number - 600550-2** Lamps -G16.5, LED, E12 Base (2 per fixture)	Wall Sconce Fixture Quantity Shown = Actual +2 (spares)
8	I	16	VISA Lighting*	Shine wall sconce, 120 volt, high power factor electronic ballast. standard painted finish; Include lamp with fixture. Catalog Number - CB5512-1F017** Lamps - FO17/841/XPS/ECO (1 per fixture)	Wall Mounted Fixture Quantity Shown = Actual +2 (spares)

ITEM	DWG SYMBOL	FIXTURE QUANTITY	MANUFACTURER	DESCRIPTION	REMARKS
9	J	***	Pinnacle Architectural Lighting*	Linear suspended fixture - single circuit dimming; 120 volts. Include LED lamps. Catalog Number - L6A35-40HO- (3) - (4) - 1D-CC (2)** Lamps - LED	(2) Architect to select custom color (3) Refer to floor plan for length (4) Provide adjustable aircraft cable. Verify mounting type for each space.
10	K	10	Phillips Lightolier*	Lytecaster downlighting - recessed low voltage. Include LED lamp. Catalog Number - 1100IC/N-1161** Lamp - Phillips Item Number 101-00007401, 30° iColor MR GEN3	RGB Downlight Wallwasher
11	L	16	H.E. Williams, Inc.*	High Efficiency Surface Mount Fixture - electronic ballast; 120 volts. Include lamps with fixture. Catalog Number - HES-14-232-A** Lamps - FO32/841/XPS/ECO (2 per fixture)	Surface 1x4
12	M	6	The Kirlin Company*	Recessed downlight -120/277 multi-volt electronic ballast. For use in showers. Include lamp with fixture. Catalog Number - FRR-05032** Lamp - CF26DT/E/IN/841/ECO (1 per fixture)	Recessed Downlight (Shower)
13	N	14	Phillips Lightolier*	Recessed Downlight - LED - Input Voltage (120V); Include lamp with fixture. Catalog Numbers -C7L-20-N-VB-LD/C7L-1520-DL-40K-M-CCL-W-VB **	Recessed Downlight
14	O	15	Phillips Lightolier*	Recessed Downlight Wall Washer - LED (Dimming) Input Voltage (120V) Include lamp with fixture. Catalog Numbers -C7L-15-N-VB-Z10V/C7L-1520-WW-40K-COL-W **	Recessed Downlight Wall Washer (Dimming) Fixture Quantity Shown = Actual +2 (spares)
15	P	10	George Kovacs*	Reading Light - LED - Wall Mount - Brushed Nickel - 120 volts. Include lamp with fixture. Catalog Number - P4328-084** Lamp - Z05, 8W LED	Reading Light Fixture Quantity Shown = Actual +2 (spares)
16	Q	17	Phillips Lightolier*	Recessed Downlight - LED - (Dimming) Input Voltage (120V); Include Lamp with fixture. Catalog Numbers -C7L-20-N-VB-Z10V/C7L-1520-DL-40K-M-CCL-W-VB **	Recessed Downlight (Dimming) Fixture Quantity Shown = Actual +3 (spares)
17	R	1	Singapore Moderne*	Pendant light fixture - warm muted silver leaf finish. 120 volts. Include lamps with fixture. Catalog Number - 600140-2** Lamp - LED 4B10C/BLUNT/DIM/827 (12 ea.)	Pendant

ITEM	DWG SYMBOL	FIXTURE QUANTITY	MANUFACTURER	DESCRIPTION	REMARKS
18	S	***	Finelite, Inc.*	Recessed linear LED luminaire - High Performance 4" Aperture; 120 volts. Catalog Number - HP-4R-(3)-HO-4000K-SC**	(3) Refer to floor plan for length
19	U1	2	H.E. Williams, Inc.*	Fluorescent light fixture - Chain hung industrial - Input Voltage (120V). Include lamps with fixture. Catalog Number - 80-4-332-VBY-2 (6)-EB3** Lamps - FO32/841/XPS/ECO (3 per fixture)	(6) Provide Wireguard Fixture Quantity Shown = Actual +1 (spares)
20	U2	2	H.E. Williams, Inc.*	Fluorescent light fixture - Chain hung industrial - Input Voltage (120V). Include lamps with fixture. Catalog Number - 80-8-632-VBY-2 (6)-EB3** Lamps - FO32/841/XPS/ECO (6 per fixture)	(6) Provide Wireguard
21	X	14	Evenlite *	Self Luminous Exit Sign Catalog Number - SL201RB** Lamps -N/A	Slimline - Single Sided Include mounted brackets as required Fixture Quantity Shown = Actual +2 (spares)
22	X1	2	Evenlite *	Self Luminous Exit Sign Catalog Number - SL202RB** Lamps - N/A	Slimline - Double Sided Include mounted brackets as required Fixture Quantity Shown = Actual +1 (spare)

LEGEND/NOTES

* Provide products from the specified manufacturers - **(exact match, no substitutes)**

** The catalog numbers are described as shown on the Drawing E001 Lighting Fixture Schedule. The bidder shall review and revise the catalog numbers as required to meet the project requirements.

*** Fixture lengths and quantities will depend on configuration. Refer to project drawings for layout.

Note 1 - Lighting fixture types A & B (shown on Drawing E001, but not shown on this document) refer to previous purchased products and are not included with this proposal.

Note 2 - Bidders are responsible for verifying all fixture quantities. Additional quantities were calculated for some of the fixtures. Refer to the remarks column for details.