SEE P-4 FOR CONTINUATION
MATCH LINE

CONSTRUCTION NOTES:

1. LAB FAUCETS: REPLACE EXISTING LABORATORY FAUCETS WITH NEW. INSTALL ISOLATION VALVES ON HOT AND COLD WATER SUPPLY PIPING. INSTALL CHECK VALVE ON HOT WATER SUPPLY PIPING. ALL VALVES SHALL BE LOCATED IN ACCESSIBLE LOCATIONS.
2. MOP SINK FAUCETS: INSTALL CHECK VALVE ON HOT WATER SUPPLY PIPING. ALL VALVES SHALL BE LOCATED IN ACCESSIBLE LOCATIONS.
3. SHOWER VALVES: INSTALL CHECK VALVE ON HOT WATER SUPPLY PIPING. ALL VALVES SHALL BE LOCATED IN ACCESSIBLE LOCATIONS.
4. SENSOR FAUCETS: INSTALL CHECK VALVE ON HOT WATER SUPPLY PIPING. ALL VALVES SHALL BE LOCATED IN ACCESSIBLE LOCATIONS.
5. KNEE PEDAL CONTROL FAUCETS: INSTALL CHECK VALVE ON HOT WATER SUPPLY PIPING. ALL VALVES SHALL BE LOCATED IN ACCESSIBLE LOCATIONS.
6. REMOVE EXISTING AERATORS, WHERE APPLICABLE, AND INSTALL LAMINAR FLOW END DEVICE ON ALL FAUCETS.
7. INSTALL CHECK VALVES ON ALL HOT WATER MAINS AND HOT WATER RECIRCULATING MAINS AT EACH FLOOR. INSTALL NEW ISOLATION VALVE IF NO EXISTING ISOLATION VALVE IS INSTALLED.

SEE P-5 FOR CONTINUATION
MATCH LINE

ALL EXISTING CONDITIONS ARE FROM RECORD DRAWINGS. CONTRACTOR TO FIELD VERIFY ALL CONDITIONS PRIOR TO START OF CONSTRUCTION.

FIRST FLOOR - D WING
PLUMBING PLAN

0 1 2 4 8 16 24 FT.
SCALE: 1/8"=1'-0"

KEY PLAN - FIRST FLOOR

BLDG. NORTH
MAG. NORTH

GEORGIA
PE032509
PROFESSIONAL
ENGINEER
CURTIS V. WILLIAMSON
3/29/13

ISSUED FOR CONSTRUCTION	03/29/13
Revisions:	Date:

Drawn By: WBR
Checked: CVW

JOHNSON, LASCHOBER & ASSOCIATES, P.C.
ARCHITECTS • ENGINEERS
LANDSCAPE ARCHITECTS
1256 BRUNDAGE ST., ALBANY, GEORGIA 31705
PHONE: (706) 724-5756 FAX: (706) 724-5955
WEBSITE: WWW.THEJLAGROUP.COM

Project Title:
Replace Water Lines – Phase 6
Building 801 – Downtown Division

Date: 03/29/13
Project No. 509-10-124

Drawing Title:
FIRST FLOOR – D WING
PLUMBING PLAN

Drawing No. P-6
Dwg. 7 of 29

Department of Veterans Affairs
VAMC Augusta, Georgia
Engineering Service (138)