

STATEMENT OF WORK for 550-14-109

1. Title of Project:

F.C.A. "Remove Underground Storage Tanks and Above Ground Steam Line"

2. Scope of Work:

VA Illiana Healthcare System, Danville, IL seeks a contractor to perform the work prescribed within this document to properly remove Underground Storage Tanks:

- #14 (4,000 gallons-diesel)
- 18VAID#1 (30,000 gallons-heating oil)
- 1D19VA#2 (30,000 gallons-heating oil)
- 20VAID#3 (30,000 gallons-heating oil)
- 21VAID#4 (30,000 gallons-heating oil)
- 22VAID#5 (30,000 gallons-heating oil)
- 23VAID#6 (30,000 gallons-heating oil)

Contractor shall be responsible for all items that are described within the Statement of Work, Drawings, and Specifications. Work included in this project shall consist of the following:

1. Erection of temporary six (6) foot tall chain link construction fence around work site.
2. Acquisition of all permits, as required by the Illinois State Fire Marshall's Division of Petroleum and Chemical Safety and by the Environmental Protection Agency (EPA).
3. Coordination with the Illinois State Fire Marshall to schedule the excavation, removal, purging, and cutting of the tanks and the testing of the adjacent soil.
4. Contractor shall be responsible for the locating of all underground utilities prior to start of excavation, and shall be held responsible for any damage and repairs made to them.
5. Exploratory excavation to determine the precise location and dimensions of the underground storage tanks.
6. Removal of adjacent concrete, asphalt, fencing, and landscaping as needed to safely excavate the tanks in compliance with all applicable OSHA regulations for excavation.

7. Excavate sufficient area around the tanks to allow for removal.
8. All excavated soil shall be stockpiled atop EPA approved containment to avoid any potential contamination.
9. Lift tank out of excavation site and place at grade.
10. Follow all State, Federal, and VA regulations for testing of explosive limits within the tanks.
11. If necessary, purge tanks of any residual explosive gasses per State, Federal, and VA regulations.
12. Cut tanks (if necessary)
13. Remove existing underground and exterior fuel piping and cap inside of Building 100.
14. Remove two existing Veeder-Root tank monitors and all associated wiring.
15. Sample soil from excavation site surrounding the former tanks to test for any potential hydrocarbons that may have leaked from the tanks.
16. Remove any contaminated soil.
17. Dispose of any contaminated soil and tanks at State of Illinois EPA approved disposal site.
18. After all soil samples have been tested and results show no contamination, backfill excavation with compacted suitable fill.
19. Top backfill with topsoil.
20. Seed and restore all disturbed areas, including replacing of sidewalks, parking, and seeded grass areas.
21. Provide a letter from the Office of the Illinois State Fire Marshall's Division of Petroleum and Chemical Safety stating that the Status of UST Tank #8 (IEMA Number 91-0968) has been changed from "Out of service" to "Removed."
22. Remove existing above ground steam line, approximately 340' (contractor to verify amount).
23. Seal off existing underground steam line, below grade, with concrete on both ends.
24. Abandon in place all underground steam lines.
25. Remove existing support structure and foundation of above ground steam line.
26. Provide documentation showing that a credit for the salvage value of the steam line was taken off of the total cost of the project.

3. Performance Period

Contractor shall complete all work associated with this project within forty-five (45) calendar days of the receipt of the Notice to Proceed (NTP). Normal working hours are Monday through Friday, 0700-1630, excluding Federal Holidays. Contractor shall provide a schedule to the Contracting Officer's Representative, through the Contracting

Officer, prior to any onsite work taking place. If for any reason the contractor can't meet the required period of performance for this project he/she must submit, in writing, to the Contracting Officer, a revised schedule, justification, and request for additional time.

Contractor shall make all concerted efforts to minimize the duration of downtime to each building. The C&A requirements do not apply and a Security Accreditation Package is not required.

4. Background:

Work will be performed at:

VA Illiana Health Care System

1900 East Main St.

Danville, IL 61832