



- Notes:
1. Demo steam and condensate lines existing to source.
  2. Relocate electric line 24" south of current location.
  3. Demo steam and condensate lines existing to source. Add new steam and condensate line 18" south of removed location.
  4. Demo existing sanitary drain lines to source. Add two new sanitary drain lines 18" south of current location.
  5. Demo existing hot and cold water lines to source. Add new hot and cold water lines 18" south of current location.
  6. All new work shall be run under existing floor.
  7. All new plumbing stub ups shall be 6" minimum above finished floor, and include isolation valves.
  8. All plumbing material used shall be as specified in the attached specifications.
  9. Repairs shall be made of all disturbed flooring to match existing.
  10. Contractor shall field verify all dimensions, and utility direction/ location.
  11. Drawings are for reference purposes only.