

**FOR OFFICIAL USE ONLY**

**Source Selection Sensitive Information—See FAR 2.101 & 3.104**

**VA261-14-R-0933 – Facility Sign Repairs, VANCHCS Mather**

**RFI's and Government Responses Through 8/7/2014**

**Proposal RFI #1 – Will shop drawings and a sign schedule be required for all signs?**

**#1 - YES**

**Proposal RFI #2 – Is it the intent of the SOW to replace all of the white Acrylic vinyl background behind the routed lettering?**

**#2 – YES**

**Proposal RFI #3 - Does VA have a specification for the type of reflective vinyl film, as there is a large variance in this material?**

**#3 – HIGH PERFORMANCE, ENGINEERING GRADE 7 YEAR VINYL, i.e. 3M 6800 SCOTCHLITE OR EQUAL QUALITY.**

**Proposal RFI #4 - Does VA have a specification for the type of paint to be applied to the signs? The exterior semi-gloss referenced in the SOW would not be as long lasting as compared to a high quality automotive type paint.**

**#4 – A PREMIUM HIGH QUALITY EXTERIOR SIGN SPECIFIC ENAMEL & PRIMER WILL BE REQUIRED, i.e. 1SHOT CHROMATIC PRIMER AND SIGN PAINT OR EQUAL. [www.1shot.com](http://www.1shot.com) (For reference only)**

**Proposal RFI #5 - Is it the intent of the SOW to strip all existing paint from the signs? If yes, is it acceptable to perform this operation off site?**

**#5 – YES, AND IT IS PREFERRED BY THE VA THAT IT BE DONE OFFSITE.**

**Proposal RFI #6 - What type of warranty will VA require for this project.**

**#6 – ONE YEAR WORKMANSHIP WARRANTED BY THE CONTRACTOR AND APPLICABLE ACCEPTED PRODUCT WARRANTY.**

**Proposal RFI #7 - During the process of painting and re-lettering, will VA require temporary signage?**

**#7 – YES, A SAMPLE TEMPORARY SIGN SUBMITTAL WILL BE REQUIRED.**

**FOR OFFICIAL USE ONLY**

**Source Selection Sensitive Information—See FAR 2.101 & 3.104**

**Proposal RFI #8 - The existing finishes appear to be sprayed on, is the intent of the scope to match the quality of the existing finish?**

**#8 – YES, THE EXISTING PAINT IS SPRAYED ON AND THE REPLACEMENT WILL BE SPRAYED ON ALSO, HOWEVER NO ONSITE SPRAYING WILL BE ALLOWED.**

**Proposal RFI #9 - Will any electrical work be required, bulbs, ballasts, etc.**

**#9 – THE CONTRACTOR IS TO COORDINATE WITH THE COR AND VA DESIGNATED ELECTRICIANS TO REPAIR ANY DEFECTIVE ELECTRICAL ISSUES DISCOVERED.**

**Proposal RFI #10 - Will vector artwork be provided for every sign type, including logos, fonts arrows, etc?**

**#10 – NO, MATCH EXISTING AND RFI ANY QUESTIONABLE OR UNCLEAR SPECIFIC SIGNS.**