



UPDATED: 5/9/2014 3:38:00 PM

	PLUMBING FIXTURE SCHEDULE											
SYMBOL			MINIMUN	I BRANCH I	PIPE SIZE							
	DESCRIPTION	HW (IN)	CW (IN)	W (IN)	TRAP (IN)	V (IN)	REMARKS					
P-103	WATER CLOSET	- (114)	1	4	INTEGRAL	2	WATER CLOSET - VITROUS CHINA WALL MOUNTED, REAR OUTLET MEETING ADA HEIGHT, WITH SENSOR FLUSH VALVE					
P-202	URINAL ADA	-	3/4	2	INTEGRAL	2	URINAL - WALL HUNG, FLUSH VALVE, 0.5 GPF, MOUNTED TO MEET ADA ACCESSIBLE HEIGHT.					
P-413	LAVATORY	1/2	1/2	2	1 1/2	2	LAVATORY - SELF RIMMING, VIT. CHINA, ADA ACCESSIBLE, W/ HARD WIRED SENSOR FAUCET & 2.5 GPM LAMINAR FLOW OUTLET					
RD-1	ROOF DRAIN	-	-	3	-	-	ROOF DRAIN - 3"					
ORD-1	OVERFLOW DRAIN	-	-	3	-	-	OVERFLOW DRAIN - 3"					
FD-1	FLOOR DRAIN	-	1/2	2	2	2	FLOOR DRAIN - PROVIDE TRAP PRIMER PIPE AND FITTING -					
HD-1	HUB DRAIN	-	1/2	4	4	2	HUB DRAIN - PROVIDE AIR GAP FITTING ANDTRAP PRIMER PIPE AND FITTING					
P-802	HOSE BIBB	-	3/4	-	-	-	HOSE BIBB - CW HOOKUP W/ VACUUM BREAKER					
P-606	DRINKING FOUNTAIN	-	3/4	2	1 1/2	2	DRINKING FOUNTAIN - BARRIER FREE WALL MOUNTED W/ DUAL HEIGHT FOUNTAINS, ADA ACCESSIBLE.					
RR-1	ROOF RECEPTOR	-	-	4	-	4	ROOF RECEPTOR - 4"					

INSTANTANEOUS ELECTRIC WATER HEATER SCHEDULE														
MARK	DESCRIPTION	TYPE USAGE	LISAGE	LOCATION	TEMP. OCATION RISE	CONN.	MAX. WORKING	ELECTRICAL					REMARKS	DETAIL
			LOCATION	IXIOL	CONN.	PRESS.	WATTS	AMPS	VOLTS	PH	HZ	NLIVIANNO	DETAIL	
(IWH)	WALL MOUNTED INSTANT. WATER HEATER	ELECTRIC POINT OF USE	AREA HAND WASH	TOILET ROOM LAVATORIES	34	1/2 NPT	150	2500	12	208	1	60	FLOW SWITCH ACTIVATES HTR. AT 0.32 GPM	

DESIGN RAINFALL RATE

1 1/2 IN./ HOUR / SQ. FT.

1) schedules 12" = 1'-0"

FULLY SPRINKLERED

	CONSULTANTS:	Stamp and Signature	ARCHITEC/ENGINEERS:	Drawing Title	Project Title NEW OFFICE	Project Number 640-379	Office of
	Syska Hennessy Group, Inc. 425 California Street Suite 700 San Francisco, CA 94104	PROFESSIONAL THE SHERNA THE	ENGINEERS ARCHITECTS ONE KAISER PLAZA SUITE 445	PLUMBING SCHEDULES	AND LABS	Building Number 1002	Construction and Facilities
	SYSKA HENNESSY GROUP A member company of SH Group, Inc. GROUP A member company of SH Group, Inc.		OAKLAND CALIFORNIA 94612 TEL 510.271.6701 FAX 510.271.6707	Approved: Project Director	Location 1080 INNOVATION WAY, SUNNYVALE, CA 94085	P-002 Dwg. of	Management
Revision_	DATE		THE KPA GROUP 2013 KPA Project No. 563.00	VAPAHCS PLANNING AND ENGINEERING	Date Checked Drawn BWA		VA SPAHCS Palo Alto Health Care System

1 2 - 3 9 | 3 9















