


- GENERAL:
- A. EACH ACU SHALL BE SEQUENCED BY A FACTORY PROGRAMMED DEDICATED DDC CONTROLLER TO PERFORM THE FOLLOWING OPERATIONS DESCRIBED BELOW:
 - (1) THE VALVE CM SHALL BE FIELD ADJUSTABLE.
 - (2) THE VALVE CM SHALL MODULATE TO MAINTAIN THE SCHEDULED CM INDEPENDENT OF THE SYSTEM PRESSURE.
 - (3) THE HIGH AND LOW LIMIT OF THE ACU SHALL BE SET TO $\pm 10\%$ (A/D) OF THE SCHEDULED CM.
 - B. LEFS₁ SHALL RUN CONTINUOUSLY. INSTALL CURRENT SENSORS ON EXHAUST FAN LEFS₁. UTILIZE THE FAN CURRENT SENSORS TO MONITOR THE FAN.
 - C. LEFS₂ SHALL RUN CONTINUOUSLY. INSTALL CURRENT SENSORS ON EXHAUST FAN LEFS₂. UTILIZE THE FAN CURRENT SENSORS TO MONITOR THE FAN.
2. SYSTEM GRAPHICS: THE SYSTEM GRAPHICS SHALL DISPLAY ALL POINTS INDICATED ON THE CONTROL SCHEMATIC AND THE FOLLOWING ITEMS:
- A. CM1 SETPOINT EACH ACU.
 - B. CM1 THROUGH EACH ACU.
 - C. TOTAL CM1 OF ALL ACU SERVED BY A SINGLE FAN.
 - D. HIGH/LIMIT CM1 SETPOINT FOR EACH ACU, AN ALARM SHALL BE SET AT THE OPERATORS WORKSTATION IF THE CM1 REARS OVER OR FALLS BELOW THE HIGH/LIMIT CM1 SETPOINT.
 - E. HIGH/LIMIT ALARM SHALL BE SET AT THE OPERATORS WORKSTATION IF THE CM1 REARS OVER OR FALLS BELOW THE HIGH/LIMIT CM1 SETPOINT.
 - F. GENERAL FAULT IN THE CONTROLLER, ANOMALY IMAGE OR A SENSOR FAILURE AS APPLICABLE.
 - G. STATUS OF FAN LEFS₁.
 - G. STATUS OF FAN LEFS₂.
 - H. IF THE FAN SERVING THE ACU IS ON, THE ACU STATUS SHALL BE DISPLAYED AS ENABLED AT THE OPERATORS WORKSTATION.
 - I. IF THE FAN SERVING THE ACU IS OFF, THE ACU STATUS SHALL BE DISPLAYED AS DISABLED AT THE OPERATORS WORKSTATION.
3. THE DIFFERENTIAL PRESSURE MEASURED ACROSS FILTER #5:
- A. PRELIMINARY WARNING: WHEN THE DIFFERENTIAL PRESSURE (DIP) IS APPROXIMATELY 0.5 INCHES (A/D) ABOVE THE DIFFERENTIAL PRESSURE EXCEEDS 0.7 INCHES (A/D) FOR THE PREFILTER AND 1.3 INCHES (A/D) FOR THE FINAL FILTER.
 - B. MAINTENANCE WARNING: WHEN THE DIFFERENTIAL PRESSURE EXCEEDS 0.9 INCHES (A/D) FOR THE PREFILTER AND 1.5 INCHES (A/D) FOR THE FINAL FILTER.

ROOM PRESSURE MONITOR (RPM), CONTROL SEQUENCE

- A. GENERAL:
- A. RPLM1 SHALL PROVIDE LOCAL ALARMS AND ALARMS AT THE OPERATORS WORKSTATION.
 - 1. WHEN THE MAGNETIC DOOR CONTACTS ARE OPEN, AUDIBLE ALARMS SHALL BE DISABLED.
 - 2. FOR STATUS AND RECORDED DIFFERENTIAL PRESSURE READINGS SHALL BE LOGGED CONCURRENTLY.
 - B. RPLM2 IS FOR MONITORING PURPOSES. STATUS WILL BE DISPLAYED AT THE OPERATORS WORKSTATION LOCAL ALARMS SHALL BE DISABLED.
 - 1. WHEN THE MAGNETIC DOOR CONTACTS ARE OPEN, DOOR OPEN SHALL BE DISPLAYED AT THE OPERATORS WORKSTATION.
 - 2. DOOR STATUS AND RECORDED DIFFERENTIAL PRESSURE READINGS SHALL BE LOGGED CONCURRENTLY.
 - C. SYSTEM GRAPHICS: THE SYSTEM GRAPHICS SHALL DISPLAY ALL POINTS INDICATED ON THE CONTROL SCHEMATIC AND THE FOLLOWING ITEMS:
 - A. ROOM PRESSURE DIFFERENTIAL
 - B. DOOR STATUS



The seal appearing on this document was authorized by Robert M. Dawes, 22679 on 9/20/2013. Alteration of a sealed document without proper notification to the responsible engineer is an offense under the Oklahoma Engineering Practice Act.




/2013

ASBESTOS NOTE:
IF THE EXECUTION OF THIS WORK REQUIRES THE DISTURBING OF ANY SUBSTANCE WHICH APPEARS TO BE ASBESTOS OR WHICH MAY CONTAIN ASBESTOS FIBER, NOTIFY THE OWNER BEFORE CONTINUING WORK AT THE SUSPECT LOCATION. ANY MATERIAL TESTING POSITIVE SHALL BE REMOVED BY THE OWNER BEFORE WORK CONTINUES.

NOTE: EXISTING CONDITIONS SHOWN WERE DERIVED FROM OWNER FURNISHED DRAWINGS AND FIELD OBSERVATIONS. SOME BUILDING FEATURES AND MEP SYSTEMS ARE NOT SHOWN FOR CLARITY. FIELD VERIFY BUILDING CONSTRUCTION. FIELD VERIFY THE LOCATION, SIZE AND QUANTITY OF ALL EQUIPMENT.

NOTE: REFER TO DETAILS AND SCHEMATICS FOR PIPING, VALVES, FITTINGS AND OTHER APPURTENANCES REQUIRED, BUT NOT SHOWN FOR CLARITY.



Y PLAN

NO SCALE

1

DEPARTMENT OF
VETERANS AFFAIRS