





- 1 ROOF DRAIN WITH 4" 8D AND 4" OD PIPING IN ATTIC.
- 2 SLOPE ROOF DRAIN PIPING 1/8" PER FOOT IN DIRECTION INDICATED. (TYPICAL).
- 3 C.W. PIPING THROUGH ROOF. SEE PP220 FOR CONTINUATION.
- 4 C.W. PIPING THROUGH ROOF. SEE PP220 FOR CONTINUATION.
- 5 VENT THROUGH ROOF. SEE PP320 FOR CONTINUATION.
- 6 COOLING TOWER. 3/4" MAKE-UP WATER RISER THRU ROOF WITH BALL VALVE. SEE MECHANICAL PLANS FOR CONNECTION REQUIREMENTS TO EQUIPMENT. SEE PP220 FOR CONTINUATION.
- 7 ENERGY RECOVERY VENTILATOR. SEE MECHANICAL DRAWINGS.
- 8 DROP 4" 8D DOWN SECOND FLOOR CHASE. SEE PP220 FOR CONTINUATION.
- 9 TERMINATE OD AT SECOND FLOOR WALL 12" BELOW ROOF.
- 10 TERMINATE OD AT SOFFIT BELOW.
- 11 DROP 3" ROOF RECEPTOR DOWN TO SECOND FLOOR ATTIC. SEE PP220 FOR CONTINUATION.
- 12 VENT THROUGH ROOF. SEE PP220 FOR CONTINUATION.
- 13 CONDENSER 3/4" MAKE-UP WATER RISER THRU ROOF WITH BALL VALVE. SEE MECHANICAL PLANS FOR CONNECTION REQUIREMENTS TO EQUIPMENT. SEE PP220 FOR CONTINUATION.
- 14 COMBINATION COMBUSTION AIRFLUE.

		<b>CONSULTANTS:</b>    <b>LP Consulting Engineers, Inc.</b> 695 W. Ashlan Ave, Suite 101 Clovis, CA 93612 p 550-348-2130 - f 550-348-2131 www.lpengineers.com Job #: 11-1688.1				<b>ARCHITECT/ENGINEERS:</b>   <b>HMC Architects</b> 1827 E. Fir Avenue / Studio 103 / Fresno, CA 93720 T 559 322 2444/ www.hmcarchitects.com HMC PROJECT #1983002-000		Drawing Title <b>PLUMBING ROOF PLAN</b>  Approved: Project Director		Project Title <b>Mental Health Psychosocial Rehab Recovery and Health Care for Homeless Veteran Center</b>  Location <b>2615 E. CLINTON AVE, FRESNO, CA 93703</b>  Date 8/ 11/ 2014		Project Number <b>570-217</b>  Building Number <b>37</b>  Drawing Number <b>PP230</b> Dwg. of		Office of Construction and Facilities Management:   Department of Veterans Affairs	
--	--	--	--	--	--	---	--	--	--	--	--	---	--	---	--