



1 FIRST FLOOR PLAN - NEW WORK  
1/8" = 1'-0"

LIFE SAFETY GENERAL NOTES:

- ALL EXISTING PENETRATIONS, VERTICAL AND HORIZONTAL, LOCATED ON THE FIRST FLOOR ARE TO BE PROVIDED WITH AN APPROVED THROUGH - PENETRATION FIRESTOP SYSTEM HAVING A SMOKE RESISTANCE AND/OR FIRE RESISTANCE RATING EQUAL TO OR GREATER THAN THE ASSEMBLY PENETRATED. SMOKE FLOW PROOF: ALL EXISTING STRUCTURAL STEEL STUDS, JOISTS, AND CONCRETE SLABS, (WHEN APPLICABLE) SHALL BE PROTECTED BY 1 HOUR FIRE RATING. THIS WORK SHALL BE COMPLETED PRIOR TO ANY OTHER CONSTRUCTION BEING STARTED.
- ALL EXISTING PENETRATIONS, VERTICAL AND HORIZONTAL, LOCATED ON THE FIRST FLOOR ARE TO BE PROVIDED WITH AN APPROVED THROUGH - PENETRATION FIRESTOP SYSTEM HAVING A SMOKE RESISTANCE AND/OR FIRE RESISTANCE RATING EQUAL TO OR GREATER THAN THE ASSEMBLY PENETRATED. ALL NEW PENETRATIONS SHALL BE SEALED. REMOVAL OF OR PENETRATIONS SHALL BE PROVIDED TO REDUCE SPREAD OF CONSTRUCTION DEBRIS AND FOR INFILTRATION CONTROL ON THE FLOOR ABOVE AND BELOW.

NEW CANOPY ROOF - SEE 2/A405

2 CHASE DETAIL  
3/4" = 1'-0"



# FULLY SPRINKLERED BID DOCUMENTS

[illegible]