

1 ELECTRICAL DEMOLITION PLAN - SECOND FLOOR
1/8" = 1'-0"

ELECTRICAL DEMOLITION NOTES (This Drawing)

1. EQUIPMENT SHOWN TO BE REMOVED IS DIAGRAMMATIC AND DOES NOT REPRESENT THE FULL SCOPE OF DEMOLITION WORK. REMOVE ALL POWER, LIGHTING, FIRE ALARM, AND TELECOMMUNICATIONS DEVICES AND EQUIPMENT LOCATED WITHIN RENOVATION AREA UNLESS NOTED OTHERWISE. REMOVE WIRING BACK TO SUBSTANTIAL POINT OF ORIGIN. EXISTING TELECOMMUNICATIONS EQUIPMENT, INCLUDING TELECOMMUNICATION SWITCHES AND PATCH PANELS, ARE TO BE REMOVED AND RELOCATED TO LOCATION SHOWN ON NEW WORK PLANS.
2. CONTRACTOR SHALL PROVIDE A MINIMUM TWO WEEKS WRITTEN NOTICE PRIOR TO ANY SHUT DOWN. NOTICE IS TO INCLUDE BUT IS NOT LIMITED TO THE LOCATION, PANELS, AND DURATION OF SHUT DOWN.
3. COFR SHALL HAVE RIGHT OF FIRST REFUSAL TO ANY EQUIPMENT, DEVICES, LUMINAIRES, ETC. DEMOLISHED FROM THE RENOVATION AREA PRIOR TO DISPOSAL.
4. PROTECT THE EXISTING EQUIPMENT THAT IS TO REMAIN IN PLACE FROM DIRT, DUST, OR DAMAGE DURING THE COURSE OF DEMOLITION.
5. THE EXISTING FIRE ALARM CIRCUITS SERVING AREAS OUTSIDE OF THE SCOPE OF WORK SHALL REMAIN OPERATIONAL DURING THE ENTIRE DURATION OF THE CONSTRUCTION.
6. PROVIDE TEMPORARY SMOKE OR HEAT DETECTION ON THE FLOOR DURING THE ENTIRE DURATION OF CONSTRUCTION. SMOKE DETECTION SHALL BE PROTECTED FROM CONSTRUCTION DUST DURING WORKING HOURS ONLY. IN AREAS WHERE CONSTRUCTION WORK IS GOING TO BE OCCURRING.
7. REMOVE ALL LIGHTING FIXTURES, EXIT SIGNS, SWITCHES, CONTROL DEVICES, WIRING AND CONDUIT IN THE AREA OF DEMOLITION. REMOVE ALL WIRING BACK TO THE PANELBOARD IT ORIGINATES FROM.
8. REMOVE ALL RECEPTACLES, AND OTHER MISCELLANEOUS POWER CONNECTIONS TO EQUIPMENT IN THE AREA OF DEMOLITION. SHOW, REMOVE ALL CONDUIT AND WIRING BACK TO THE BRANCH PANELBOARD IT ORIGINATES FROM.

ELECTRICAL DEMOLITION NUMBERED NOTES (This Drawing)

- 1 NO DEMOLITION WORK IN THIS AREA.
- 2 REMOVE ALL EXISTING LIGHTING FIXTURES, CONDUIT, WIRE, SWITCHES, ETC BACK TO SOURCE.
- 3 REMOVE ALL EXISTING RECEPTALS, BOXES, CONDUIT, WIRE, ETC. BACK TO SOURCE.
- 4 REMOVE ALL EXISTING TELECOMMUNICATION DEVICES, BOXES, CONDUIT, WIRE, ETC. BACK TO SOURCE.
- 5 REMOVE ALL EXISTING FIRE ALARM DEVICES, BOXES, CONDUIT, WIRE, ETC. BACK TO SOURCE.
- 6 REMOVE ALL CONNECTIONS TO MECHANICAL EQUIPMENT BACK TO SOURCE UNLESS NOTED OTHERWISE.
- 7 REMOVE THE EXISTING PAGING SPEAKERS, CONDUIT, BOXES, AND WIRE. MAINTAIN CONTINUITY OF ANY WIRING THAT MIGHT SERVE AREAS STILL IN USE.
- 8 REMOVE THE EXISTING NURSERY CALL SYSTEM, CONDUIT, WIRING, BOXES.
- 9 THE ELECTRICAL CONTRACTOR SHALL MAINTAIN THE CONTINUITY OF ANY SYSTEMS WHICH MAY HAVE CONDUITS RUNNING THROUGH THE AREA OF DEMOLITION. RE-ROUTE ANY CONDUITS (BRANCH OR FEEDER) AS REQUIRED TO MAINTAIN CONTINUITY OF THAT SYSTEM OR EQUIPMENT. THE ELECTRICAL CONTRACTOR SHALL NOTIFY THE ARCHITECT OF THESE FINDINGS, IF THEY OCCUR DURING DEMOLITION.
- 10 EXISTING JUNCTION BOXES IN WALL SHALL REMAIN, CIRCUITS BACK TO PANEL SCHEDULED TO BE REMOVED SHALL BE DISCONNECTED AND REMOVED.
- 11 REMOVE EXISTING PANELBOARD AND ALL ASSOCIATED FEEDERS BACK TO SOURCE.
- 12 CONDUIT RISER FOR PANELBOARDS ON SECOND FLOOR, CONDUIT AND WIRING SHALL BE REMOVED BACK TO SOURCE.
- 13 CONDUIT RISER FOR PANELBOARD IN ATTIC, CONDUIT AND WIRING SHALL BE REMOVED BACK TO SOURCE. ELECTRICAL CONTRACTOR SHALL PATCH FLOOR AT THIS LOCATION AND PROVIDE PROPER FIRE PROOFING TO PROVIDE REQUIRED FLOOR RATING.

ELECTRICAL DEMOLITION LEGEND

ETR	EXISTING TO REMAIN
RR	REMOVE AND RELOCATE
RC	REMOVE COMPLETELY BACK TO SOURCE
RN	REMOVE AND REPLACE WITH NEW DEVICE, EXISTING CONDUIT, WIRING, AND BACKBOX SHALL BE REUSED

EXISTING TO REMAIN

TO BE DEMOLISHED

FULLY SPRINKLERED BID DOCUMENTS

[illegible]