




1 FIRST FLOOR DEMOLITION PLAN - HVAC
1/8" = 1'-0"

MECHANICAL GENERAL NOTES:

1. ALL REMAINING OPENINGS IN THE WALLS OR ROOF SHALL BE PATCHED TO MATCH EXISTING CONSTRUCTION AND BE SEALED WATERTIGHT.
2. REMOVE ALL DUCTWORK INDICATED TO BE REMOVED INCLUDING ALL SUPPORTS, BRANCH DUCTS NOT SHOWN, AND ASSOCIATED CONTROLS.
3. REMOVE ALL EXISTING ABANDONED DUCTWORK, PIPING, AND CONDUIT FOUND DURING DEMOLITION.

MECHANICAL KEY NOTES:

1. REMOVE DUCT TO POINT SHOWN. CAP AND SEAL OPENING IN MAIN DUCT TO REMAIN.
2. REMOVE DUCT COIL, SUPPORTS, AND PIPING. REMOVE PIPING BACK TO MAIN, CAP AND VALVE.
3. REMOVE RADIATOR AND ASSOCIATED PIPING. REMOVE CHW AND HW UP TO FAN COIL UNIT ON 2ND FLOOR.

CONSULTANTS:		ARCHITECTS/ENGINEERS:		Drawing Title FIRST FLOOR DEMOLITION PLAN - HVAC		Project Title BUILDING 9 - SECOND FLOOR RENOVATION		Project Number 542-13-105		Office of Construction and Facilities Management Department of Veterans Affairs	
				 6587 HAMILTON AVENUE PITTSBURGH, PENNSYLVANIA 15206 PH: 412.287.7333 FAX: 412.287.7334 www.ae-works.com		Approved: Project Director		Building Number 9			
Revisions:								Location: 1400 Blackhorse Hill Road Coatesville, PA 19320		Dwg. 81 of 125	
Date								Date 05 / 12 / 14		Checked SPL	
								Drawn SPL			