



1 SECOND FLOOR DEMOLITION PLAN - HVAC  
1/8" = 1'-0"

- MECHANICAL GENERAL NOTES:**
1. ALL REMAINING OPENINGS IN THE WALLS OR ROOF SHALL BE PATCHED TO MATCH EXISTING CONSTRUCTION AND BE SEALED WATERTIGHT.
  2. REMOVE ALL DUCTWORK INDICATED TO BE REMOVED INCLUDING ALL SUPPORTS, BRANCH DUCTS NOT SHOWN, AND ASSOCIATED CONTROLS.
  3. REMOVE ALL EXISTING ABANDONED DUCTWORK, PIPING, AND CONDUIT FOUND DURING DEMOLITION.
- MECHANICAL KEY NOTES:**
- 1 REMOVE STEAM RADIATOR / FAN COIL UNIT, ANY ENCLOSURE, AND ANY REMOTE THERMOSTAT. CAP STEAM AND CONDENSATE OR HOT AND CHILLED WATER PIPING BELOW THE FLOOR.
  - 2 REMOVE WINDOW MOUNTED EXHAUST FAN AND ALL CONTROLS.
  - 3 REMOVE CEILING MOUNTED EXHAUST FAN AND ANY CONNECTED DUCTWORK.
  - 4 REMOVE WINDOW VENT.
  - 5 REMOVE DUCT MOUNTED HOT WATER REHEAT COIL, PIPING, CONTROLS, AND SUPPORTS.
  - 6 PIPING RISERS TO THE ATTIC TO REMAIN. (5" LPS, 3" CHWS, 3" CHWR)
  - 7 REMOVE FIRE DAMPER AND ASSOCIATED PNEUMATIC CONTROL DEVICES AND TUBING.

<div>Revisions:</div> <div>Date</div>		<b>CONSULTANTS:</b> <div>HOPE FURRER Associates, Inc.</div>		<b>ARCHITECTS/ENGINEERS:</b> <div>A/E works</div> <div>6587 HAMILTON AVENUE PITTSBURGH, PENNSYLVANIA 15206 PH: 412.287.7333 FAX: 412.287.7334 www.ae-works.com</div>		<div>Drawing Title</div> <div>SECOND FLOOR DEMOLITION PLAN - HVAC</div> <div>Approved: Project Director</div>	<div>Project Title</div> <div>BUILDING 9 - SECOND FLOOR RENOVATION</div> <div>Location: 1400 Blackhorse Hill Road Coatesville, PA 19320</div> <div>Date</div> <div>05 / 12 / 14</div> <div>Checked</div> <div>SPL</div> <div>Drawn</div> <div>SPL</div>	<div>Project Number</div> <div>542-13-105</div> <div>Building Number</div> <div>9</div> <div>Drawing Number</div> <div>HD102</div> <div>Dwg. 82 of 125</div>	<div>Office of Construction and Facilities Management</div> <div>Department of Veterans Affairs</div>	
---------------------------------------	--	---	--	--	--	---	---	--	---	--