



CBLH Design
7850 Freeway Circle
Cleveland, Ohio 44130

Attention: Kevin Kantz

Regarding: VAMC – Chalmers P. Wylie ACC
Build Specialty Care Center
Amendment A00004

Dear Kevin,

Please incorporate the following items as an amendment for the mentioned project.

Electrical Item

- Item 1. Drawing E7.6 Revise panelboard schedules to include spare 20A-1P circuit breakers in lieu of provisions as indicated.
- Item 2. Specification 26 24 16 (2.3) (C) Revise to “Circuit breakers shall have minimum interrupting rating as required to withstand the available fault current according to 26 05 73 OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY, but not less than:
1. 120/208 V Panelboard: 10,000 A symmetrical.
 2. 120/240 V Panelboard: 10,000 A symmetrical.
 3. 277/480 V Panelboard: 14,000 A symmetrical.”

Please contact us with any questions

Sincerely yours,

Christopher P. Campbell, PE
Fredrick, Fredrick & Heller Engineers, Inc