

 Department of

- 1. CONSTRUCTION TO BE PERFORMED IN PHASES.**
- 2. ALL SHUT-DOWNS SHALL BE COORDINATED WITH THE OWNER TO CORRECT PHASE AND TO ALLOW FOR CONTINUATION OF SERVICES IN NON-CONSTRUCTION AREAS AS REQUIRED.**
- 3. ALL SHUT-DOWNS AND CHANGE-OVERS SHALL BE PREVIOUSLY SCHEDULED AND APPROVED BY THE OWNER. MINIMIZE DOWNTIME AND DISRUPTION TO FACILITY SERVICES FOR OTHER NON-CONSTRUCTION ACTIVITIES. COORDINATE SHUT-DOWNS AND CHANGE-OVERS WITH OWNER'S C.**
- 4. ALL REMOVED FIXTURES OR EQUIPMENT AND ASSOCIATED PIPING, HANGER, INSULATION, SUPPORTS, ETC., SHALL BE REUSED OR REINSTALLED AT NEAREST SERVICES AT NEAREST ACTIVE MAINS OR BRANCH LINES AS CLOSELY AS POSSIBLE TO ELIMINATE ALL DEAD END**
- 5. COORDINATE ROUTING OF ALL PIPING WITH NEW AND EXISTING STRUCTURAL CONDITIONS AND WITH OTHER TRADES WORK, BOTH NEW AND EXISTING.**
- 6. ALL RISERS SERVING OTHER FLOORS SHALL REMAIN UNCHANGED. IF ANY PART OF A RISER OR WORK SHALL BE REROUTED AS REQUIRED TO PROVIDE CONTINUED SERVICE WITH AS LITTLE DISRUPTION AS POSSIBLE. COORDINATION OF REROUTED RISERS IN SERVICE WITH G.C. AND INSTALL ALL NEW PIPING TO BE INSTALLED IN ACCORDANCE WITH THE DISSECTION OF SERVICES. CHANGE-OVER SHALL BE IN SUCH A MANNER AS TO MINIMIZE DISRUPTION TO OTHER AREAS OF THE FACILITY.**

Data of

WA FORM 08-6231