



FLOOR PLAN:

INFECTION CONTROL RISK ASSESSMENT:

LOW/MEDIUM RISK (LEVEL II):
NO WORK SHALL COMMENCE WITHOUT PRIOR SCHEDULING AND APPROVAL FROM COTR. PROVIDE ACTIVE MEANS TO PREVENT AIRBORNE DUST FROM DISPERSING INTO THE ATMOSPHERE. WATER MIST WORK SURFACES TO CONTROL DUST WHILE CUTTING. WIPE WORK SURFACE WITH DISINFECTANT. CONTAIN CONSTRUCTION WASTE BEFORE TRANSPORT IN TIGHTLY COVERED CONTAINERS. ALL CEILING TILES REMOVED FOR CONDUIT INSTALLATION SHALL BE REPLACED AT THE END OF EVERY WORK SHIFT IN ORDER TO MAINTAIN THE SMOKE BARRIER. USE A HEPA VACUUM ON EVERY TILE BEFORE REINSTALLATION. ONLY ONE CEILING TILE CAN BE REMOVED AT A TIME FOR CABLE/CONDUIT INSTALLATION. WET MOP AND/OR VACUUM WITH HEPA FILTERED VACUUM AT THE END OF EVERY WORK SHIFT.

SHEET NOTES:

NOTES

- EXISTING FAN COIL UNIT
- EXISTING STERILE PROCESSING EQUIPMENT TO BE REMOVED BY OWNER
- REMOVE EXISTING DOOR AND CONSTRUCT WALLS
- REMOVE WINDOW EXHAUST FAN AND REPLACE WINDOW
- REMOVE AND DISPOSE OF ALL FIXED EQUIPMENT (SINKS, SHELVING, COUNTERTOPS, PARTITION WALL)

NOTE - PIPING IN ROOMS WILL NEED TO BE CUT BACK AND CAPPED AT MAIN. REPAIR WALLS TO MATCH EXISTING.

By	Revisions	Date

GENERAL NOTES:
1. SCALED DIMENSIONS & ARCHITECTURAL FEATURES MAY NOT BE CORRECT.
2. CONTRACTORS & A/E's ARE RESPONSIBLE TO FIELD VERIFY ALL DIMENSIONS WITHIN THE PROJECT AREA.

DEPARTMENT OF VETERANS AFFAIRS
MEDICAL CENTER
1055 Clermont Street
Denver, Colorado, 80220

Drawing Title 8TH FLOOR PLAN - GI LAB CURRENT LAYOUT/DEMO PLAN		Project Title GI HVAC & EQUIPMENT SITE PREP		Date 05/15/2014
Approved: Service Chief	Drawn CMG	Building Number 1	Title Block By ska	Project No. 554-14-821
Approved: Section Chief	Checked	Wing C	DRAWING No A-01 Dwg 2 Of 2	

Department of
Veterans Affairs