

Sapphire™ Multi-Therapy Infusion Pump Kit

Page 1 of 1

Tuesday, July 15, 2014
3:43 PM



[PRODUCTS + SERVICES](#) [HEALTHCARE TRENDS](#) [SUPPORT CENTER](#) [ABOUT HOSPIRA](#)

[Products + Services](#) [Infusion Pumps](#)

Sapphire™ Multi-Therapy Infusion Pump Kit

Sapphire™ Multi-Therapy Infusion Pump Kit includes multi-therapy pump, cradle, connection knob key, power supply with international adapter plugs and user manual. Reference number 17000-028-0061. Product specifications below. Click [here](#) for more product information.

Availability	In Stock
Hospira Product Numbers	
List Number	16311
Case Information	
Order Quantity	1 Unit
Case Size	1 x 1
Pump Line	Sapphire™
Pump Type	Ambulatory Infusion
Dimensions	Approx. 5.63" h x 3.78" w x 1.93" d
Weight	Approx. 14.7 oz (without battery)
Battery Life	Approx. 24 hours at 125 mL/hr
Power Requirements	100-240 V, 50-60 Hz, 0.6 A
Volume Range	1 - 9999 mL (increments of 1 mL)
Delivery Rate Accuracy	± 2.5% (subject to external conditions)
Delivery Rates	0.1 - 99.9 mL/hr with increments of 0.1 mL/hr; 100 - 999 mL/hr with increments of 1 mL/hr
System Alarms	Air In Line, Cassette Misplaced, Occlusions, Check for Occlusion, Downstream Occlusion, Upstream Occlusion, Flow Error, Insufficient Battery
Occlusion Alarm Pressure	Up to 17.4 PSI (1.2 Bar)
KVO Rate	Up to 20 mL/hr with increments of 0.1 mL/hr



