

35 FINISH LEGEND					
TYPE	MARK	FINISH ITEM	MANUFACTURER	COLOR	NOTES
PAINT	PT-1	PAINT			
	PT-2	PAINT			
	PT-3	PAINT			ACCENT COLOR IN CORRIDORS; SEE A5 INTERIOR ELEVATIONS
	PT-4	PAINT			ACCENT COLOR IN CORRIDORS; SEE A5 INTERIOR ELEVATIONS
	PT-5	PAINT			ACCENT COLOR IN CORRIDORS; SEE A5 INTERIOR ELEVATIONS
	PT-6	PAINT			ACCENT COLOR IN CORRIDORS; SEE A5 INTERIOR ELEVATIONS
FLOORS	CONC-1	SEALED CONCRETE			INTEGRALLY COLORED CONCRETE
	CONC-2	SEALED CONCRETE			ACCENT EPOXY COATED CONCRETE AT RECEPTION DESK AREAS; SEE A2.10
	MAT-1	WALK-OFF MAT			PERMANENT WALK-OFF SYSTEM
	VS-1	VINYL SHEET FLOORING			COVED BASE
WALLS	CG-1	CORNER GUARD	ACROVYN CO-8		
	CR-1	12" CRASH RAIL	ACROVYN 4000 RUBSTRIP		
	CR-2	6" CHAIR RAIL	ACROVYN 4000 RUBSTRIP		
	GWB-1	GYPSUM BOARD - 5/8"			SEE PARTITION SCHEDULE
	GWB-2	GYPSUM BOARD - 5/8" TYPE X			SEE PARTITION SCHEDULE
	GWB-3	GYPSUM BOARD - 1"			SEE PARTITION SCHEDULE
	RB-1	4" RUBBER BASE (1/8" THICK)	BURKEBASE TYPE TS		NO SEAMS EXCEPT AT INSIDE CORNERS
	TP-1	TEXTURED PANEL			
	WP-1	FIBER REINFORCED PLASTIC	KOROGARD ETS		BUTT JOINTS
	WP-2	STEEL MAGNETIC PANEL			
CEILINGS	ACT-1	2x4 ACOUSTICAL CEILING TILE	ARMSTRONG OPTIMA	WHITE	TEGULAR (FINE TEXTURE)
	ACT-2	2x5 ACOUSTICAL CEILING TILE	ARMSTRONG OPTIMA	WHITE	TEGULAR (FINE TEXTURE)
	ACT-3	2x6 ACOUSTICAL CEILING TILE	ARMSTRONG OPTIMA	WHITE	TEGULAR (FINE TEXTURE)
	GYP. BD.	GYPSUM BOARD			
	MF-1	WHISPERWAVE CLOUD	ACOUSTICAL SOLUTIONS, INC.		WWW.ACOUSTICALSOLUTIONS.COM/WHISPERWAVE-CLOUDS
CASEWORK	SS-1	SOLID SURFACE MATERIAL	SLOANE STONE DSG-81000		CORIAN TOP FOR SINK
	SS-2	SOLID SURFACE MATERIAL			RECEPTION DESKS
OTHER	AR-1	ARCHITECTURAL RESIN PANEL	3FORM		3-FORM.COM
	MTL-1	(EXTERIOR) CORRUGATED MTL PANEL - COLOR A	METAL SALES MANUFACTURING CORPORATION	RIVER TEAL	IC72 PANEL - WWW.METALSALES.US.COM; MADE IN WOODLAND, CA
	MTL-2	(EXTERIOR) CORRUGATED MTL PANEL - COLOR B	METAL SALES MANUFACTURING CORPORATION	AGED COPPER	IC72 PANEL - WWW.METALSALES.US.COM; MADE IN WOODLAND, CA
	MTL-3	(EXTERIOR) CORRUGATED MTL PANEL - COLOR C	METAL SALES MANUFACTURING CORPORATION	METALLIC SILVER (K7)	IC72 PANEL - WWW.METALSALES.US.COM; MADE IN WOODLAND, CA
	MTL-4	(EXTERIOR) FLAT METAL PANEL - COLOR C	METAL SALES MANUFACTURING CORPORATION	METALLIC SILVER (K7)	TL-17D - WWW.METALSALES.US.COM & TL-17; MADE IN WOODLAND, CA
	MTL-5	PERFORATED METAL SCREEN (EXTERIOR)		STAINLESS STEEL	1/2" MESH WELDED STAINLESS; WWW.TWPINC.COM
PLASTER	CP-1	CEMENT PLASTER - COLOR A			
	CP-2	CEMENT PLASTER - COLOR B			

TL-17 USED AS MAIN PANEL @ ENTRY. TL-17D USED FOR 1" REVEAL.
SEE LOCATION ON ELEVATIONS, SEE CALLED OUT LOCATIONS ON A3.10
AND A3.11 AND DETAIL 36/A8.11.

FINISHES NOTES

1. BASE BID FLOORING IS INTEGRALLY COLORED CONCRETE THROUGHOUT - DAVIS INTEGRAL COLOR: COCOA.

100%CONSTRUCTION DOCUMENT

FINISH SCHEDULE

Project Title MEDICAL SPECIALTIES BUILDING 648			Project Number 612-122		Office of Construction and Facilities Management
Location VA MATHER			Building Number 648		
Date 09/18/2014	Checked M.H.	Drawn HA	Drawing Number A9.41		
			Dwg. 47 of		

Department of
Veterans Affairs