

LIGHT FIXTURE SCHEDULE						
FIXTURE TYPE	DESCRIPTION	VOLTAGE	LAMP	WATTS	MANUFACTURER	NOTES
A	2'X4' LED TROFFER LENS	277 V	LED	70 W	COOPER #24EN-LD1-67-UNV-L835-CD1-U	
B	2'X4' LED TROFFER LENS - EMERGENCY POWER	277 V	LED	70 W	COOPER #24EN-LD1-67-UNV-L835-CD1-U	
C	2'X2' LED TROFFER FIXTURE	277 V	LED	26 W	COOPER #2EN-LD1-25-UNV-L835-CD-1	
D	3" LED DOWNLIGHT	277 V	LED	20 W	CALCULITE # FRAME IN KIT - C3L085N LIGHT ENGINE - C3L085DL-01 MTG2 LED 30K 8 80 TRIM KIT - C3LDL-M-CCD-P	
E	12" HIGH LED PENDANT	277 V	LED	14 W	LINDSLEY WILLOW PENDANT	
EL	JELLY JAR WALL MOUNT	120V/277V **	LED	32 W	Cooper Crouse-Hinds EVLEDBX2C701	**UNIVERSAL CONNECTION VOLTAGE TO EITHER 120V OR 277V 20A 1P
EXIT	EXIT SIGN RECESSED MOUNT	120V/277V ***	LED	5 W	REURA18R(SINGLE FACE) - REURA28R(DOUBLE FACE)	***UNIVERSAL CONNECTION VOLTAGE TO EITHER 120V OR 277V 20A 1P DUAL POWER INPUT
G	Solutube 290DS Optiview Diffuser - White Trim	N/A	NONE	0 W	Solutube International Inc	
H	CYLINDRO 650 PENDANT LAMP	277 V	LED	72 W	DELRAY	WARM WHITE 2 WRAP LED
K	GLOBE LED PENDANT LAMP	277 V*	LED	10 W	SynergyLED #LED-ALC-F3401-30 2700K WARM WHITE - 800 LUMEN	* PROVIDE UL LISTED 277 - 120V SETP DOWN XFMR WITH INTEGRAL PROTECTION AT EACH FIXTURE. 12" GLOBE
M	COOPER 22DIW LINEAR LED, WALL MOUNT	277 V	LED	37 W	Cooper Industries, Inc.	
N	WALL MOUNT LED FLOOD LIGHT	120 V	LED	20 W	Acuity Brands Lighting	

Project Title MEDICAL SPECIALTIES BUILDING 648		Project Number 612-122		Office of Construction and Facilities Management
Location VA MATHER		Building Number 648		
Date 09/18/2014	Checked M.H.	Drawn LTA	Drawing Number E-803	
Dwg. of				