

SOLICITATION VA69D-14-B-1453
AMENDMENT A00001, 23 September 2014
RFI-001

1. Will VA test the floor tile for ACM?
 - **Yes**
 2. Is this project to be done during normal working hours?
 - **Yes.**
 3. What level of Infection Control is this going to be?
 - **Type C, Low/Medium Risk Group, Class 3.**
 - **See Attached for approximate barrier location, type and duration.**
 4. Is there a basement under floor area to be cut for trench drain?
 - **No. It is crawlspace.**
 - a. How tall is the basement area under the floor to be cut?
 - **Between dirt floor to pan can be anywhere from approximately 4 to 5 feet. However, there are lots of utilities that will make actual "clearance" vary.**
 - b. Where is the access point?
 - **Access in from the tank room/basement in the center of the building.**
 5. Will the current areas of storage adjacent to the project be occupied during construction?
 - **Yes. Access will be given as/when needed and shall be requested to the COR.**
 6. Will the VA remove all materials and equipment off of the outside of the interior wall to allow construction on the frames/doors and wall or will the contractor be removing?
 - **Yes.**
 7. Will the VA be removing all items of storage inside of the construction area other than those listed on the plan documents?
 - **Yes**
 8. Does the prime contractor bring in their own construction dumpsters and where are they to be staged?
 - **Contractor will provide construction dumpster and will be located during Pre-con meeting and a close as practical to construction site.**
 9. Will the VA issue a key into the locked storage area for construction or will the prime contractor be supplying their own lock?
 - **The VA will provide construction cores/keys as needed for security**
 - a. Will the lock have to be wired into the security of the building?
 - **No**
-

10. On sheet E200 Demolition and Installation Notes, Notes #7

Note # 7 refers to installing new heat detectors but I do not see where they are shown on the new work plan. There is a circle symbol like a key with a note 6 in the middle of each room being remodel are those note 6 suppose to be note 7

- **Yes, see attached.**

11. Model numbers for the Drench Hose (EDH-1) and mixing valve (MV-1).

- **EDH-1: Bradley Model #S1944011ABC or prior approved equal**
- **MV-1: Bradley Model #S19-2000 or prior approved equal**

12. Plan sheet A201 wall type F2 and F2a are using 2" rigid and drywall only. How is this to be attached to the concrete columns?

- **Wall type F2 shall be "2 ½" steel studs @ 16" O.C. w/ 2" ridged insulation and 5/8" type X gypsum board on interior face. Extend to deck above.**
- **Wall type F2a shall remain the same.**