TOILETS
Bariatric
Patient
Staff
DENTIST OFF OFD03 120 SF / 120 SF
DENTIST OFF OFD03 120 SF / 120 SF
DENTIST OFF OFD03 120 SF / 120 SF
GENERAL TREATMENT OPERATORY DNTG1 144 SF / 120 SF
GENERAL TREATMENT OPERATORY DNTG1 145 SF / 120 SF
GENERAL TREATMENT OPERATORY DNTG1 141 SF / 120 SF
GENERAL TREATMENT OPERATORY DNTG1 145 SF / 120 SF
GENERAL TREATMENT OPERATORY DNTG1 137 SF / 120 SF
MECHANICAL MECH1 105 SF / 80 SF
FLAMABLE CABINET SRHM1 111 SF / 0 SF
EYE WASH SINK
STAFF TLT TLTU1 55 SF / 55 SF
DENTAL PROSTHETIC LABORATORY DNPL1 124 SF / 100 SF
SOILED SPD CART HOLDING LCSL1 69 SF / 70 SF
STORAGE RM SRE01 100 SF / 100 SF
INSTRUMENT PREP & STERILIZATION DNSC2 118 SF / 125 SF
CLEAN GOWN CART & INST BINS LCSL1 48 SF / 40 SF
STORAGE RM OMNI CELL SRE01 75 SF / 75 SF
X-RAY AREA DNXD1 100 SF / 100 SF
STORAGE, WHEELCHAIR SRLW1 60 SF / 60 SF
GENERAL STORAGE SRE01 131 SF / 0 SF
CART STORAGE SRE01 23 SF / 0 SF
SECURITY/INFO DESK RECP3 74 SF / 60 SF
LOBBY LOBO1 383 SF / 200 SF
OUTDOOR EXERCISE ? 154 SF / 150 SF
OUTDOOR SPACE ? 326 SF / 0 SF
TREATMENT EXERCISE AREA PTEA1 1017 SF / 425 SF
OFFICE OFA01 115 SF / 120 SF
DRESSING RM DR001 49 SF / 35 SF
PAT TLT TLTU1 58 SF / 55 SF
STORAGE RM SRCS1 80 SF / 80 SF
PM&R CLINIC SPACE OPMH1 249 SF / 0 SF
TREATMENT CLINIC OTGC1 112 SF / 120 SF
EQUIP STOR SRE01 75 SF / 75 SF
CLEAN UTLC1 66 SF / 50 SF
STAFF TLT TLTU1 69 SF / 55 SF
ELEC CLOSET 80 SF / 0 SF
SOILED UTLC1 ? SF / 50 SF
PAT TLT TLTE1 61 SF / 55 SF
DF
LOBBY/WAITING AREA LOBO1 751 SF / 200 SF
KIOSK OFA35 39 SF / 0 SF
BREAK ROOM (LACTATION) SL001 127 SF / 0 SF
EYE CARE PROVIDER OFD03 149 SF / 160 SF
CONFERENCE RM CRA01 267 SF / 250 SF
PC/MH STAFF WRCH1 65 SF / 60 SF
SOCIAL WORK WRCH1 68 SF / 60 SF
LEAD PHYSICIAN OFC01 149 SF / 120 SF
CHIEF ADMIN OFFICER OFC01 157 SF / 150 SF
CLINIC MANAGER OFC01 140 SF / 150 SF
RN MANAGER OFM01 106 SF / 120 SF
OFFICE, ADMINISTRATOR OFA02 109 SF / 120 SF
LOCKERS LR001 22 SF / 40 SF
BREAK RM SL001 132 SF / 240 SF
DIRECTOR OFA02 167 SF / 120 SF
COPY/FILE RPR01 102 SF / 0 SF
HEARING AID FAB / MOD RM HAFR1 233 SF / 200 SF
AUDIOLOGIST EXOS1 120 SF / 120 SF
AUDIOMETRIC BOOTH EXAM PEHS1 70 SF / 0 SF
AUDIOMETRIC BOOTH CONTROL PEHS1 118 SF / 200 SF
SPEECH PATHOLOGIST EXOS1 120 SF / 120 SF
WAITING AREA WRC01 247 SF / 210 SF
STAFF TLT TLTU1 71 SF / 0 SF
STAFF TLT TLTU1 71 SF / 0 SF
EXAM / TREATMENT RM TREY1 139 SF / 130 SF
VISUAL FIELDS RM EYVF1 101 SF / 100 SF
FITTING AND DISPENSING RM EYFD1 161 SF / 130 SF
WAITING AREA (DILATION) WRC01 138 SF / 120 SF
PAT TLT TLTU1 68 SF / 60 SF
STORAGE / SUPPLIES SRPS1 79 SF / 80 SF
JC JANC1 46 SF / 40 SF
DISINFECTING RM SRPS2 96 SF / 80 SF
EXAM / TREATMENT RM TREY1 133 SF / 130 SF
EXAM / TREATMENT RM TREY1 133 SF / 130 SF
TELERETINAL RM ZTELE 121 SF / 120 SF
EXAM / TREATMENT RM TREY1 199 SF / 150 SF
WAITING AREA WRC01 247 SF / 200 SF
CLEAN UCCL1 96 SF / 100 SF
SOILED USCL1 61 SF / 100 SF
STORAGE RM SRS01 96 SF / 80 SF
DIETICIAN OFFICE OFDC2 112 SF / 120 SF
PODIATRY EXAM RM EXRG3 127 SF / 120 SF
EXAM RM (PC/MH) EXRG3 120 SF / 120 SF
INTERVIEW RM OFA03 121 SF / 100 SF
EXAM RM EXRG3 115 SF / 120 SF
EXAM RM EXRG3 129 SF / 120 SF
EXAM RM EXRG3 118 SF / 120 SF
EXAM RM EXRG3 118 SF / 120 SF
PAT TLT TLTU1 55 SF / 55 SF
MEDICATION RM MEDP1 50 SF / 100 SF
EXAM RM EXRG3 118 SF / 120 SF
EXAM RM EXRG3 118 SF / 120 SF
EXAM RM EXRG3 127 SF / 120 SF
TEAMLET OFM03 147 SF / 250 SF
TEAMLET OFM03 149 SF / 250 SF
TEAMLET OFM03 126 SF / 250 SF
TEAMLET OFM03 131 SF / 250 SF
ETCHING GLASS PANELS
EXAM RM EXRG3 120 SF / 120 SF
EXAM RM EXRG3 120 SF / 120 SF
EXAM RM EXRG3 120 SF / 120 SF
MEDICATION RM MEDP1 48 SF / 100 SF
PAT TLT TLTU1 66 SF / 55 SF
EXAM RM EXRG3 120 SF / 120 SF
EXAM RM EXRG3 120 SF / 120 SF
TREATMENT RM OOHR1 161 SF / 150 SF
PATIENT LIFT
EXAM RM EXRG3 125 SF / 120 SF
GYN. WAIT TREY5 35 SF / 0 SF
PAT TLT TLTU1 49 SF / 55 SF
EXAM RM EXRG3 120 SF / 120 SF
INTERVIEW RM OFA03 111 SF / 100 SF
TELEMEDICINE RM ZTELE 122 SF / 120 SF
TELEMEDICINE RM ZTELE 122 SF / 120 SF
TELEMEDICINE RM ZTELE 127 SF / 120 SF
TEAMLET OFM03 172 SF / 250 SF
GROUP THERAPY RM OPMH1 321 SF / 300 SF
GROUP THERAPY RM OPMH1 303 SF / 300 SF
TV
STAFF TLT TLTU1 65 SF / 55 SF
STAFF TLT TLTU1 65 SF / 55 SF
TELEHEALTH COMM RM ZTELC 104 SF / 110 SF
PAT TLT (F) TLTU1 76 SF / 55 SF
AMINISTRATIVE CUBICLE OFA03 59 SF / 60 SF
GROUP THERAPY RM OPMH1 185 SF / 300 SF
ELEC CLOSET ? 100 SF / 0 SF
FAMILY TLT TLTF3 75 SF / 80 SF
PAT TLT TLTU1 63 SF / 55 SF
RECEPTION / CONTROL UNIT RECP1 140 SF / 120 SF
JC JANC1 46 SF / 40 SF
DF
COUNSELING STAFF OFDC1 124 SF / 120 SF
COUNSELING STAFF OFDC1 122 SF / 120 SF
COUNSELING STAFF OFDC1 118 SF / 120 SF
COUNSELING STAFF OFDC1 122 SF / 120 SF
COUNSELING STAFF OFDC1 122 SF / 120 SF
COUNSELING STAFF OFDC1 119 SF / 120 SF
COUNSELING STAFF OFDC1 122 SF / 120 SF
COUNSELING STAFF OFDC1 120 SF / 120 SF
COUNSELING STAFF OFDC1 120 SF / 120 SF
COUNSELING STAFF OFDC1 120 SF / 120 SF
COUNSELING STAFF OFDC1 120 SF / 120 SF
COUNSELING STAFF OFDC1 120 SF / 120 SF
COUNSELING STAFF OFDC1 120 SF / 120 SF
LOBBY/WAITING AREA LOBO1 123 SF / 0 SF
TV
LAB TLT TLTU1 62 SF / 55 SF
BREAK RM SL001 105 SF / 0 SF
HUD/VASH WORKSTATIONS OFA01 108 SF / 0 SF
UNION WORKER OFA01 105 SF / 0 SF
PAT WAIT WRC01 130 SF / 0 SF
STORAGE SRE01 105 SF / 160 SF
LAB TLT TLTU1 63 SF / 55 SF
TELECOMMUNICATIONS ROOM COMC1 132 SF / 110 SF
MECHANICAL MECH1 292 SF / 0 SF
BLOOD SPECIMEN COLLECTION LBVP1 140 SF / 120 SF
STORAGE, BULK SRS01 235 SF / 0 SF
HEAD END EQUIP ROOM ? 160 SF / 0 SF
LOADING DOCK DOCK1 558 SF / 110 SF
OPERABLE GLASS PARTITION
VENDING MACHINE BX001 98 SF / 60 SF
INTERNET CAFE CLR03 388 SF / 120 SF
CENTRAL RECEPTION RECP1 405 SF / 150 SF
MSA ORA03 28 SF / 0 SF
MSA OFA03 30 SF / 0 SF
MSA OFA03 31 SF / 0 SF
CONFERENCE RM CRA03 462 SF / 350 SF
CUSTOMER SERVICE OFA03 52 SF / 0 SF
OFFICE, SECRETARY WAITING SEQ01 109 SF / 120 SF
LEAD MSA OFA02 109 SF / 120 SF
BUSINESS OFFICE OFA02 107 SF / 120 SF
KITCHEN SL001 135 SF / 0 SF
STORAGE OFA31 58 SF / 0 SF
PATIENT OUTDOOR PLAZA ? 612 SF / 0 SF
STAFF COURTYARD ? 688 SF / 0 SF
OUTDOOR WATER FEATURE
CIRCULATION LOBO1 3504 SF / 200 SF
FAMILY TLT TLTF3 104 SF / 80 SF
FAMILY TLT TLTF3 169 SF / 80 SF
STAFF TLT TLTU1 55 SF / 55 SF
CONSULTATION RM OFDC2 106 SF / 100 SF
PRESCRIPTION RECEIVING OFA03 162 SF / 140 SF
CONSULTATION RM OFDC2 103 SF / 100 SF
REFRIGERATION / FREEZER AREA SRR01 99 SF / 93 SF
MAIL OUT PHMP2 98 SF / 100 SF
VAULT STORAGE SRE01 74 SF / 0 SF
DISPENSING PHOD2 287 SF / 300 SF
PREPACKAGING PHMP2 289 SF / 300 SF
STORAGE, CONTROLLED SUBSTANCE / SECURED DISPENSING SSS01 252 SF / 250 SF
TELEPHONE EQUIPMENT ROOM ? 97 SF / 0 SF
WORKSTATION OFA03 110 SF / 80 SF
WORKSTATION OFA03 105 SF / 80 SF
OFFICE, ADMINISTRATOR OFA02 102 SF / 120 SF
OFFICE, SERVICE ORGANIZATION (SHARED) OFA02 102 SF / 120 SF
MAIN ELEC ROOM ? 192 SF / 0 SF
ASSOCIATE CHIEF OFA02 109 SF / 120 SF
IV RM EXRG4 67 SF / 0 SF
ANTE RM EXRG4 40 SF / 0 SF
OFFICE, CHIEF OFA02 110 SF / 120 SF
BREAKRE SL001 79 SF / 0 SF
CHILDREN AREA LOBO1 200 SF / 120 SF
LOBBY/WAITING AREA LOBO1 780 SF / 0 SF
30'-0"
32'-0"
23'-0"
15'-0"