



420 Rail Street  
Negaunee, MI 49866  
906-475-6616  
WWW.NDW.US

Response to Bidder Questions  
October 30, 2014

1. Will an inspection report be furnished for materials to be removed from site in efforts to identify asbestos containing material? Section 02 82 13.13 indicates removal of 500lnft of pipe insulation with nothing noted for VCT or mastic.

Contractor will be responsible for removal of 500 lineal feet of asbestos containing pipe insulation. No asbestos containing VCT or mastic has been identified in the area of this project.

2. Drawing Q000 indicates VA to furnish and install relocated radiology equipment in rooms 2242, 2261, and 2263. Specification section 11 77 00 3.1 indicates contractor to remove and reinstall equipment as indicated in drawings and specification. With specifications superseding drawings please clarify who is responsible for cost to relocate radiology equipment and provide new equipment. Also drawing AD100 keynote 5 indicates rm 2227 radiology equipment to be relocated to phase 1 rm 2261 upon completion of phase 1. Drawing Q000 does not call out this equipment as relocated . Please clarify.

Equipment in 2242 is new equipment that will be provided and installed by the VA. Equipment noted in Specification Section 11 77 00 is to be relocated and reinstalled per that spec section and the notes on AD100. The notations on Q000 are corrected in addendum 3.