



420 Rail Street
Negaunee, MI 49866
906-475-6616
WWW.NDW.US

Response to Bidder Questions
November 3, 2014

1. The Plans do not indicate the number of data outlets per data location.

See Addendum 4, sheet E002 for clarification quantity of data outlets per location.

2. Panel LS2C the panel schedule indicates a 100 amp rated panel and the panel riser diagram indicates a 225 amp rated panel.

Panel is 100A. This will be reflected in Addendum 4, sheet EY504.

3. The panel schedules do not indicate whether the panels are to be main lug or main circuit breaker, surface or flush mounted.

Panel "X-RAY" = Main Lug Only, Surface mount

Panel "CR2C" = Main Lug Only, Surface mount

Panel "PACS" = Main Lug Only, Flush mount

Panel "LS2C" = Main Lug Only, Surface mount

Panel "E2A" = Main Lug Only, Surface mount

Panel "CR2B" = Main Lug Only, Surface mount

This will be reflected in Addendum 4, sheet EY506.