

## **STATEMENT OF WORK**

Rev. 1

11/05/14

534-15-1-5034-0045

### **A. GENERAL INFORMATION**

1. **TITLE OF PROJECT:** Replace Temporary Pure Water Tanks With New Equipment
2. **SCOPE OF WORK:** The contractor shall provide all resources necessary to perform the work specified, to include replacement of water softener tank and carbon filter tank, including all labor and parts, optional prefilter and inserts as specified.
3. All work to be performed at the Ralph H. Johnson VA Medical Center (RHJVAMC).
4. **BACKGROUND:** Pure water tanks must be replaced.
5. **PERFORMANCE PERIOD:** The contractor shall complete the work required under this Statement of Work (SOW) within 30 days after award unless otherwise directed by the Contracting Officer (CO).
6. **TYPE OF CONTRACT:** Firm-Fixed price -Contractor to perform all services IAW attached statement of work. Submitted offers must include lump sum bid for all services. See attached SOW for requirements.

### **B. GENERAL REQUIREMENTS**

These specifications are a statement of the minimum level of work and services that are to be provided under this contract. They are not intended to be, nor shall they be construed as, limiting specifications or requirements. At a minimum, the contractor shall be required to take all steps and measures which would be taken by a prudent building owner to ensure that pure water will be available as needed.

### **C. CHANGES TO STATEMENT OF WORK**

Any changes to this SOW shall be authorized and approved only through written correspondence from the CO. A copy of each change will be kept in a project folder along with all other products of the project. Costs incurred by the Contractor through the actions of the parties other than the CO shall be borne by the Contractor.

### **D. REPORTING REQUIREMENTS**

The Contractor shall obtain all necessary licenses and/or permits required to perform the work. In addition, the Contractor shall provide the COTR with a copy of any licenses and/or permits obtained.

### **E. TRAVEL**

All work is to be conducted at the RHJVAMC located at 109 Bee St, Charleston, SC 29401-5703. The Contractor is responsible for any anticipated travel and per diem.

#### **F. GOVERNMENT RESPONSIBILITIES**

The VA shall grant the Contractor access permission to all areas of the RHJVAMC necessary to provide the services required under this contract.

#### **G. CONTRACTOR EXPERIENCE REQUIREMENTS**

The Contractor shall be a licensed provider of technical and mechanical services contractor for installation and testing of water softener and water filtration equipment. The Contractor shall provide trained supervisory personnel, and trained technicians experienced in installation and service of water softener/filtration and associated equipment.

#### **H. CONFIDENTIALITY AND NON-DISCLOSURE**

It is agreed that:

1. The preliminary and final deliverables, and all associated working papers, application source code, and other material deemed relevant by VA which have been generated by the contractor in the performance of this task order, are the exclusive property of the U.S. Government and shall be submitted to the CO at the conclusion of the task order.
2. The CO will be the sole authorized official to release, verbally or in writing, any data, draft deliverables, final deliverables, or any other written or printed materials pertaining to this task order. No information shall be released by the contractor. Any request for information relating to this task order, presented to the contractor, shall be submitted to the CO for response.
3. Press releases, marketing material, or any other printed or electronic documentation related to this project, shall not be publicized without the written approval of the CO.

#### **I. CONTRACTOR PERSONNEL SECURITY REQUIREMENTS**

N/A

SPECIFIED WORK

Repairs to RO Pre-Treatment System			
Item	Qty	Description	Total Price
1	1	New Softener System: 14" x 65" FRP tank with 3 cu ft softener media, Fleck 2750 control valve- 7 day timer initiated, 115V; <i>pricing with re-use of existing brine tank</i>	
2	1	New Tank Assembly and Media- for Carbon Filter: includes 16" X 65" tank shell and riser assembly, 4 cu ft carbon and gravel base; <i>pricing with reuse of existing 2750 control valve.</i>	
3	1	Installation Estimate: labor, travel (same visit as system PM during normal PWS service hours), and plumbing materials for replacement of damaged components, restart of system.	
		Subtotal:	
		Add system pre-filter	
	1	20" BB Housing Assembly: wall mount, with pressure gauge; <i>Pricing includes install on same visit for repairs- as above.</i>	
	1case	20" 5 micron BB Filter Cartridges: 5 per case	

Total Price for entire job to include parts and labor: \_\_\_\_\_