

DOOR SCHEDULE																	
DOOR NO.	FIRE RATING	To Room: Number	To Room: Name	DOOR				GLASS	DOOR FINISH	FRAME					FRAME FINISH	HDW SET	COMMENTS
				DOOR TYPE	DOOR MAT'L	OPN'G SIZE				FRAME TYPE	FRAME MAT'L	DETAIL					
						WIDTH	HEIGHT					HEAD	JAMB	SILL			
102A		GC-102A	OFFICE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	-	-	-	-	PNT	2	X
102B.1		GC-102F	OFFICE SUITE	A	WD	3' - 0"	7' - 0"	---	STN	1	HM	1/A600	2/A600	-	PNT	5	X
102C		GC-102C	OFFICE	A	WD	3' - 0"	7' - 0"	---	STN	1	HM	1/A600	2/A600	-	PNT	5	X
102D		GC-102D	OFFICE	A	WD	3' - 0"	7' - 0"	---	STN	1	HM	1/A600	2/A600	-	PNT	5	X
102E		GC-102E	OFFICE	A	WD	3' - 0"	7' - 0"	---	STN	1	HM	1/A600	2/A600	-	PNT	5	X
102F		GC-102F	OFFICE SUITE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	3	X
102H		GC-102H	OFFICE	A	WD	3' - 0"	7' - 0"	---	STN	1	HM	1/A600	2/A600	-	PNT	5	X
102I		GC-102I	OFFICE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	2	X
102K		GC-102K	OFFICE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	2	X
102K.1		GB-C10	CORRIDOR	ETR	MTL	6' - 0"	7' - 0"	---	PNT	ETR	HM	-	-	-	PNT	1	X
102K.2		GB-120K	BREAK ROOM	A	WD	3' - 0"	7' - 0"	---	STN	1	HM	1/A600	2/A600	-	PNT	6	X
102L		GC-102L	VOLUNTEER TRAINING ROOM	ETR	WD	3' - 0"	7' - 0"	ETR	STN	ETR	HM	-	-	-	PNT	1	X
108.1		GB-120A	STORAGE	ETR	MTL	3' - 8"	7' - 0"	ETR	PNT	ETR	HM	-	-	-	PNT	1	X
108A		GB-108	GL. TERMINAL	ETR	-	2' - 8"	7' - 0"	---	ETR	-	-	-	-	-	ETR	1	X
110.1		GB-120G	STERILIZATION RM. (SOILED AREA)	B	HM	3' - 8"	7' - 0"	GL-2	PNT	1	HM	1/A600	2/A600	-	PNT	11	X
111.1		GB-111	FEMALE TOILET	ETR	HM	3' - 0"	7' - 0"	---	PNT	ETR	HM	-	-	-	PNT	1	X
111.2		GB-111	FEMALE TOILET	ETR	-	3' - 0"	7' - 0"	---	ETR	-	-	-	-	-	ETR	1	X
112		GB-112	MALE TOILET	ETR	-	3' - 0"	7' - 0"	---	ETR	-	-	-	-	-	ETR	1	X
112.1		GB-112	MALE TOILET	ETR	HM	3' - 0"	7' - 0"	---	PNT	ETR	HM	-	-	-	PNT	1	X
113.1		GB-113	OFFICE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	3	X
113.2		GB-113B	OFFICE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	2	X
113.A		GB-113A	SCOPE ROOM	A	HM	3' - 6"	7' - 0"	GL-2	PNT	1	HM	1/A600	2/A600	-	PNT	10	X
113.A2		GB-113A	SCOPE ROOM	A	HM	3' - 6"	7' - 0"	GL-2	STN	1	HM	1/A600	2/A600	-	PNT	9	X
113B		GB-113B	OFFICE	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	3	X
114		GC-C1	CORRIDOR	ETR	-	3' - 0"	7' - 0"	---	ETR	-	-	-	-	-	ETR	1	X
115.1		GB-115	VESTIBULE	B	WD	3' - 0"	7' - 0"	GL-2	STN	1	HM	1/A600	2/A600	-	PNT	13	X
115.2		GB-115	VESTIBULE	ETR	WD	3' - 0"	7' - 0"	ETR	STN	ETR	HM	-	-	-	PNT	8	X
115A		GB-115A	FEMALE TOILET	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	12	X
115B		GB-115B	MALE TOILET	ETR	WD	3' - 0"	7' - 0"	---	STN	ETR	HM	-	-	-	PNT	12	X
116.1		GB-116	LOUNGE	B	WD	3' - 0"	7' - 0"	GL-2	STN	1	HM	1/A600	2/A600	-	PNT	13	X
116.2																	



Owner
SPD and SPS Modifications, Phase I
MARTINSBURG, WV

ADD ASK1