



CONTROL SCHEDULE				
POINT NUMBER	NORTHING	EASTING	ELEVATION	SET CONTROL
506	5700.47	5236.67	1545.16	SET PK NAIL
508	5288.48	5411.84	1561.11	SET SPIKE
509	5380.26	5253.19	1543.36	SET PK NAIL
511	4978.92	5658.04	1567.81	SET SPIKE
515	5108.75	5505.97	1563.9	SET SPIKE

SEE SHEET B-1.2

LEGEND

- AIR CONDITIONER
- CATCH BASIN
- CULVERT
- ELECTRIC BOX
- GRAVE SECTION MARKER
- SPRINKLER HEAD
- GATE VALVE
- CLEAN OUT
- GUARD POST
- HYDRANT
- HANDHOLE
- LIGHT POLE
- MANHOLE
- IRRIGATION CONTROL
- POWER POLE
- SIGN
- SOIL BORING
- TELEPHONE BOX
- ELECTRIC METER
- ROOF DRAIN
- BENCH
- CONTROL POINT
- GRAVE SECTION MONUMENT
- FENCE
- GAS MAIN
- OVERHEAD WIRES
- STORM SEWER
- UNDERGROUND ELECTRIC
- UNDERGROUND TELEPHONE
- WATER MAIN

TREE LEGEND

- CONIFEROUS
- 2" CEDAR
- 4" DECIDUOUS
- 6" MAPLE
- 8" OAK
- 10" PINE

SECTION 21

SEE SHEET B-1.4

BID DOCUMENTS 7/1/2011

Revisions	Date



Anderson Engineering of Minnesota, LLC
13605 1st AVENUE NORTH, SUITE 100, PLYMOUTH, MN 55441
TEL (763) 412-4000 FAX (763) 412-4090
www.ae-mn.com



NATIONAL
CEMETERY
ADMINISTRATION

Drawing Title EXISTING CONDITIONS MAP - CENTRAL	Project Title REPLACE ADMINISTRATION AND MAINTENANCE BUILDING AND SITE IMPROVEMENTS	Date 7-1-2011
Approved: Director, Office of Construction Management	Building Number Checked GRJ Drawn DD	Project No. 906CM3009
Approved: Director, Project Management Service	Location EAGLE POINT NATIONAL CEMETERY 2763 RILEY ROAD EAGLE POINT, OR 97524	DRAWING NO. B-1.3 Dwg. 7 Df. 166