



1010 Kings Highway South
Building Two – 2nd Floor
Cherry Hill, NJ 08034

Phone: 856-429-4000
Fax: 856-429-5002
E-mail: office@miller-remick.com

Request for Information

Contractor RFI No.: 1

Request Date: 12/18/14

Contractor/Supplier: Johnson Controls

M-R RFI Log No.: 10

Response Date: 00/00/14

VA Project No.: 528-13-C-0179

M-R Project No.: 3-0499-0046

Project Name: Renovate 6B Ward Syracuse VAMC

RFI: (Attachments Yes No)

(Q) The specified room pressure monitors or equals are not manufactured to operate BACNET over IP. They are manufactured as BACNET mstp devices only. The current devices frequently used at the VA are BACNET mstp devices.

Please provide an alternate recommendation or clarification on the requirement.

Thank You,
Todd Mancuso
Branch Installation Manager
Johnson Controls, Inc.
Rochester & Syracuse, NY

(A) Where an HVAC device is not available with BACnet/IP communication, provide a BACnet/IP to BACnet/MSTP converter located adjacent to the device with excess Ethernet cable to support direct IP connection in the future.

Michael Arnold- VA Energy Engineer