

UPGRADE DIALYSIS SUITE FINISHES

COR: JON BASSIGNANI

BUILDING 100 - VA PALO ALTO

PROJECT NO: 640-15-136

DEC. 5th, 2014

TASK SPREADSHEET

Room Number	Room Name	Misc. / See SOW for Details and Additional Notes	Patch and Paint	Doors / Hardware	Casework	Lights	Floor	Base	Ceiling Tiles and Grid	Diffusers	Patient Curtains	Corner Guards	Data	Electrical
B2-100	Office	Ground diffuser to ceiling	Y	Y	N	Y	N	N	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches
B2-101	Conference	TV wall mount installation, new sink, eyewash	Y	Y	Y	Y	Heat welded sheet rubber flooring with integral base, match color to existing	Integral rubber covered base	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches
B2-102C	Med Room	Install Porcelain Wall Mounted Sink 19x16x9	Y	N	N	N	N	N	N	N	N	N	N	N
B2-102D	Fellows	N	N	N	N	N	N	N	N	N	N	N	Install 2 new data drops and activate	N
B2-105	Exam	Install Porcelain Wall Mounted Sink 19x16x9	Y	Y	N	Y	Heat welded sheet rubber flooring with integral base, match color to existing	Integral rubber covered base	2'x2' ACT	Y	Y	N	Replace receptacles	Replace receptacles / switches
B2-109	Staff Lounge	Magazine rack and repairing walls	Y	Y	Y	Y	Rubber tile	Rubber Base	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches
B2-128	Soiled Utility	Install new eyewash outside /inside room / new soiled sink with peddles match	Y	Y	Y / S.S. 8'	Y	Heat welded sheet rubber flooring with integral base, match color to existing	Integral rubber covered base	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches / New GFCI receptacle @ Casework
B2-129	Ante Room	Floor diffuser replace and sink along with access panel	Y	Y	N	Y	N	N	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches
B2-129A	Isol Room	Toilet and Sink replacement	Y	N	N	N	N	N	N	Y	Y	N	N	N
B2-130	Storage	Remove electrical raceway and replace with new wall circuits	Y	Y	N	Y	Heat welded sheet rubber flooring with integral base, match color to existing	Integral rubber covered base	2'x2' ACT	Y	N	Y	Replace receptacles and install new data ports	Replace receptacles / switches/ Install 3 new normal power electrical outlets
B2-131	Tech	N	Y	Y	N	Y	N	Integral rubber covered base	2'x2' ACT	Y	N	N	Replace receptacles/ Repair and replace data outlet	Replace receptacles / switches
B2-132	HAC	Mop Sink Replace and HAC Accessories	Y	Y	Y	Y	Porcelain Tile	Porcelain Tile	2'x2' ACT	Y	N	N	Install new receptacle	Replace receptacles / switches / New GFCI's
B2-134	Reuse	Utilities Cut and Cap Work / Correct Work Station and Provide access panels and counter tops / New sink and eye wash @ casework/ R.O. system work required/ See SOW	Y	Y	Y / 10' S.S.	Y	Adjust flooring same material to meet new casework	Integral covered base	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches / x2 New GFCI receptacle @ Casework
B2-135	Disinfection	Adjustable Shelving	Y	Y	Y	Y	Epoxy Flooring	Integral covered base	2'x2' ACT	Y	N	N	Install new data drop and replace all receptacles	Replace receptacles / switches
Room Number	Room Name	Misc.	Patch and Paint	Doors / Hardware	Casework	Lights	Floor	Base	Ceiling Tiles and Grid	Diffusers	Patient Curtains	Corner Guards	Data	Electrical
B2-138	Tech	New utility chase, extend utility soffit to ground. New corian counterop same as lobby setup. Access panels required and break away corian top. See SOW	Y	Y	Yes / Shelving	Y	Heat welded sheet rubber flooring with integral base, match color to existing	Integral rubber covered base	2'x2' ACT	Y	N	N	Install new data drop and replace all receptacles	Replace receptacles / switches / Install 6 new dedicated GFCI circuits and receptacles
B2-139	Storage	Adjustable Shelving	Y	Y	Y	Y	Heat welded sheet rubber flooring with integral base, match color to existing	Integral rubber covered base	2'x2' ACT	Y	N	N	Replace receptacles	Replace receptacles / switches
B2-150	Water Treatment Room	Demo and correct curb with bump. Install new R.O. drain piping for three stations and install new 12x12x8 S.S. standing sink. Demo all existing casework and stub out utility wall.	Y	Y	Y	N	Epoxy flooring - Correct all locations required	Integral covered base	N	N	N	N	N	New GFCI receptacle @ Casework