

Addendum #02 (AD#02)

Date:	1/20/2015
Project	VAWLA MH 2269066

Executive Summary

This Addendum is being issued for clarification of Contract Bid Requirements and the information being provided shall become part of the Bid Documents provided by the VA.

Drawings, Details and Note Provided as part of this Addendum.

Item	ITEM #	Sheet Name	Description of Change
1. CLARIFICATION OF SPECS	1		The Tower Roof specifications may indicate 263 and 289 surfacting materials. These are only to be used on trafficable systems such as on the podium deck.
2. CLARIFICATION OF SPECS	2		The Plans or Specs may indicate the need for additional smell required in roofing material. This is not necessary and cost should not be added for this.
3. CLARIFICATION OF SPECS	3		The insulation spec calls for 1 1/2" min. thickness with 1/4" taper. The insulation should be 1 1/2" min. thickness with 1/16" tapered insulation to avoid existing changing curb heights.
4. CLARIFICATION OF DRAWINGS	4		It may have inadvertantly been mentioned that there was to be no insulation scope on the tower roof. This is incorrect information. Per plans tower roof is to receive new insulation and tapered insulation. Also see item 3 on this addendum for clarification on thickness and slope.
5. CLARIFICATION OF DRAWINGS	5		Bids shall include work on 2 existing roof drains not shown on the podium roof drawings to receive same scope as other drains.
6. CLARIFICATION OF AMENDMENT	6		It may have been interpreted from addendum 1 that the light weight insulating concrete on the roof is required to be removed. This is not the intent.