



[Home](#) / [Live Sound](#) / [Speakers](#) / [Commercial/70V Speakers](#) / [Ceiling-Mount Speakers](#) /

JBL 8138 8" 6-Watt 70-Volt In-Ceiling Speaker for Pre-Installed Backcans



[View all JBL products »](#)

JBL 8138 8" 6-Watt 70-Volt In-Ceiling Speaker for Pre-Installed Backcans



Share 0

SKU: 8138

\$50.00

Qty:

Add to Cart

\$ Request a Quote

In Stock

Questions? We're here to help.

(800) 433-2105

[Email us](#)

Overview

❗ Priced as each, but sold only in multiples of 4.

The 8138 is an 8" ceiling speaker designed for use with a pre-installed in-ceiling backcans, resulting in high-fidelity performance at a cost-effective price point. The 8138 is ideal for a wide variety of commercial sound applications from restaurant and retail to professional offices and reception areas.

Features

- Stylish, contemporary appearance enhances any decor.
- Clear sound from an 8 inch dual-cone full-range driver.
- Very high sensitivity of 97 dB for maximum sound levels using minimum amplifier power.
- 6W transformer for use on 70V/100V distributed speaker lines
- Installs to in-ceiling backboxes having 4 mounting points on an 11.25" (286 mm) diameter mounting circle.
- For use with MTC-81BB8 backcan and MTC-81TB8 tile bridge or standard backcans.

Specifications

- Component: 200 mm (8 in) Full-Range, Dual-cone
- Frequency Range (-10 dB): 95 Hz - 18 kHz
- Coverage (2 kHz): 90° conical
- Sensitivity (2.83V@ 1m): 97 dB (1 kHz - 8 kHz)

We also recommend:



Crown
135MA
Commercial
Mixer/Amplif
35 Watts at
70/100V
\$179.00

**Add to
Cart**

Usually
Ships from
Stock



West Penn
225 16 GA
Installation
Speaker
Wire, Gray
(1,000 ft)
\$205.95

**Add to
Cart**

- Driver Power Capacity: 40W (160W peak), 2 hrs
25W (100W peak), 100 hrs
- 70V/100V Transformer Taps: 6W, 3W, 1.5W, (0.75W at 70V only)
- Termination: Bare Wire
- Magnet: 10 ounces (283 g)
- Safety Agency: Transformer is UL registered per UL1876
- Installation: Full assembly consists of 8138 speaker plus MTC-81BB8 backbox and MTC-81TB8 tile bridge. Four screw holes at industry standard 286 mm (11.25 in) mounting circle.
- Dimensions (Diameter x Depth): 327 mm (12.9") diameter
baffle x 84 mm (3.3") depth from back of baffle.
Overall depth: 99 mm (3.9")
- Mounting Points: 4 points on 286 mm (11.25 in)
dia. mounting circle
- Ceiling Cutout Dimension: 300 mm (11.75") with tile bridge and backbox. 228 mm (9.0")
diameter as stand alone.
- Net Weight: 1.4 kg (3.0 lb)
- Included Accessories: Integral grille, 4 pcs M4 x 40 mm tapping screws
- Optional Accessories: MTC-81BB8 backcan, MTC-81TB8 tile bridge

Usually
Ships from
Stock



JBL 8128
8" 6-Watt
70-Volt In-
Ceiling
Speaker
\$47.00

Add to
Cart

Usually
Ships from
Stock



JBL
CONTROL
26-DT 6.5"
2-Way In-
Ceiling
Speaker
with
Transformer
for Pre-
Installed
Backcans
\$100.00

Add to
Cart

Usually
Ships from
Stock



JBL MTC-
81BB8 Pre-
Install In-
Ceiling
Backcan for
8138
\$34.00

Add to
Cart

Usually
Ships from
Stock



JBL MTC-
81TB8 Pre-
Install In-
Ceiling Tile
Bridge for
8138
\$18.00

Add to
Cart

Usually
Ships from
Stock

Ratings & Reviews

Write a Review

©2015 JPK Corporation dba ProAudio.com and Crouse-Kimzey Company. All rights reserved.