

CONTRACTOR SHALL REMOVE ALL EXISTING LIGHT FIXTURES SHOWN ON DRAWINGS IN DEMOLITION (NON-SHADE) AREAS, UNLESS OTHERWISE NOTED. ALL CIRCUIT WIRING CONNECTED TO LIGHT FIXTURES BEING REMOVED SHALL BE DISCONNECTED, CAPPED, AND LEFT IN SAFE CONDITION FOR LATER RECONNECTION TO RELOCATED AND/OR NEW FIXTURES IN NEW CONSTRUCTION PHASE. THE REMAINING ENDS OF REMOVED WIRING SHALL BE TERMINATED AND CAPPED WITHIN THE NEAREST J-BOX/EQUIPMENT ENCLOSURE. WHERE EXISTING LIGHT FIXTURES ARE BEING REUSED: REMOVE FIXTURES AND CLEAN AS REQUIRED, RELAMP AND REINSTALL IN NEW LOCATIONS AS INDICATED ON THE DRAWINGS.

1. LIGHT FIXTURES MARKED 'E' ARE EXISTING AND SHALL BE RELOCATED OR DEMOLISHED AS NOTED. LIGHT FIXTURES TO BE RELOCATED SHALL BE PROTECTED FROM DAMAGE AND STORED FOR LATER REINSTALLATION. REFER TO ELECTRICAL SYMBOL LEGEND, SHEET G1001.

- ① DEMOLISH EXISTING FLUORESCENT FIXTURES SHOWN ON DRAWING. REMOVE EXISTING EXIT LIGHTS AND STORE FOR LATER REINSTALLATION. CIRCUIT WIRING SHALL REMAIN AND BE RECONNECTED TO NEW LIGHT FIXTURE. REFER TO NEW WORK LIGHTNING PLANT SHEETS.
- ② REMOVE EXISTING LIGHT FIXTURES IN THIS SPACE, BUT ONLY IN AREAS WHERE CEILING IS TO BE TAKEN DOWN AND RELOCATED TO FACILITATE HVAC DUCT WORK. COORDINATE THIS WORK AND REINSTALLATION OF FIXTURES WITH HVAC CONTRACTOR.



SCALE: 1/16" = 1'-0"