

AREAS SAMPLED JANUARY 2003:  
NON-ASBESTOS-CONTAINING MATERIALS

- 12FT04 12"x12" White w/Gray Floor Tile and Mastic  
WC01 Window Caulking  
PC01 Plaster Ceiling  
PW01 Plaster Wall  
CB01 Black Covebase Mastic  
CB03 Taupe Covebase Mastic  
CB04 Brown Covebase Mastic  
CB06 Dark Gray Covebase Mastic  
2SC04 2"x2' Wormhole/Pinhole (small) Ceiling Panel  
PP01 Pink Pipe Putty (Firestop)  
PP02 Green Pipe Putty (Firestop)  
BC01 Black Mastic on Cork Insulation  
GW01 Drywall Joint Compound


SAMPLE IDENTIFICATION

09-WC01-105-03 NON-ASBESTOS-CONTAINING MATERIAL

DESCRIPTION	LOCATIONS
FT01-12"x12" TAN W/ BROWN FLECK FT/ BLACK MASTIC	EVERYWHERE

Homogenous Area	Sample Number	Sample Description	Locations	Results
FT01	22-2-3-01	Tan with Brown Fleck FT / Black Mastic	Hall o/s RM 5104	3% CH-tile, 3% CH-mastic
	22-2-3-02		Hall o/s RM 5093	3% CH-tile, 3% CH-mastic
	22-2-3-03		RM 5013, Southeast corner	3% CH-tile, 3% CH-mastic
	22-2-3-04		RM 5013, Northeast corner	3% CH-tile, 3% CH-mastic
	22-2-3-05		Rm 5057, Behind Door	3% CH-mastic
	22-2-3-06		Hall o/s RM 5061A	2% CH-tile, 3% CH-mastic
	22-2-3-07		Hall o/s RM 5021	2% CH-tile, 3% CH-mastic

BULK SAMPLE LOCATIONS  
BUILDING 2 - 5TH FLOOR  
VA MEDICAL CENTER  
SALISBURY, NORTH CAROLINA



**HGS ENGINEERING, INC.**

1121 NOBLE STREET  
ANNISTON, ALABAMA 36201