



**SUMMARY OF SUPPLEMENTAL WATERPROOFING:**

- ALL WALLS OF DEEPEST PITS ON NORTH AND SOUTH SIDES AND CONVEYOR INCLINES:  
A. 2 COATS OF SIKATOP SEAL 107 FROM ELEV. 760'-6" TO 764'-7".
- BASE OF WALL AT H LINE AT ELEV. 764'-7", ALONG BASE OF NORTH AND SOUTH DEEP PITS WHERE WALL AND FLOOR MEET AT ELEV. 760'-6", AND AT WALL AND FLOOR CRACKS AT NORTH AND SOUTH DEEP PITS AND CHIP BUNKER:  
A. INJECTION WITH SIKADUR 35 THEN SIKADUR 31 GROUT OVER INJECTION LOCATIONS.  
B. COAT ENTIRE INTERIOR SURFACES OF THE BOX OUT WITH 2 COATS OF SIKATOP SEAL 107 FOLLOWED BY MIN. 1 COAT OF XYPER.
- HYDRAULIC BOX OUTS AT FOUR JOINTS:  
A. INJECTION WITH SIKADUR 35 THEN SIKADUR 31 GROUT OVER INJECTION LOCATIONS.  
B. COAT ENTIRE INTERIOR SURFACES OF THE BOX OUT WITH 2 COATS OF SIKATOP SEAL 107 FOLLOWED BY MIN. 1 COAT OF XYPER.

**NOTES:**

- SEE WELLONS DWG. NO. 10018-AB22A FOR EMBEDMENT DETAILS AT THESE LOCATIONS.
- SEE WELLONS DWG. NO. 10018-A147D FOR ASH DUMPSTER PAD EMBEDMENT DETAILS.

**FOUNDATION PLAN - BOILER AND FUEL STORAGE BUILDING**  
SCALE: 1/8" = 1'-0"  
EP# INDICATES EMBED PLATE (SEE DETAILS ON DWG. SB111)

**FOR CONSTRUCTION**  
**NEW CONSTRUCTION FULLY SPRINKLERED**

<b>DESIGN/BUILD CONTRACTOR:</b> <b>THE WHITING-TURNER CONTRACTING COMPANY</b> 300 E. JOPPA ROAD, SUITE 800 BALTIMORE, MARYLAND 21286 VA CONTRACT NUMBER : VA701-RA-0063 VA PROJECT NUMBER : 101-09-067		<b>ARCHITECT/ENGINEERS:</b> <b>MOHLIN &amp; COMPANY</b> CONSULTING ENGINEERS 146 Main Street, Suite 300 Saco, Maine 04072 (207) 283-9151		<b>Drawing Title</b> <b>BOILER AND FUEL STORAGE BUILDING</b> <b>FOUNDATION PLAN</b>  <b>Approved Project Director:</b> RON EISENBERG, PROJECT EXECUTIVE THE WHITING-TURNER CONTRACTING COMPANY 300 E. JOPPA ROAD, SUITE 800 BALTIMORE, MARYLAND 21286		<b>Project Title</b> <b>VAMC - BIOMASS</b> <b>COGENERATION ENERGY CENTER</b> <b>CANANDAIGUA, NEW YORK</b>  <b>Location</b> <b>VAMC - CANANDAIGUA, NY</b>  <b>Date</b> 05/24/18 <b>Checked</b> - <b>Drawn</b> DSF		<b>WT Project Number</b> <b>12855</b> <b>Building Number</b> <b>012</b> <b>Drawing Number</b> <b>SB100</b> Dwg. 1 of 12			
---	--	---	--	---	--	---	--	---	--	--	--