1.0 BASE BID SCOPE OF WORK

A. Narrative of Base Bid Scope of Work for Primary Electrical Radial Replacement Phase 5:

**OVERALL PROJECT SCOPE, COMPLETE BID PACKAGE:** The intent of VA Project 660-15-102 is to provide additions and modifications the 15kv redundant loop distribution system at the Wahlen Campus. The project will complete Segment 12 with S&C Switches and Conductors up to and including Switches C14 and D14, enabling 15kV Redundant Loop power to be extended at a later date to the existing Parking Structure Building B.48 and the new Specialty Services Clinics Building B.51 from Switches C14 and D14. The Project will also complete the Inner Redundant Loop by installing the completion of Segments 7C, 7B, 7A, and 7 in their entirety. The installation of duct-bank and manhole infrastructure for the West Outer Redundant Loop will continue with the installation of duct-banks & manholes for Segment 8.

The Scope of the above **Base Bid Package** may, at the Government's discretion, be reduced by the following **DEDUCTIVE** Alternates:

1. **Deductive Alternate-1: "Delete Segment 8"** All work detailed on the Construction Documents related to the installation of the Duct-Bank starting at existing Switches C09 and D09 and connecting to and including Manholes C07 and D07 shall be deducted in their entirety.

**Deduct Alternate 1**: $_____

2. **Deductive Alternate-2: "Delete Segment 7 Conductors"**

   All 15kV conductors and terminations in Segment 7 shall be deducted in their entirety.

**Deduct Alternate 2**: $_____

3. **Deductive Alternate-3: "Delete Segment 7A Conductors"**

   All 15kV conductors and terminations in Segment 7A shall be deducted in their entirety.

**Deduct Alternate 3**: $_____

4. **Deductive Alternate-4: "Delete Segment 7 Duct-Bank"**

   All excavation, installation and materials for the Segment 7 Duct-Bank shall be deducted in their entirety.

**Deduct Alternate 4**: $_____

5. **Deductive Alternate-5: "Delete Segment 7A Duct-Bank & Man-Holes"**

   All excavation, installation and materials for the Segment 7A Duct-Bank and Manholes C06 & D06 shall be deducted in their entirety.

**Deduct Alternate 5**: $_____

- - - E N D - - -