

9/23/2014 9:35:20 AM

one-eighth inch = one foot

one-quarter inch = one foot


one-half inch = one foot

three-eighths inch = one foot

one-half inch = one foot

one and one-half inches = one foot

three inches = one foot



GENERAL NOTES

- THIS SHEET SHOWS WORK FOR DEDUCTIVE ALTERNATE.
- REMOVE ACCESSORIES AND SUPPORTS ASSOCIATED WITH DEMOLISHED WORK.
- NOT EVERY PIECE OF EXISTING MECHANICAL IS SHOWN ON THIS SHEET. FOR THOSE EXISTING ITEMS NOT SHOWN, REQUEST DIRECTION FROM THE VA COR REGARDING WHETHER THEY ARE TO REMAIN OR TO BE DEMOLISHED.
- COORDINATE WORK WITH THAT OF ALL DISCIPLINES, INCLUDING BOTH THE NEW WORK AND THE EXISTING TO REMAIN. RELOCATE EXISTING TO REMAIN WORK AS REQUIRED TO ACCOMMODATE THE PHASING REQUIREMENTS AND THE NEW WORK.
- COORDINATE SHUTDOWNS AND OUTAGES WITH VA COR 2 WEEKS PRIOR TO COMMENCEMENT OF WORK.
- BEFORE COMMENCING WORK, MEASURE AND DOCUMENT THE AIR FLOW AT EVERY ROOM SUPPLY, RETURN, AND EXHAUST DEVICE. DO THIS FOR EACH DEVICE THAT WILL REMAIN AND BE REUSED. ALSO, MEASURE AIR FLOWS AT AC-5, AND AC-17, AND AT EACH RETURN AND EXHAUST FAN. DOCUMENT MEASUREMENTS IN A REPORT AND REVIEW WITH THE VA COR.
- MOST OF THE WORK SHOWN IS LOCATED IN THE INTERSTITIAL SPACE.
- BEFORE COMMENCING DEMOLITION, REQUEST FROM COR A LIST OF ITEMS TO BE SALVAGED. FOR THOSE ITEMS, REMOVE AND DELIVER TO THE VA. SEE SPECS.



KEYED NOTES

- EXISTING INFILL AREA IS SERVED FROM EXISTING ROOF MOUNTED HVAC UNIT. EXISTING REMAINS AND IS REUSED.
- EXISTING AHU-5 REMAINS AND IS REUSED.
- EXISTING AHU-17 REMAINS AND IS REUSED.

LEGEND

- EXISTING TO REMAIN
- EXISTING TO BE REMOVED

KEY PLAN - 3RD FLOOR




COMPLETION ITEM NO. _____
FULLY SPINKLERED

A1 MECHANICAL DEMOLITION PLAN- 3RD FLOOR- QUAD D-PACU-PHASES 1,2- (DEDUCTIVE ALTERNATE)

#	Revisions	Date
1	ADDENDUM #001	07-15-2014

CONSULTANTS:



ARCHITECT/ENGINEERS

THE HARTMAN + MAJEWSKI
DESIGN GROUP
Architects Engineers Interior Design
Planners Urban Designers LEED®
120 Vassar Dr SE Suite 100
Albuquerque New Mexico 87106
Tel 505 242 6880 Fax 505 242 6881



Drawing Title
DEDUCTIVE ALTERNATE- MECHANICAL DEMOLITION PLAN- 3RD FLOOR- QUAD D-PACU-PHASES 1,2

Approved: Project Director

Project Title
MICU-SICU CONSOLIDATION & PACU BUILDING 41

Location
NMVAHCS RAYMOND G. MURPHEY VAMC

Date
SEPTEMBER 26, 2014

Project Number
501-324

Building Number
BUILDING 41

Drawing Number
MD101DA

Dwg. Of

Office of
Construction
and Facilities
Management
Department of
Veterans Affairs