



LEGEND

- 1001 6" Steam Header Pressure Gauge, 0-200 psig
- 1002 6" Natural Gas Header Pressure Gauge, 0-30 psig
- 1003 6" Fuel Oil Header Pressure Gauge, 0-200 psig
- 1004 6" Feedwater Pressure Gauge, 0-300 psig
- 1005 12 Inch Clock
- 1006 Emergency Gas Shut-off Pushbutton
- 1007 Ronan 16 Pt. Annunciator with Test & Ackn. Pushbuttons & Alarm Bell
- 1008 D-02100 Circular Chart Recorder
 - Stm Header Press, 0-150 psig
 - Feedwater Temp., 0-300 deg. F
 - Outside Air Temp., 0-150 deg. F
- 1009 D-02100 Circular Chart Recorder
 - Hospital, 0-40,000 lb/hr with Integrator
 - Laundry, 0-15,000 lb/hr with Integrator
 - In-house, 0-10,000 lb/hr with Integrator
- 1010 Illum. Stop/Start Pushbuttons for Feedwater Pump #1
- 1011 Illum. Stop/Start Pushbuttons for Feedwater Pump #2
- 1012 Illum. Stop/Start Pushbuttons for Feedwater Pump #3
- 1013 Illum. Stop/Start Pushbuttons for Cond. Transfer Pump #1
- 1014 Illum. Stop/Start Pushbuttons for Cond. Transfer Pump #2
- 1015 Illum. Stop/Start Pushbuttons for Cond. Transfer Pump #2
- 1016 C-10004 CCP, with A01 Controller Card Cage
- 1017 E06 Sub-Master M/A Station for Stm Silencer Control
- 1018 E06 Vent Valve Position M/A Station
- 1019 E01 Master Controller M/A Station
- 1020 Illum. Stop/Start Pushbuttons for Fuel Oil Pump #1
- 1021 Illum. Stop/Start Pushbuttons for Fuel Oil Pump #2
- 1022 Illum. Stop/Start Pushbuttons for Fuel Oil Transf Pump #2
- 1023 Fluorescent Light & Canopy
- 1024 Annunciator Bell

Panel - 86" X 66" X 24" with lighted canopy, painted black, Textured exterior and white interior.

NOTE 1 - Provide separate isolation Section for direct connected pressure gauges. This section should not have access/drain to electrical section of panel.

DIMENSIONS IN MILLIMETERS / INCHES		DB. J/A	Hays Republic Division of Eastman Kodak Inc.	
DO NOT SCALE DRAWING		DATE	V.A. PALO ALTO	
CONFIDENTIAL INFORMATION NOT TO BE COPIED OR USED WITHOUT WRITTEN CONSENT OF HAYS REPUBLIC		CHK	MASTER PANEL ARRANGEMENT	
FINISH		R & D	SCALE	DWG. NO. B 66 860
		MF.	SHEET 1 OF 1	REV.