GENERAL DEMOLITION NOTES

1. SEE MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION DRAWINGS FOR DEMOLITION OF MECHANICAL, ELECTRICAL, PLUMBING, AND FIRE PROTECTION ITEMS AND SYSTEMS.
2. CONTRACTOR SHALL REFER TO HAZARDOUS MATERIAL ABATEMENT PLAN PRIOR TO PERFORMING ARCHITECTURAL OR MECHANICAL RENOVATION OR DEMOLITION WORK TO DETERMINE IF ASBESTOS, LEAD, PCBS, BATTERIES, OR MERCURY IN FLUORESCENT BULBS WILL BE DISTURBED. ABATEMENT CONTRACTOR SHALL REMOVE ALL HAZARDOUS MATERIALS PRIOR TO GENERAL ARCHITECTURAL AND MECHANICAL RENOVATION AND DEMOLITION WORK.
3. EXISTING SIGNAGE REMOVED FROM WALLS AND DOORS SHALL BE TURNED OVER TO COR.

SECOND FLOOR DEMOLITION KEY PLAN NOTES

1. REMOVE EXISTING PARTITIONS AS SHOWN. REPAIR FLOOR SURFACES FOR NEW FLOOR FINISH AS SCHEDULED.
2. REMOVE EXISTING DOOR AND FRAME.
3. REMOVE EXISTING FLOOR AND CEILING FINISHES THIS AREA. WHERE EXISTING SUBSTRATE IS TO REMAIN, PREPARE IT FOR NEW FINISH AS SCHEDULED. WHERE EXISTING PARTITIONS ARE TO REMAIN REPAIR THEM TO RECEIVE NEW PAINT, COATING OR TILE AS SCHEDULED.
4. REMOVE EXISTING CEILING.
5. NO CONSTRUCTION WORK IN THIS AREA.
6. REMOVE EXISTING CABINETS AND COUNTER.
7. REMOVE EXISTING PLUMBING FIXTURES.
8. REMOVE EXISTING METAL LOUVERS. SEE SHEET A201
9. REMOVE EXISTING LOUVER / FAN SEE MECHANICAL DRAWINGS.
10. PROVIDE OPENING IN EXISTING PARTITION FOR NEW DOOR AND FRAME.
11. REMOVE EXISTING FLOORING AND BASE PREPARE SURFACES FOR NEW FLOOR AND BASE.
12. REMOVE EXISTING CRASH / HANDRAIL. PREPARE WALL SURFACE FOR PAINTING.
13. DEMO EXISTING CONCRETE FLOOR TOPPING DOWN TO TOP OF EXISTING STRUCTURAL FLOOR SLAB. PREPARE CONCRETE SURFACE FOR NEW FLOOR FINISH.

DEMOLITION PLAN LEGEND

- EXISTING CONSTRUCTION TO REMAIN
- EXISTING CONSTRUCTION TO BE REMOVED
- DEMOLITION KEY NOTE
- RD EXISTING ROOF DRAIN
- RV EXISTING RIDGE VENT
- AREA OF EXISTING MEMBRANE DEMOLITION

KEY PLAN
N.T.S.

1 AD121 2ND FLOOR – DEMOLITION PLAN
1/8" = 1'-0"

0' 4' 8' 16' 24'
SCALE: 1/8"=1'-0"

PLAN NORTH

FINAL SUBMITTAL

Revisions:	Date

CONSULTANTS:

ALAN JACKSON TOLAND REGISTERED ARCHITECT No. 8509 NORTH CAROLINA ATLANTIA GEORGIA

ARCHITECT:
TOLAND MIZELL MOLNAR
435 Spence Drive
Salisbury, NC 28144
704.762.9652

Drawing Title: SECOND FLOOR DEMOLITION PLAN
Approved: Project Director

Project Title: RENOVATE / EXPAND SURGICAL SUITE
Location: FAYETTEVILLE, NC
Date: 08-22-2014 | Checked: | Drawn:

Project Number: 565-13-105
Building Number: 1
Drawing Number: AD121
Dwg. XX of

OFFICE OF CONSTRUCTION AND FACILITIES MANAGEMENT
Department of Veterans Affairs

VA FORM 08-6231

Drawing No.: D:\Projects\565-13-105 Renovate Expand Surgical Suite\Drawings\Revit Drawings\565-13-105_Demolition_Second_Floor.rvt
Plotted By: cholt
Plotted Date: Sep 10, 2014 – 10:10am