

8

7

6

5

4

3

2

1

IMPORTANT SAFETY NOTICE

RANGE SAFETY DEPENDS CHIEFLY UPON RANGE DISCIPLINE. USE OF EYE AND HEARING PROTECTION SHOULD BE MANDATORY.

BAY A

ITEM	DESCRIPTION	QTY.
1.	BULLET TRAP 9'-0" MODEL LE7500-OTR	23'-10" LFT.
2.	WIRELESS MONORAIL TARGET SYSTEM WITH ICU MODEL XWT-75'	2 EACH.
3.	ICU MOUNT / ENCLOSURE BOX (MOUNT TO EXISTING SB7 STALL PANELS)	4 EACH.
4.	BASTION SHOOTING STALLS (MIDS) BLACK W/SHELF, BLAST SHIELD AND WING BARRICADE MODEL BP10B - HANDGUN	1 EACH.
5.	BASTION SHOOTING STALLS (ENDS) BLACK W/SHELF, BLAST SHIELD AND WING BARRICADE MODEL BP3/4B - HANDGUN	1 EACH.
6.	PC MASTER CONTROL WITH TOUCH SCREEN TABLET MODEL RM10K/TABLET	1 EACH.
7.	SAFETY CEILING MODEL JG12C	379 SQFT. 3 ROWS.
8.	CEILING BAFFLE MODEL JA4C	1045 SQFT. 8 ROWS.
9.	REDIRECTIVE GUARD MODEL JR5C	95 SQFT. 2 ROWS.
10.	ACOUSTICAL FOAM (BAFFLES/SAFETY CEILING AND WALLS) MODEL AAF CLASS 1/CHARCOAL SONEX	1440 SQFT.
11.	RUNNING MAN MODEL DP65-DBL CEILING MOUNTED	1 EACH. 8 ROWS.
12.	TRAPVAC RECYCLING - 1 PHASE UNIT (5HP) MODEL 88317 (NOT SHOWN)	1 EACH.
13.	STALL SPEAKERS (MOUNT TO EXISTING SB7 STALL PANELS) MODEL EG66 (NOT SHOWN)	4 EACH.
14.	TARGET-POP UP/TURN (FRIEND/FOR) MODE MF-SIT 230V-50Hz MUX	2 EACH.
15.	COMBAT WALL (FURRING/PLYWOOD/SPR) MODEL BWN	1296 SQFT.
16.	BALLISTIC KNEE WALL (GRAN GUARD 32") MODEL LE7700	32 LFT.
17.	MASTER COMMUNICATION STATION MODEL EG-58 (10 CHANNEL)	1 EACH.
18.	FIRING LINE SECURITY SYSTEM MODEL EM30	1 EACH.
19.	SRP FLOOR TILE MODEL 43-600-030-BK	1296 SQFT.
20.	PAGING SYSTEM (NOT SHOWN) 16a. NOISE REDUCING STEREO EAR PROTECTORS MODEL EG55 16b. WALL PAGING HORN MODEL EG67 16c. PAGING KIT W/PAGING ADAPTER & AMP MODEL EG68 AND EG69	9 EACH. 1 EACH. 1 EACH.

CUSTOMER ACKNOWLEDGMENTS

NOTES:

1. ALL CONDUIT, A.C. WIRING, A.C ELECTRICAL HOOK UP, CONTROL WIRE CONDUITS, LIGHTING, LIGHTING CONTROLS OR INTERFACES BY G.C.

2. ANY ACOUSTICAL MATERIALS/TREATMENTS NOT SHOWN BY G.C.

3. ALL BRIDGING MATERIAL (IF REQUIRED) BY G.C. ALL BRIDGING MUST BE INSTALLED PRIOR TO THE ARRIVAL OF MTSI TECHNICIAN.

4. ALL CONCRETE ANCHORS AND TIES BY MTSI.

5. WALLS AND FLOORS IN TRAP AREA MUST BE FLAT WITH NO DEPRESSIONS.

6. G.C. TO VERIFY THAT MTSI'S EQUIPMENT AS SHOWN, DOES NOT CONFLICT WITH DUCTWORK, PIPES, AND OTHER TRADES.

7. UNLOADING OF ALL EQUIPMENT BY G.C.

8. REMOVAL AND INSTALLATION OF SHOOTING RANGE EQUIPMENT BY MTSI.

9. INSTALLATION OF SHOOTING RANGE EQUIPMENT BY G.C. UNDER MTSI TECHNICAL SUPERVISION.

IT IS THE CUSTOMER'S RESPONSIBILITY TO VERIFY THE STRUCTURAL INTEGRITY OF THE BUILDINGS CEILINGS AND WALLS ABILITY TO SUPPORT THE ADDITIONAL LOAD OF THE RANGE EQUIPMENT PROVIDED BY MEGGITT TRAINING SYSTEMS, INC. CUSTOMER TO VERIFY THAT MTSI EQUIPMENT AS SHOWN DOES NOT CONFLICT WITH DUCT WORK, PIPES AND/OR OTHER TRADES.

G.C./CUSTOMER TO SIGN:_____.DATE:_____

ALL DRAWINGS SPECIFICATIONS AND OTHER DESIGN DOCUMENTS PREPARED BY MEGGITT TRAINING SYSTEMS AND ITS CONSULTANTS IN CONNECTION WITH THE PROJECT ARE THE PROPERTY OF MTSI. MTSI SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RIGHTS, INCLUDING ALL COPYRIGHT, RELATED TO SAID DESIGN DOCUMENTS. THE GENERAL CONTRACTOR OR CUSTOMER SHALL NOT USE THE DESIGN DOCUMENTS ON OTHER PROJECTS WITHOUT THE SPECIFIC WRITTEN CONSENT OF MEGGITT TRAINING SYSTEMS.

G.C./CUSTOMER TO SIGN:_____.DATE:_____

MEGGITT TRAINING SYSTEMS REQUIRES THE G.C./CUSTOMER TO VERIFY THE DIMENSION AS NOTED ON THE DRAWING. MEGGITT TRAINING SYSTEMS WILL BUILD OUR EQUIPMENT TO MATCH THE DIMENSION DATA AS SHOWN. MEGGITT TRAINING SYSTEMS RESERVES THE RIGHT TO SEEK ADDITIONAL CHARGES IF THE BUILDING SPACE IS DIFFERENT FROM THE DIMENSIONAL DATA AS SHOWN ON OUR DRAWINGS.

G.C./CUSTOMER TO SIGN:_____.DATE:_____

THE EQUIPMENT BALLISTIC INTEGRITY MUST TAKE PRIORITY OVER ALL WORK WITHIN THIS SPACE. IT IS THE GENERAL CONTRACTORS RESPONSIBILITY TO COORDINATE WITH OTHER TRADES - NOT TO INTERFERE WITH RANGE EQUIPMENT LOCATIONS, SUSPENSION LOCATIONS AND OTHER RANGE EQUIPMENT LOCATIONS AND REQUIRED ACCESS AREAS.

G.C./CUSTOMER TO SIGN:_____.DATE:_____

-	-	-	-		
REVISION	DESCRIPTION	DATE	SIGN		
DRAWN BY	DWH	<div><div>MEGGITT</div><div>Meggitt Training Systems, Inc 296 Brogdon Rd, Suwanee GA 30024, USA</div></div>			
PROJECT MANAGER	-				
DATE	-				
PROPRIETARY AND CONFIDENTIAL <small>THIS DRAWING AND/OR ITS CONTENTS ARE CONFIDENTIAL AND ARE PROTECTED BY TRADE SECRETS, COPYRIGHT, AND OTHER APPLICABLE LAWS. IT IS TO BE USED ONLY AS AUTHORIZED BY MEGGITT TRAINING SYSTEMS, INC. UNAUTHORIZED USE IS ILLEGAL.</small>		PROJECT NAME INDOOR SMALL ARMS RANGE INDEX PAGE			
REV.	SIZE	CAGE CODE	SCALE	PROJECT NO.	REV
AJ	E1	087W6	AS NOTED	PROTO-1	1
THIS DOCUMENT IS CONTROLLED UNDER THE EXPORT ADMINISTRATION REGULATORY DISPOSITION CATEGORY TO U.S. LAW IS PROHIBITED.				FILENAME: GUN_RANGE_XX001	SHEET 1 OF X